





Environmental Compliance Approval No. A272301

Eastnor Landfill Site: Annual Monitoring Report (2024)

Municipality of Northern Bruce Peninsula, Ontario

Submitted to:

Municipality of Northern Bruce Peninsula 56 Lindsay Road 5 Lion's Head, ON NOH 1W0

Submitted by:

GEI Consultants Canada Ltd. 1260 2nd Avenue East, Unit #1 Owen Sound, ON N4K 2J3 519.376.1805 May 20, 2025 Project No. 2402867



andrae Welson

Andrea Nelson Project Manager

Table of Contents

| 1. | INTRODUCTION | 1 |
|---|--|-----------------------|
| 2. | SITE USAGE | 1 |
| | SITE LIFE EXPECTANCY Area A and Area B | |
| 4. 4.1. 4.2. 4.3. 4.4. | SITE DEVELOPMENT AND OPERATIONS Method of Operation Periods of Operation – Landfill Hours Waste Receiving Station Wood Waste Disposal Area | 4 4 |
| 5. 5.1. 5.2. 5.3. | LANDFILL MANAGEMENT Vector, Vermin and Wildlife Control Litter Control Site Inspections | 5 |
| 6.5. 6.6. 6.7. 6.8. 6.9. | RECYCLING AND WASTE REDUCTION Blue Box Materials | 7 8 8 8 |
| 7. | BURNING OPERATIONS | 9 |
| 8.3. | SUMMARY OF HYDROGEOLOGIC SETTING Physiographic Setting and Regional Geology Site Geology Overburden Characteristics Groundwater Flow | 10 10 |
| 9. 9.1. 9.2. | MONITORING REQUIREMENTS Monitoring Locations and Parameters Sampling Methodology | |
| 10.2. | | 13 13 14 |
| 11. | · | 15 |

| 11.1. | Leachate Generation | 15 |
|------------------------------|--|-----------|
| 11.2. | Leachate Characterization | 16 |
| 11.3. | East Property Boundary Condition (UpGradient) | 17 |
| | North Property Boundary Condition (Cross-Gradient) | |
| 11.5. | Downgradient – West of the Existing Landfill | 19 |
| 11.6. | South Property Boundary Condition (Cross-Gradient) | 20 |
| 11.7. | Water Quality Summary | 21 |
| | TRIGGER MECHANISMS AND CONTINGENCY PLAN Trigger Locations | 22 |
| | | |
| | | |
| 12.2. | Trigger Levels – Comparison and Findings | 22 |
| 12.2. 12.3. | Trigger Levels | 22 |
| 12.2. 12.3. 13. | Trigger Levels | 22 23 |

List of Tables [Embedded in Report]

| Table 4-1. Eastnor Landfill Site – Hours of Operation | 4 |
|--|----|
| Table 6-1. Northern Bruce Peninsula – Population Proportions | |
| Table 6-2. Northern Bruce Peninsula – Diversion Estimates | 6 |
| Table 6-3. Summary of Waste Diversion (Tonnes) | 9 |
| Table 9-1. Groundwater Monitoring Program | 12 |
| Table 11-1. Leachate Characterization | 16 |
| Table 11-2. East Boundary Condition – Groundwater Quality | 18 |
| Table 11-3. North Boundary Condition – Groundwater Quality | 18 |
| | |

Tables [End of Report]

- Table 1: Eastnor Landfill Volume Capacity (m³)
- Table 2: Summary of Borehole Logs and Monitoring Well Installation Details
- Table 3: Site Specific Background Concentrations & Guideline B-7-1 RUC Determination
- Table 4: Groundwater Quality Summary 2023 and 2024
- Table 5: Comparison of Groundwater Quality at the Established Trigger Locations to the Trigger Levels

Figures [End of Report]

- Figure 1: Site Location Map
- Figure 2: Site Layout
- Figure 3: Site Layout Showing Monitoring Locations
- Figure 4: Shallow Groundwater Flow & Chloride Concentration Distribution (Fall 2024)
- Figure 5: Groundwater Flow: Deeper Sand Unit (Fall 2024)

Appendices [End of Report]

- Appendix A Environmental Compliance Approval No. A272301
- Appendix B Correspondence
- Appendix C Vector & Vermin Control/Management Plan
- Appendix D Borehole Logs & Summary of Groundwater Elevations (2000 to Present)
- Appendix E Cross-Sections A-A' through E-E'
- Appendix F Historical Groundwater Quality Results (Tables & Graphs)
- Appendix G Laboratory Certificates of Analyses

AN/MN:clw

1. INTRODUCTION

The Eastnor landfill site is located approximately 25 km north of the geographic town of Wiarton within Lots 17 and 18, Concession 2WBR in the former Township of Eastnor, in the Municipality of Northern Bruce Peninsula, County of Bruce, where shown on Figure 1. The Municipality was formed in 1999 as the result of the amalgamation of the former Townships of Eastnor, Lindsay and St. Edmunds, as well as the Village of Lion's Head. Prior to 1999 each respective township was serviced by a landfill, of which the Municipality assumed ownership upon amalgamation. As a result, the Eastnor landfill is one of three landfill sites that service the Municipality and is approved to accept non-hazardous municipal wastes generated from within the geographic boundaries of the Municipality.

Operations at the Site are governed by Environmental Compliance Approval No. A272301 (ECA) which was issued on February 20, 2007, this superseded and replaced the previous approval issued on September 24, 1980. The ECA, as amended, recognizes the use of a 9.5 ha (23.5 acre) landfill area, a 1.09 ha wood waste disposal area, and a transfer station within a total Site area of 81 ha (200 acres). Further, the ECA approves a total waste disposal capacity of 625,500 m³ including waste, wood waste, and interim cover (i.e., not final cover). The approval, and its amendments, are enclosed in Appendix A.

Of the 9.5-hectare landfill area, a 3.3-hectare area with a volumetric capacity of 103,500 m³ was initially approved for landfilling. A Site Plan is provided in Figure 2. The Approval was amended on December 8, 2009, to permit the establishment of an additional 1.09 ha (2.7 acre) area for the disposal of wood waste (i.e., stumps), with an additional approved volumetric capacity of 39,000 m³. Additional amendments were issued on June 14, 2016, to outline the groundwater monitoring program requirements, and on November 1, 2017 (Notice 3) and April 15, 2019 (Notice 4), to approve the continued use and development of the remaining 6.2 ha waste fill area to the northwest of the existing landfill. More specifically, the amended ECA approves landfill operations within the Phase I area, where shown on Figure 3, which has capacity for waste and interim cover of 270,000 m³ (i.e., not including final cover). An additional capacity of 250,000 m³ remains available in the Phase II area, subject to the submission and approval of a detailed Hydrogeological Assessment and Plan of Development and Operation.

Condition 45 of the Approval requires that a monitoring report be submitted by May 31st of each year to summarize the previous year's operations, waste quantities and groundwater quality results. This monitoring report, for the year 2024, is being submitted to meet these requirements. It is noted that MECP comments pertaining to past Annual Reports are addressed herein, where applicable. MECP correspondence was not received during the reporting year. Select correspondence is included in Appendix B.

2. SITE USAGE

The Eastnor landfill is currently one of three landfill sites approved for the disposal of solid non-hazardous waste that services the Municipality of Northern Bruce Peninsula. Refuse received at the Site originates from full time and seasonal residents and local businesses of the Municipality of Northern Bruce Peninsula. Currently, there are no major industrial, commercial or institutional (IC&I) contributors of waste to the Eastnor Landfill.

According to Statistics Canada's 2021 census data, the Municipality of Northern Bruce Peninsula has a permanent population of 4,404 and a total of 5,101 dwellings, of which 2,206 are occupied by permanent residents. For the purpose of waste generation and usage of waste management services, the contributing population is more accurately estimated to be 5,610. This is based on the method adopted by Waste Diversion Ontario (WDO) where 6 seasonal households are equivalent to 1 permanent household and an average of 2.5 persons per permanent household. The former Township of Eastnor is estimated to account for approximately 45% of the population in the Municipality, which equates to approximately 2,525 persons.

As of January 2017, the entire Municipality is serviced by curbside waste and recycling collection. Residents are limited to 2 bags per week. Household waste collected through the municipally provided waste collection services are disposed of directly in the active area of the landfill. Recycling depots are available at the three landfill sites, where shown in Figure 1.

Activities that currently occur at the Eastnor landfill site include landfilling of residual waste and wood waste, burning of clean wood waste, collection of blue box materials, electronic waste, and mattresses, stockpiling of scrap metal and tires, as appropriate, and goods exchange through their reuse building. According to Site records an estimated 1,425 tonnes (metric) of waste was landfilled at the Eastnor landfill site in 2024.

3. SITE LIFE EXPECTANCY

3.1. Area A and Area B

The ECA, as amended, approves the establishment and use of an 81-ha Site consisting of a 9.5-ha landfill, a transfer station for recyclables, and a 1.09-ha (2.7 acre) wood waste disposal area, where shown on Figure 3. Approved landfilling was originally limited to a 3.3 ha licensed limit/useable area which was divided into two areas: Areas A and B (Figure 3). Based on the original plans for the Site, Area B encompassed 1.84 ha and is no longer used for waste disposal and Area A encompassed an area of 1.46 ha and was filled to capacity in 2019. It is noted that during additional investigations at the Site conducted in 2007, a 0.7 ha portion of Area B situated closest to the southern property boundary was observed to contain no waste (i.e., natural conditions), therefore refuse placement was observed to be limited to an area of approximately 1.1 ha within Area B.

In the fall of 2007, a survey of Areas A and B was completed by Gamsby and Mannerow Limited (now GEI Consultants) to determine the remaining Site capacity. The survey data was used in conjunction with the proposed final contours outlined in the PSMI PDO (May 2004). The remaining capacity for waste and daily cover within this 3.3-hectare area originally approved was determined to be approximately 29,500 m³ at that time.

Since then, the remaining capacity has been determined by subtracting the estimated volumetric capacity used derived from annual surveys of the active fill areas. Using the elevation difference between the December 2023 and December 2024 topographical surveys, a capacity of 3,625 m³ was calculated to have been used during the reporting period. Assuming 20% interim cover by volume, the amount of landfilled waste in 2024 is estimated to be 2,900 m³.

It is noted that in 2019, the remaining capacity for waste and interim cover within the initially approved area (i.e., Area A and Area B) was consumed and landfill operations were initiated within the Phase I area. As per Section 7.3 of the PDO for the Eastnor Landfill Site (December 2017), it is recommended that the following operations be completed.

- Final grading of the entire approved landfill area (i.e., Areas A and B) to the approved final contours, with a maximum 4:1 slope
- Final cover and topsoil be applied to the 0.6 ha area where no additional waste placement is expected
- Intermediate cover be applied to the remainder of the previously approved fill area

3.2. Site Life Estimate

As recognized in the ECA, as amended, additional capacity is available within the remaining 6.2-hectare landfill area (i.e., the Phase I and Phase II areas) and the 1.09-hectare wood waste disposal area. Continued landfill development will include raising the contours of the initially approved landfill area and includes for landfill development to the north along the geologic feature identified as a former beach ridge (Figure 2).

The area demarked as Phase I outlines 5.8 hectares and, in consideration of the Municipality's long-term waste management plan, is estimated to provide for an additional 40 to 45-year disposal period. This landfill development area is designed to overlap with a 2-hectare portion of the initially approved area (i.e., Area A/B) while maintaining a sufficient buffer from the south property boundary and allowing for efficient use of the approved landfilling area.

Based on the conceptual design, the Phase I capacity for waste and interim cover is calculated to be approximately 270,000 m³ (i.e., not including final cover). As shown in Table 1, at the 5-year average fill rate for the Eastnor landfill, it is estimated that the Phase I area alone would provide for greater than 65-years of capacity. However, in consideration of the Municipality's long-term waste management plan to dispose of waste from the entire Municipality at the Eastnor landfill as the other two sites reach capacity, it is projected that the Site will provide the entire Municipality with sufficient capacity for up to about 40 to 45 years of landfilling.

The Phase II area is shown to illustrate the remaining landfilling potential within the approved 9.5 ha area for future consideration and represents the remaining 3.1 hectares, which includes the 0.7 ha area not previously utilized within the initially approved limit of fill (i.e., the southern portion of Area B). This area has an additional capacity of an estimated 250,000 m³ for waste and interim cover.

4. SITE DEVELOPMENT AND OPERATIONS

As previously discussed, the ECA initially approved the use of a 3.3 ha area, within a total approved area of 9.5-hectares, for municipal waste disposal to a total capacity of 103,500 m³ (i.e., waste, interim and final cover). However, upon completion of additional hydrogeological investigations supporting the use of the additional area/capacity and the PDO the ECA, as amended, approves the use of the entire 9.5-hectare area for waste disposal. The ECA also recognizes the waste management operations that are occurring on the property including its use as (i) a waste receiving and waste transfer area, for waste diversion and recycling operations, (ii) buffer lands; and (iii) a 1.09 ha wood waste disposal site.

4.1. Method of Operation

The initially approved landfill footprint was divided into two areas: Areas A and B, as shown in Figure 3. Area B is considered closed and is no longer used for waste disposal and Area A was filled to capacity in 2019. Landfill operations have recently transitioned into the Phase I area. The landfill boundaries are periodically marked with grade stakes in the active landfilling area to ensure waste placement remains within the licensed limit and approved contours. To date, landfill operations have generally occurred from the southeast to northwest within the approved landfill footprint. Landfilling operations are currently occurring within the Phase I area, where shown in Figure 3.

The Municipality uses the area-ramp method of landfilling and uses a packer to help maximize the waste density achieved at the Site. The area-ramp method is efficient with respect to space utilization and requires less cover material than other methods. According to Condition 31 of the ECA, cover material is to be applied three times per week between May and October and once per week between November and May. Continued attention should be given to ensuring that waste at the active face is sufficiently covered in a timely fashion with an adequate amount of material.

4.2. Periods of Operation – Landfill Hours

During the reporting year, the Site was open to the public/vehicles hauling waste during the following operating hours:

Table 4-1. Eastnor Landfill Site - Hours of Operation

| Date | Monday | Tuesday | Wednesday | Thursday | Friday | Saturday | Sunday |
|------------------|--------------|---------|-----------|----------|--------|-------------|--------|
| Nov 1 – Mar 31 | 10:00 – 4:00 | Closed | Closed | Closed | Closed | Closed | Closed |
| April 1 - Oct 31 | 9:00 - 5:00 | Closed | Closed | Closed | Closed | 9:00 - 5:00 | Closed |

A sign at the access gate notes the hours of operation. A site attendant is present during operating hours. When the site is closed to the public, a locked gate across the entrance road controls access to the site. Waste may be received outside the hours of operation, by appointment and under the supervision of a trained attendant.

According to Condition 3.1.2 of the ECA, as amended, the hours of operation may be changed by the Owner at any time, subject to notification given to the District Manager, provided that the hours are correctly posted at the Site gate, and that suitable public notice is given of any change.

4.3. Waste Receiving Station

In 2009, the Municipality completed the construction of a waste receiving station at each of their landfill sites (Eastnor, Lindsay, and St. Edmunds). The station, which includes a weigh scale and collection bins for recyclables and household waste to be landfilled, is located approximately 200 m north of Area A, along the site access road, where shown in Figure 2. The collection bins are available to the public for waste drop-off and sorting. Access to the landfill area is limited to contractors and municipal employees.

4.4. Wood Waste Disposal Area

To accommodate the increase in demand for stump disposal, the Municipality obtained approval to expand its operations to permit the landfilling of uncontaminated stumps in 2009. The wood waste disposal site borders the northeastern limit of the Phase I area and extends an additional distance of approximately 80 m to the northeast, occupying an approved area of 1.09 ha which has an additional approved volumetric capacity of 39,000 m³ (Figure 3). To date, landfilling of wood waste has not occurred in this area.

It is noted that in December 2014 an application to amend the ECA to facilitate the use of the additional capacity associated with the remaining 6.2-hectare landfill area was submitted to the MECP. As part of the review process the wood waste disposal area was moved further to the north to provide a greater buffer area between the wood waste disposal footprint and the southern property boundary. A detailed assessment of the Site conditions and a discussion pertaining to the development of this area is provided in the 'Design and Operations Report – Wood Waste Disposal Site: Revised Footprint' (Revision 2: December 2017).

Prior to disposing of wood waste within this area, the Municipality should ensure that base preparations be completed in accordance with the Design and Operations Report. It is noted that the approved area has been delineated and is clearly defined and signed at the Site.

5. LANDFILL MANAGEMENT

5.1. Vector, Vermin and Wildlife Control

At the Eastnor landfill site there are several types of vermin, vector and wildlife that have been identified as requiring some form of precautionary management plan, including bees/wasps, coyotes, gulls, turkey vultures, rodents and black bears. Control can be accomplished by applying cover material after each day of refuse deposition and through good housekeeping (i.e., daily litter pick-up, regular site inspection and proper waste segregation practices). An electric fence also lines the perimeter of the waste disposal area to discourage black bears and coyotes from entering the active area of the waste disposal site. As per Condition 37 of the ECA, the electric fencing should be operated and maintained from April 1st to November 30th of each year, unless environmental conditions dictate otherwise. As per Condition 34 of the ECA, the 'Vector and Vermin Control/Management Plan' should be implemented if/when vermin, vector and/or wildlife become a nuisance. A copy of the Plan is enclosed in Appendix C.

5.2. Litter Control

Covering and compaction is the most effective tool in preventing the spread of litter via wind or scavenging. Cover material is to be applied, and compaction is to occur three times a week during the cottage season (June to October) and once a week in the off-season (November to May). Additionally, litter pick-up is recommended to help prevent fire hazards and for aesthetic reasons. As per Condition 35 of the ECA, landfill staff should conduct litter pickup each operating day from June to October, and on an as-needed basis from November through May.

If the windblown debris becomes unmanageable, the installation of mobile litter screens should be erected to further control resultant litter. Litter screens should be placed adjacent to active deposition faces. Moveable fencing in the unloading area close to the working face can be used, if necessary, to reduce the problems of litter and blowing paper. However, the moveable fencing should be kept clean to remain effective. Once a fence becomes clogged, air flow patterns change, and litter can be blown over the fence.

5.3. Site Inspections

As part of site operations, inspections of the landfill property and operations are to be conducted on a routine basis to ensure best management practices are maintained and that operations remain compliant. According to Condition 33 of the ECA, the following inspection schedule must be maintained:

- a. On each operating day, an inspection of the working face and storage areas.
- b. On a weekly basis, during the period of April 1st and November 30th, the fence voltage and the perimeter of the electric fencing must be checked.
- c. On a monthly basis, an inspection of the general condition of the site, access road, signage, fencing and gate, and the amount of available cover material.
- d. On a semi-annual basis, an inspection of the monitoring wells and the condition of the cover material.
- e. On an annual basis, a field survey of the fill area.

At this time, the site operator and/or supervisor ensure that inspection items (a), (b) and (c) are completed and inspection items (d) and (e) are completed by a qualified consultant. Changes to the Site inspection requirements and/or frequency may be made as the Municipality increases the waste receiving volumes at the Eastnor landfill in conjunction with the closing of the St. Edmunds and Lindsay landfill sites. It is recommended that the inspections document (i) the date of the inspection; (ii) the name of the operator conducting the inspection; (iii) any deficiencies noted; and (iv) when applicable, the date and steps taken to correct an identified issue.

6. RECYCLING AND WASTE REDUCTION

Currently, refuse segregation and recycling services are available at all three municipal landfill sites. Further, to encourage recycling, curbside collection of recyclables is provided to the entire Municipality.

The site attendant/supervisor is responsible for the proper segregation and recycling of refuse at the Site. Waste segregation and recycling occurs in the waste transfer and receiving area for ease of access and supervision, where shown on Figure 3. It is important that the Municipality continue to remove stockpiles of recyclable goods on a regular basis to prevent clutter and to maintain an aesthetically acceptable site. The following goods are separated from the solid waste stream and stockpiled in designated areas that are clearly labelled.

6.1. Blue Box Materials

In addition to the curbside collection of recyclable materials, the Municipality currently provides three depot locations to drop off recyclables, each associated with the municipal landfill sites, where shown on Figure 1. The Municipality accepts mixed recyclables, meaning that all accepted recyclable materials can be placed into one bin at the Municipality's Recycling Depots/Facilities. Recyclables are then transferred to a Material Recovery Facility (MRF) in Mount Forest. This single-stream recyclable processing uses separation technologies specifically designed for a mixed recyclable stream. The list of recyclable items accepted includes the following:

- glass
- steel paint cans
- aluminum cans, foil and pie pans
- paper, boxboard and cartons
- various types of plastic including, but not limited to, PETE, HDPE, LDPE, PP, and PVC

Waste Management has provided an analysis of the blue box recyclables diverted for the 2024 calendar year. It is noted that the amount of blue box recyclables diverted, specifically from the former Township of Eastnor, is not available. However, an estimate has been completed based on the percentage of the estimated population contributing recyclables from within the former Township of Eastnor. The estimated population contributing waste to each municipal landfill is as follows:

Table 6-1. Northern Bruce Peninsula – Population Proportions

| Estimated Contributing Population | | | | | | | |
|-----------------------------------|---------------|---------|--|--|--|--|--|
| Site | Total Persons | Percent | | | | | |
| Eastnor | 2,525 | 45% | | | | | |
| Lindsay | 840 | 15% | | | | | |
| St. Edmunds | 2,245 | 40% | | | | | |
| Total | 5,610 | 100% | | | | | |

Based on the estimated proportion of the municipal population in each of the former townships, the estimated recyclables diverted from each of the municipal landfills (in tonnes) for the 2024 calendar year is presented below:

Table 6-2. Northern Bruce Peninsula – Diversion Estimates

| Landfill Site | Total Diverted |
|---------------|----------------|
| Eastnor | 217.8 |
| Lindsay | 72.6 |
| St. Edmunds | 193.6 |
| Total | 484.0 |

Note: All values are presented in tonnes

The total combined amount of blue box recyclables collected during the reporting period by Waste Management for the Municipality was 484 tonnes. Based on the proportion of the Municipality's population serviced by the Eastnor landfill (i.e., 45%), an estimated 218 tonnes of the blue box recyclables were diverted from the Eastnor landfill.

6.2. Used Tires

In January 2019, tires were the first material to be moved to the individual producer responsibility (IPR) framework under the recent waste diversion legislation, the Waste-Free Ontario Act. The Municipality continues to collect, and stockpile, used tires at all three of its landfills. As a registered collector, the Municipality accepts used tires from residents. These tires are recycled by tire producers (or Producer Responsibility Organizations), who are now directly responsible and accountable for meeting mandatory collection and recycling targets for used tires. According to the site records, an estimated quantity of 632 tires weighing approximately 8.7 tonnes were received at the Eastnor landfill in 2024.

According to Condition 28(g) of the ECA, the volume of tires within an individual stockpile should not exceed 45 m³. There must be greater than 15 meters between the stockpile and the property line, buildings, and the active area of the landfill, and greater than 30 meters separation from the burn pile. Tires should be stockpiled in an area where there is no vegetation within 4.5 meters. Individual stockpiles should be separated from each other and from other waste piles by a minimum of 6 meters.

6.3. Scrap Metal: Propane Tanks, Scrap Metal and White Goods

The Municipality accepts scrap metal at the Site, including propane tanks and both chlorofluorocarbon (CFC)-containing (i.e., air conditioners, dehumidifiers, freezers, refrigerators and water coolers) and non-CFC-containing white goods. According to Condition 28(c) of the ECA, white goods and marketable scrap metals should be stockpiled separately and should not exceed 100 tonnes.

Site records indicate that 32.1 tonnes of scrap metal (including propane tanks and white goods) were diverted from the waste stream at the Eastnor landfill site during the reporting period. Scrap metal and white goods are periodically removed from the Site for recycling by All Ontario Recycling (AOR).

Propane Tanks

According to Condition 28(e) of the Approval, empty propane tanks should be stored on the ground surface in a segregated area no larger than 500 m². Tanks should be stored in such a manner that minimizes the potential for cylinder valves to be damaged or broken (i.e., in a single layer and in an upright position).

White Goods

In compliance with Ontario Regulation 463/10, CFC-containing white goods are to be properly drained by a certified technician and then tagged to indicate that the CFC's have been removed, prior to the removal of white goods from the site. White goods and scrap metal are collected by a hauler on an as needed basis for salvage. According to Condition 30 of the Approval, the site operator is required to maintain a detailed log of all CFC-containing white goods received at the Site that includes:

- i. The date
- ii. The types, quantities and sources of CFC-bearing items
- iii. The destination of the white goods
- iv. The details on the removal of refrigerants

6.4. Automotive Batteries

Batteries are to be stored in a single layer under a roof to prevent precipitation from coming in contact with the batteries and in a manner that provides secondary containment in the event of leakage. Currently, batteries are stored in the re-use storage building to prevent spills or weathering. According to the Site operational records, no battery units were received at the site during the reporting period. Automotive batteries are periodically removed by Sullivan Salvage for recycling.

6.5. Electronic Waste

The Municipality has been collecting e-waste since 2010. Initially the electronic waste diversion program was operated by the Ontario Electronic Stewardship (OES) who was responsible for electronics recycling in Ontario on behalf of the electronics industry. In January 2021, Electrical and Electronic Equipment (EEE), specifically information technology, telecommunications and audio-visual equipment (ITT/AV), became the third material to be moved to the individual producer responsibility (IPR) framework under the Waste-Free Ontario Act. The producer responsibility for lighting equipment came into effect in January 2023.

The Municipality continues to collect and stockpile electronic waste at all three of its landfills. Electronic waste can be dropped off free of charge. At the Eastnor landfill site e-waste is stored and locked in a steel shipping container adjacent to the scale house. The municipality reported receiving 3.4 tonnes of e-waste at the site during the reporting period.

6.6. Bale Wrap

White plastic bale wrap is accepted by the Municipality free of charge at the Eastnor Landfill Site. This material is collected in a designated area which prevents the plastic from blowing (within a perimeter of concrete block walls). This material should be free of rocks and stones, with a minimal amount of dirt. No colored wrap, twine or other plastic materials should be stored in this pile. Currently, the Municipality has retained Clean Farms to remove the material from the Site. Material is typically removed on an as needed basis. According to site records, approximately 4.25 tonnes of bale wrap was diverted from the waste stream at the Eastnor landfill site during the reporting period.

6.7. Mattresses

In 2012, the Municipality began diverting mattresses as an additional waste diversion stream. According to the Site operational records 213 mattresses, totaling 3.2 tonnes, were received at the Eastnor landfill in 2024. These mattresses are stored in a dry storage area at the Site and are removed periodically for recycling by Recyc-matelas.

6.8. Hazardous and Special Products (HSP)

In October 2021, Hazardous and Special Products transitioned to the individual producer responsibility framework. The HSP program for the Municipality is operated by the County of Bruce through the Orange Drop Program. In the Municipality of Northern Bruce Peninsula, the County typically provides two to three collection events per year.

Based on the Household Hazardous Waste Program summary of materials reportedly received by the County, the amount of HSP collected through the Orange Drop Program was estimated to be 15.3 tonnes during the reporting period. Based on the proportion of the Municipality's population serviced by the Eastnor landfill (i.e., 45%), an estimated 6.9 tonnes of HSP were diverted from the Eastnor landfill through the Orange Drop Program.

6.9. Leaf and Yard Waste

Although the Municipality promotes home composting for wet organics through the distribution of backyard composting bins, a leaf and yard waste composting pile is maintained at the Site. The municipality reported receiving approximately 114 tonnes of leaf and yard waste at the site during the reporting period. This pile should be turned on a regular basis. Surface water run-off generated from this pile should be either prevented or managed. If the pile becomes odorous, it should be placed in the active face of the landfill and immediately covered. Topsoil generated from this service can be used for placement over the final cover.

6.10. Waste Diversion Summary

Based on the sum of the diversion programs at the Eastnor landfill site and local depot, approximately 392 tonnes of materials were diverted from the landfill during the reporting period. It is noted that this quantity of diverted materials does not account for the clean wood and brush (i.e., burnable) that is also diverted from the landfill.

Table 6-3. Summary of Waste Diversion (Tonnes)

| Materials Diverted | 2017 | 2018 | 2019 | 2020 | 2021 | 2022 | 2023 | 2024 |
|---------------------------|-------|-------|-------|-------|-------|-------|-------|-------|
| Blue Box Recyclables | 234.5 | 247.8 | 219.1 | 234.9 | 255.8 | 238.7 | 202.8 | 217.8 |
| Tires | 5.2 | 7.0 | 10.2 | 10.0 | 17.4 | 9.8 | 5.4 | 8.7 |
| Scrap Metal & White Goods | 48.9 | 53.9 | 69.9 | 75.7 | 87.8 | 64.4 | 37.3 | 32.1 |
| Automotive Batteries | 0.07 | 0.11 | 0.27 | 0 | 0.09 | 0.17 | 0 | 0.05 |
| Bale Wrap | 8.4 | 5.4 | 10.9 | 5.8 | 6.1 | 9.5 | 3.5 | 4.3 |
| Electronic Waste | 4.46 | 8.16 | 14.87 | 8.9 | 8.7 | 8.4 | 4.0 | 3.4 |
| Mattresses | 1.7 | 1.8 | 2.8 | 2.7 | 3.8 | 3.2 | 2.5 | 3.2 |
| HSP | 9.0 | 9.6 | 7.6 | 4.0 | 6.7 | 7.1 | 7.1 | 6.9 |
| Polystyrene | | | | | 2.4 | | | 1.4 |
| Leaf and Yard Waste | 61.2 | 91.1 | 144.5 | 76.8 | 244 | 456 | 444 | 114 |
| Total | 373.4 | 424.9 | 480.1 | 418.8 | 632.8 | 797.3 | 706.6 | 391.9 |

Note: All values are presented in tonnes. NA = Not Available

7. BURNING OPERATIONS

Any brush, trees and clean wood material should be stockpiled separately. According to Condition 29(a) of the Approval, this material should be placed in a cleared area no larger than 1,000 m² with a height of 3 meters or less, and a minimum of 30 m separation distance to all other wastes, flammable materials and buildings. As per Condition 29 of the ECA, the burning of clean wood and brush in accordance with the MOE Guideline "Burning at Landfill Sites" is allowed. Before burning takes place, the Chief Fire Official must be notified of the date and time the burning is to take place, in accordance with the Municipal By-Law No. 2000-24, as amended. In 2024, approximately 200 tonnes of clean wood waste and brush was reportedly received at the Site. This material was presumably burned.

Burning at the site is to be restricted to clean, dry wood waste such as brush, trees and lumber. Wood waste is to be stockpiled in a designated burn area. Burning of designated wood waste is to be carried out in an area at least 30 meters away from the active area of landfilling. Additionally, an area of 4.5 meters around the burn pit should be kept free of vegetation.

Burning may occur only on clear, dry, windless days and is to be conducted under the direct supervision of an attendant. The site attendant is responsible for the removal of any non-wood waste from the pile prior to burning, as well as regularly removing cold ashes from the burn area for disposal in the active landfill area. The attendant must fully extinguish the fire at the end of the day.

8. SUMMARY OF HYDROGEOLOGIC SETTING

8.1. Physiographic Setting and Regional Geology

Based on Chapman and Putnam (1984), the Eastnor landfill site is located within the physiographic region known as the Bruce Peninsula. With the exception of the small clay plains characterized by deep poorly drained lacustrine deposits/silt beds in Eastnor Township and various drumlins, gravel bars and sand dunes, the region is generally characterized by flat topography sloping gradually towards Lake Huron, with shallow overburden and abundant bedrock exposed at ground surface (i.e., dolostone plains). The overburden thickness over the majority of the Northern Bruce Peninsula is typically less than 10 meters thick.

8.2. Site Geology

Based on physiographic mapping from the Ontario Geologic Survey and the Ontario Department of Mines and Northern Affairs (Map 2224), the approved fill area is situated on a former beach ridge and the majority of the property is characterized by clay plains (i.e., silt loam soils). It is noted that sand was mined from the former beach ridge associated with the Site prior to its use as a landfill.

Consistent with the regional topography, the Site generally slopes to the west towards West Road. Downgradient of the former beach ridge is an area of saturated soil conditions associated with the poor drainage characteristics of the silt loam plain. This lacustrine deposit (i.e., the silt loam plain) was derived from a former shallow water environment and/or shoreline area and extends towards Little Pike Bay. Consistent with the presence of a lacustrine deposit in the location of the former Bay, the depth to bedrock/overburden thickness appears to be greater in the area that extends from Little Pike Bay to the former beach ridge at the Site. This trend of thicker overburden is inferred to occur in a linear fashion from the beach ridge to Little Pike Bay. Bedrock valleys with thicker overburden that coincide with existing Bays occur throughout the Bruce Peninsula, from Owen Sound to Tobermory.

Local water well records indicate that the overburden in the area is typically less than 5 meters in depth, however, it extends to greater than 10 meters in some areas. Overburden to the north and south of the Site is described as sandy loam underlain by clay in some areas. The overburden becomes finer to the east, along Shaw Road, and is described as clay and silt in this area. The underlying bedrock is characterized by buff to brown medium bedded dolostone of the Guelph Formation. The exposed bedrock surfaces are scoured from glacial activity and are typically irregular due to weathering.

8.3. Overburden Characteristics

Shallow and deep groundwater monitoring wells have been installed at the Site and are located where shown on the attached Figures. With the exception of the boreholes associated with the deep wells, which extend to depths of up to 15.2 m below ground surface (mbgs), well/testhole depths generally range between 3 mbgs and 7 mbgs. The overburden thickness extends to depths of at least 11.7 m, and to greater than 15 m, in the vicinity of the approved fill area. In addition, results of the subsurface investigations conducted at the Site are generally consistent with the Grey and Bruce Counties Groundwater Study which indicates that the overburden in the vicinity of the Site is in the range of 20 m thick. Borehole logs documenting the overburden soils encountered during the well installation activities are enclosed in Appendix D. A detailed summary is provided in Table 2.

Based on a detailed review of the borehole logs, the overburden soils at the Site were divided into four units that generally slope towards the west, as shown on the cross—sections provided in Appendix E. Underlying the thin layer of topsoil or peat, the overburden consists of a medium to fine sand that is an estimated 2.5 to 4 m thick in the

vicinity of the fill area and thins out to the west (UNIT 1). In areas of the Site where the beach ridge has not been extracted/disturbed, the sand unit extends to depths of up to 8.5 meters (i.e., BH-1(15) and BH-2(15)).

This upper sand unit is underlain by UNIT 2 which is a relatively thick unit of silt loam soils (i.e., greater than 4 m in thickness). Based on the borehole logs associated with the deep overburden wells OW-7D, OW-10D and OW-12D, the silt unit is further underlain by a medium to coarse sand, with gravel in some locations (i.e., UNIT 3), which is further underlain by stiff silty clay with gravel (i.e., Unit 4) which is inferred to overlie the bedrock unit.

8.4. Groundwater Flow

Groundwater level measurements are collected bi-annually in conjunction with the monitoring program. Groundwater flow maps, developed using the fall water level measurements, are provided as Figure 4 for the shallow overburden unit and Figure 5 for the deeper sand unit.

Based on the observed water levels, groundwater flow in the shallow overburden aquifer is generally to the southwest across the Site. Groundwater through the deeper sand unit flows in a similar direction, to the southwest. The hydraulic gradient in the vicinity of the former beach ridge was calculated to be approximately 0.2% to 0.45% within the upper and lower sand units. Comparatively the hydraulic gradient downgradient of the landfill footprint was calculated to be more variable, typically ranging between 0.5% and 2.2% within the upper sand unit. Based on the results of the hydrogeological assessment, the representative K-values for Unit 1 and Unit 2 were determined to be approximately 3.7x10-5 m/s and 3.3x10-7 m/s, respectively.

Previous hydrogeologic evaluations and ongoing annual monitoring programs indicate that the vertical gradient in the overburden unit is predominantly downwards in the vicinity of the landfill, as indicated by the gradient noted at well couplet OW-10S/D. This gradient becomes primarily horizontal in the vicinity of OW-7S/D. However, although the vertical gradients measured indicate that a downwards flow component exists in the vicinity of the landfill footprint, the downward migration of leachate-impacted groundwater would be limited by the low permeability associated with the silt loam unit that underlies the upper sand unit. In other words, the underlying low-permeability soils appear to act as an aquitard which would reduce the downward migration of shallow groundwater and result in groundwater flow into the generally flat and wet area situated to the west of the landfill. Groundwater migration from beneath the landfill is likely to be primarily horizontal within the shallow more permeable sand unit in the area directly downgradient of the landfill (i.e., within the area monitored).

Based on the thinning of the shallow sand unit towards the west, as noted in the cross-sections, the wet surficial soils noted further downgradient of the former beach ridge, and the water levels that are typically at or above ground surface at the most downgradient monitoring locations, a predominantly horizontal to upwards gradient is inferred to exist in the vicinity of, and downgradient from, wells OW-4, OW-6 and OW-9.

9. MONITORING REQUIREMENTS

9.1. Monitoring Locations and Parameters

Currently, the Eastnor Waste Disposal Site has 16 groundwater monitoring wells at thirteen different locations, where shown on Figure 3. In September 2000, the first four monitoring wells were installed, followed by the installation of OW-5 and OW-6 in 2010. In conjunction with hydrogeological investigations for the Site, an additional six monitoring wells at four different locations (i.e., two well couplet locations) were installed in 2012 and four monitoring wells at three different locations were installed in 2015. While some of these wells are only used to assess the groundwater flow regime at the Site, several wells are also used to monitor groundwater quality downgradient of the fill area and to assess compliance along the southern compliance limit, as well as site compliance downgradient and to the west of the fill area.

As per Condition 41(3) of the ECA, as amended in November 2017, the groundwater quality is monitored twice annually in the Spring and Fall as per the requirements outlined in Schedule B (Appendix A) and summarized in the following Table.

Table 9-1. Groundwater Monitoring Program

| Man | itaring Landing and Durana | Pa | rameters |
|--------|---------------------------------------|--------|-------------|
| IVIO | itoring Location and Purpose | Spring | Fall |
| OW-1 | Background |)==== | IND |
| OW-2 | Leachate – Closed Area B | | COMP + VOCs |
| OW-3 | Downgradient | | IND |
| OW-4 | Downgradient / South Compliance Well | IND | IND |
| OW-5 | South Compliance Well | IND | IND |
| OW-6 | Furthest Downgradient Well | IND | IND |
| OW-7S | Downgradient of Active Area - Shallow | IND | IND |
| OW-7D | Downgradient of Active Area - Deep | | IND |
| OW-8 | Leachate – Active Area A | IND | COMP + VOCs |
| OW-9 | Background (GW Levels Only) | | |
| OW-10S | Background (Phase I Area) - Shallow | | IND |
| OW-10D | Background (Phase I Area) - Deep | | IND |
| OW-11 | Background (Phase I Area) | | IND |
| OW-12S | Background (Phase I Area) - Shallow | | IND |
| OW-12D | Background (Phase I Area) - Deep | | IND |
| OW-13 | Background (Phase I Area) | | |

Notes: Parameter Requirements:

--- = Water levels to be measured at all monitoring locations during each monitoring event.

Indicator List [IND]:

Alkalinity, conductivity, pH, ammonia, hardness, calcium, iron, magnesium, manganese, phosphorus, potassium, sodium, chloride, nitrate, nitrite, phosphate, sulphate, DOC and TKN. As of 2019, boron is included in this list of required parameters.

Comprehensive List [COMP]:

(as per Column 1, Schedule 5: Inorganic Parameters for Groundwater) and DOC.

Volatile Organics [VOCs]:

Once a year for BTEX and once every three years for VOCs. Analysis is scheduled for 2026. VOCs were added to the list of required parameters for leachate well OW-2 (Fall only).

Water quality results from 2023 and 2024 are summarized in Table 4. Historical groundwater sampling results, including VOCs, and graphical trends of select indicator parameters are included in Appendix F.

To ensure there are adequate sampling locations as landfill development continues within the approved area, monitoring results are reviewed annually with comments provided in the Annual Monitoring Reports. As per the Approval for the Site, recommendations for changes to the monitoring program are to be proposed within the Annual Reports and require approval from the MECP, under the process described in Conditions 4.1 and 4.2.2 of the ECA (as amended November 2017), prior to implementation. In response to MECP comments pertaining to the Trigger Mechanism and Contingency Plan, boron was added to the list of required indicator parameters (i.e., the Indicator List outlined in Schedule B). Further, in response to MECP comments dated August 17, 2022, VOCs were added to the list of required parameters for leachate well OW-2 (Fall only).

9.2. Sampling Methodology

For groundwater sampling, the static groundwater level and well depth are measured in each monitoring well prior to purging three casing volumes of stagnant water from each well. GEI personnel also check to ensure that all monitoring wells are properly secured and in compliance with O.Reg.903. After purging, monitoring wells are allowed to recharge with fresh groundwater before sampling occurs. Groundwater purging and sampling is conducted using dedicated Waterra™ tubing and inertial-type pumps. Samples are collected in laboratory supplied containers and are kept chilled following completion of the sampling program and sent within 24 hours of the sampling event to an accredited laboratory for analysis. Under the site-specific program, samples collected for indicator metals are placed in laboratory supplied containers without preservative and are filtered and preserved at the lab prior to analysis. Samples collected for metals under the comprehensive list are filtered in the field and placed in laboratory supplied containers with preservative. The laboratory analytical reports for samples collected during the reporting period are included in Appendix G.

10. DETERMINATION OF REASONABLE USE CRITERIA FOR THE SITE

10.1. Determination of Action Levels

MECP Guideline B-7 establishes the basis for determining what constitutes the reasonable use of groundwater on properties adjacent to landfill sites. This approach uses both the provincial maximum concentrations identified in the Ontario Drinking Water Standards (ODWS), revised June 2006, and the site-specific background values, to calculate acceptable concentrations at the Site boundary. By applying the RUC, the potential use of groundwater for domestic consumption will almost always provide the lowest allowable concentration limits, referred to as the objective levels. MECP Procedure B-7-1 provides technical details for the application of the reasonable use approach. A change in the quality of groundwater on an adjacent property, where the reasonable use is determined to be for drinking water, will be acceptable only where:

- i. Quality is not degraded by more than 50% of the difference between background concentrations and the ODWS for non-health related parameters, and
- ii. Quality is not degraded by more than 25% of the difference between background concentrations and the ODWS for health-related parameters.

Background concentrations are the quality of the groundwater prior to any contamination from landfill activities.

VOC Analyses at OW-3/OW-8

It is noted that VOC sampling was initiated at well OW-3 in 2005. VOC or BTEX analysis occurred at monitoring well OW-3 until 2015 at which time the VOC sampling location was revised to well OW-8 in order to better reflect groundwater quality downgradient of the active area of landfilling. For RUC calculation purposes, it is assumed that VOCs were not present prior to the initiation of landfill operations at the Site as VOC compounds are not considered to occur naturally in groundwater. A table summarizing the VOC analytical results with comparison to the RUC is provided in Appendix F.

Historically, VOC analytical results reported for well OW-3 indicated trace concentrations of toluene and xylene (i.e., less than 1 μ g/L), when detected. However, VOC results obtained from well OW-8, located closer to the recently active area of landfilling, reported benzene concentrations generally in the range of 1.5 to 2.5 μ g/L between 2015 and 2024, exceeding the RUC of 1.25 μ g/L for benzene. It is noted that, based on the relatively low concentration previously detected and the buffer area of greater than 500 meters to the western compliance limit, it is anticipated that benzene will be adequately attenuated on-site. As per the revised monitoring program, monitoring for VOCs or BTEX from well OW-8 will continue to occur on an annual basis. Further, in response to MECP comments dated August 17, 2022, VOCs were added to the list of required parameters for leachate well OW-2. VOC compounds have not been detected in the groundwater quality samples collected from OW-2.

10.2. Background Water Quality

Background concentrations are the quality of the groundwater prior to any contamination from landfill activities. Monitoring well OW-1 has historically been used as the background monitoring location based on the direction of the shallow groundwater flow at the Site and its cross-gradient location relative to the fill area which results in the least potential for impacts from the landfill. Historical and on-going water quality results support the use of OW-1 as a background well as the results indicate that this monitoring location has consistently had the lowest concentrations of indicator parameters with no indication of leachate influence. Monitoring well couplet OW-10S/D, located upgradient of the fill area, which is also considered to represent background conditions, shows similar parameter concentrations and supports the ongoing use of OW-1 as a background well at this time.

Groundwater quality results collected from well OW-1 between 2001 and November 2017, provided in Appendix F, were used to calculate the average and 95th-percentile background concentrations for each indicator parameter to aid in the determination of RUC values. The 95th-percentile concentration was used to reflect the RUC background concentrations for parameters with concentrations that exceed the ODWS, including hardness, iron, manganese, and DOC. The background concentration ranges, averages, and resulting RUC values (i.e., objective levels) for several indicator parameters are summarized in Table 3.

Based on the analytical data for well OW-1, the shallow background groundwater chemistry for the Site can generally be described as having low levels of chloride, typically less than 5 mg/L, a slightly basic pH of approximately 7.9, and conductivity in the range 415 μ S/cm. The average hardness and alkalinity are approximately 235 mg/L and 210 mg/L, respectively, which is representative of a carbonate-rich groundwater system.

10.3. Calculation of Objective Levels

Table 3 identifies the concentrations of groundwater quality indicator parameters used for evaluating the acceptable level of contaminant concentrations at the site boundary. Background concentrations (Cb) are the site-specific values (discussed in the previous section). The provincial maximum concentrations (Cr) are identified in the Technical Support Document for Ontario Drinking Water Standards Objectives and Guidelines (June 2006), referred to herein as the ODWS. Acceptable concentrations at the site boundary (Cm) (herein referred to as the Reasonable Use Criteria (RUC)), are calculated from MECP Procedure B-7-1 using the following formula.

$$Cm = Cb + x(Cr - Cb)$$

Where:

Cm = Maximum concentration acceptable in groundwater beneath an adjacent property.

Cb = Background concentration.

Cr = Maximum concentration that should be present in groundwater for domestic consumption according to the ODWS.

X = 0.5 for non-health related parameters (AO/OG) and 0.25 for health-related parameters (MAC & IMAC).

AO = Aesthetic Objective

OG = Operational Guideline

MAC = Maximum Acceptable Concentration, Parameters Related to Health

IMAC = Interim Maximum Acceptable Concentration, Parameters Related to Health

It should be noted that if background concentrations exceed the ODWS, the objective level is to be set at the background concentration, as outlined by Procedure B-7-1. A summary of the 2023 and 2024 analytical results compared to the RUC and ODWS is provided in Table 4.

To determine if leachate is impacting groundwater, individual indicator parameters were evaluated in conjunction with other indicator parameters and concentration trends. Wells with elevated and stable concentrations of the identified naturally elevated constituents, that show no increases in other leachate indicator parameters, are deemed un-impacted by landfill leachate. Additionally, known leachate impacted groundwater is compared to the groundwater chemistry at locations with naturally elevated concentrations to determine if leachate contributes to the elevated concentrations measured.

11. MONITORING RESULTS AND DISCUSSION

11.1. Leachate Generation

Leachate is produced when surface water percolates down through refuse resulting in impacted water that has the potential to migrate along the surface or in the ground. Landfill derived leachate that enters into the groundwater is often attenuated by natural mechanisms along the water migration pathway. The attenuation of leachate can occur by dilution, biologic activity, and geochemical mechanisms.

To determine the presence of potential impacts from leachate, several indicator parameters are monitored, and a trend analysis is conducted to determine changes in water quality over time. The following sections discuss the potential impacts to groundwater, with a focus on the water quality crossing the property boundaries and compliance with the Reasonable Use Criteria (RUC). The results of the most recent groundwater monitoring and compliance with the RUC are provided in Table 4. Historical groundwater sampling results and graphical trends of indicator parameters are included in Appendix F.

11.2. Leachate Characterization

Leachate production is typically greatest directly beneath the landfill and at the perimeter of the landfilled area. According to a letter dated January 9, 2003 and addressed to the MOE summarizing the results of an EM survey conducted by the MOE in November 1995, a contaminant plume was interpreted to be migrating to the southwest, as later monitored by well OW-3, and a high conductivity zone was noted to extend approximately 200 m downgradient from the fill area (i.e., in the vicinity of OW-4).

Monitoring well OW-2 was historically used to monitor the characteristics of the leachate impacted groundwater at the Site. This leachate well is located approximately 10 meters west of the approved landfill limit for historically filled Area B. In conjunction with the well installation activities that were required to support the Hydrogeological Investigations in 2013, the characteristics of the leachate downgradient of Area A was evaluated from well OW-8.

As would be expected due to the proximity these wells to the fill area, while OW-2 had historically shown the greatest influence from landfill leachate downgradient from Area B, groundwater quality results from well OW-8 were indicative of leachate impacts downgradient of Area A.

Comparison of the groundwater quality from these two wells most proximal to the fill area suggests that leachate characteristics downgradient of historically landfilled Area B and the more recently active Area A are notably different. Consequently, the primary site-specific indicator parameters associated with each area of landfilling is considered as part of the impact assessment for downgradient monitoring wells. A comparison of the primary leachate parameter characteristics for each location, based on each of the 2014 and 2015 monitoring events, the 2016 and 2017 monitoring events and the monitoring events from 2018 to present is provided in Table 11-1. It is noted that the geochemical signature at each of these locations generally remains similar, however concentrations at OW-8 have generally decreased in recent years.

Table 11-1. Leachate Characterization

| Parameter | Units | Back ground | THE RESERVED IN SECTION AND ADDRESS OF THE PARTY OF THE P | Average Concentration (2014/2015) Average Concentration (2016/2017) | | | Average Concentration (2018 to 2024) | |
|---------------------|-----------|----------------|--|---|------------------|------------------|--------------------------------------|------------------|
| Monitoring Location | | OW-1 | OW-2 OW-8 (Area B) (Area A) | | OW-2 (Area B) | OW-8 (Area A) | OW-2 (Area B) | OW-8 (Area A) |
| Conductivity | μS/cm | 418 | 3,238 | 3,523 | 3,265 | 3,040 | 2,962 | 2,213 |
| Alkalinity | mg/L | 214 | 1,010 | 1,575 | 977 | 1,363 | 962 | 993 |
| Hardness | mg/L | 237 | 1,643 | 883 | 1,558 | 828 | 1,482 | 693 |
| Calcium | mg/L | 61.0 | 259 | 236 | 254 | 226 | 268 | 205 |
| Magnesium | mg/L | 19.8 | 242 | 71.2 | 226 | 64.4 | 198 | 44 |
| Chloride | mg/L | 3.36 | 129 | 244 | 166 | 155 | 129 | 103 |
| Sulphate | mg/L | 20.7 | 903 | 31.2 | 838 | 98.6 | 768 | 59 |
| Sodium | mg/L | 1.47 | 77.2 | 212 | 77.1 | 148 | 78 | 94 |
| Potassium | mg/L | 0.52 | 143 | 123 | 133 | 106 | 122 | 56 |
| Ammonia | mg/L | 0.22 | 0.12 | 114 | 1.45 | 89.5 | 0.07 | 44 |
| DOC | mg/L | 19.3 | 9.53 | 63.3 | 12.3 | 50.9 | 13.4 | 35 |
| TKN | mg/L | 1.1 | 0.77 | 127 | 2.26 | 98.9 | 0.58 | 54 |
| Note: Backgro | und conce | entration for | OW-1 is base | d on the avera | ige value from | data collected | between 2001 | and 2024. |

Based on a comparative analysis of the primary leachate indicator parameters downgradient of Areas A and B, it is evident that the indicator parameters, and/or relative magnitude thereof, are variable. Area A is considered to be reflective of reducing conditions. Comparatively, Area B, which is older and contains increasingly mature and degraded refuse, is more oxidized. This is considered to be typical for the progression of water quality associated with leachate generation. In either case, it is important to note that areas influenced by leachate have increased concentrations for several leachate indicator parameters.

While some of the leachate indicators for both Area A and Area B are similar, including conductivity, hardness, alkalinity, chloride, sodium and potassium, the relative concentrations for some of these parameters differs between both locations. For example, the alkalinity at OW-2 is lower than that reported for OW-8 while the hardness is significantly higher at OW-2. Hardness concentrations at OW-2 appear to be more significantly affected by increased magnesium concentrations (i.e., at OW-2 calcium and magnesium concentrations are similar, whereas at OW-8 magnesium concentrations are typically one quarter to one-third the concentration of calcium). In addition, while sulphate appears to be a primary indicator for leachate downgradient of closed Area B, with concentrations reported to be in the range of approximately 600 mg/L to 900 mg/L, recent concentrations downgradient of the active area are only slightly elevated above background (i.e., less than 100 mg/L). Conversely, ammonia, DOC and TKN appear to be primary indicators of leachate downgradient of Area A, while concentrations downgradient of Area B remain similar to background.

Groundwater quality trends at OW-2, as presented on the graph provided in Appendix F, suggest that leachate indicator parameter concentrations are generally lower than they were in the early 2000's. More specifically, chloride concentrations, which were in the range of 250 to 400 mg/L, have generally remained below 200 mg/l since 2005, periodically exceeding the RUC of 127 mg/L. The concentrations of other leachate indicator parameters have generally remained stable.

11.3. East Property Boundary Condition (UpGradient)

The eastern property boundary is located approximately 130 meters upgradient from the landfill footprint at its closest point. Due to the southwesterly groundwater flow direction and the extensive buffer zone to the east of the landfill, leachate impacts to groundwater are not anticipated along the eastern compliance limit.

Groundwater quality to the east of the landfill is currently monitored at OW-10S/D, located greater than 30 meters upgradient of the active fill area. Based on the underlying sandy soils in the vicinity of the fill area and the groundwater flow direction, the potential for radial flow at a scale that would result in measurable impacts to background well OW-10S/D is considered to be low. An additional monitoring location OW-11 is situated 150 meters to the north and upgradient of the future Phase I landfill area. Water quality at well OW-1 is considered to represent background conditions.

Review of the analytical data from the shallow groundwater monitoring wells OW-10S and OW-11 compared to background well OW-1 indicates that, in general, the analytical data from wells OW-10S/D and OW-11 is similar to that reported for the established background monitoring well OW-1 (Table 4). However, some minor differences are evident. More specifically, the shallow groundwater in the area to the east of the existing and future approved fill areas has a slightly higher conductivity than that noted at background well OW-1. This is likely due to the slightly elevated hardness, alkalinity, and DOC concentrations, as well as slightly higher concentrations of sulphate and sodium noted for wells OW-10S and OW-11.

A comparison of the average concentrations calculated using all the available data (i.e., up to and including 2024) is provided in Table 11-2.

Table 11-2. East Boundary Condition – Groundwater Quality

| Parameter Units | | Background | A | Average Concentration | | | | | |
|---------------------|-------|------------|--------|-----------------------|--------|--|--|--|--|
| Monitoring Location | | OW-1 | OW-10S | OW-11 | OW-10D | | | | |
| Conductivity | μS/cm | 418 | 606 | 600 | 524 | | | | |
| Alkalinity | mg/L | 214 | 304 | 327 | 284 | | | | |
| Hardness | mg/L | 237 | 296 | 317 | 279 | | | | |
| Calcium | mg/L | 61.0 | 82.7 | 89.6 | 71.6 | | | | |
| Magnesium | mg/L | 19.8 | 21.8 | 22.6 | 24.3 | | | | |
| Chloride | mg/L | 3.36 | 5.8 | 4.96 | 3.98 | | | | |
| Sulphate | mg/L | 20.7 | 33.5 | 18.8 | 12.7 | | | | |
| Sodium | mg/L | 1.47 | 16.9 | 4.19 | 1.62 | | | | |
| Potassium | mg/L | 0.52 | 0.95 | 0.46 | 0.67 | | | | |
| Ammonia | mg/L | 0.22 | 0.48 | 0.21 | 0.12 | | | | |
| DOC | mg/L | 19.3 | 36.1 | 42.8 | 8.8 | | | | |
| TKN | mg/L | 1.1 | 1.92 | 2.26 | 0.27 | | | | |

RUC exceedances in the background monitoring locations OW10S/D and OW-11 were noted for hardness and DOC during the reporting period.

11.4. North Property Boundary Condition (Cross-Gradient)

The northern property boundary is cross-gradient from the landfill and is located greater than 500 m from the existing landfill footprint at its closest point, as shown in Figure 2. Monitoring well OW-1 is situated approximately 30 meters north of the approved landfill footprint. As previously discussed, this well is used as the background monitoring location and, to date, the reported groundwater chemistry has not exhibited influence from landfill leachate.

Two additional monitoring locations are available further to the north, including well couplet OW-12S/D and OW-13. These were installed proximal to the western limit of the approved Phase I area and are located an estimated 75 m and 175 m north of OW-1, respectively. As would be expected, water quality monitoring completed at these monitoring locations consistently indicates that the water quality in this area to the north of the existing landfill and west of the beach ridge is generally similar to that reported for well OW-1. A comparison of the average concentrations calculated using the available data for OW-1, OW-12S/D and OW-13 is provided in Table 11-3.

Table 11-3. North Boundary Condition – Groundwater Quality

| Parameter | Units | Background | verage Concentration | | | |
|--------------|-----------------|------------|----------------------|-------|--------|--|
| Monit | toring Location | OW-1 | OW-12S | OW-13 | OW-12D | |
| Conductivity | μS/cm | 418 | 363 | 438 | 369 | |
| Alkalinity | mg/L | 214 | 207 | 227 | 229 | |
| Hardness | mg/L | 237 | 190 | 204 | 189 | |
| Calcium | mg/L | 61.0 | 49.5 | 62.2 | 53.9 | |
| Magnesium | mg/L | 19.8 | 16.2 | 11.8 | 13.2 | |
| Chloride | mg/L | 3.36 | 1.9 | 0.91 | 1.98 | |
| Sulphate | mg/L | 20.7 | 5.0 | 2.46 | 1.08 | |
| Sodium | mg/L | 1.47 | 0.86 | 0.78 | 2.3 | |
| Potassium | mg/L | 0.52 | 0.48 | 0.27 | 1.3 | |
| Ammonia | mg/L | 0.22 | 0.018 | 0.06 | 0.12 | |
| DOC | mg/L | 19.3 | 8.5 | 23.4 | 43.0 | |
| TKN | mg/L | 1.1 | 0.13 | 0.23 | 1.04 | |

No RUC exceedances were noted at well couplet OW12S/D during the reporting period.

11.5. Downgradient - West of the Existing Landfill

The western compliance boundary is situated greater than 600 m downgradient of the existing landfill footprint. Groundwater quality is monitored downgradient of Area B at wells OW-2, OW-3 and OW-4, and downgradient of Area A at wells OW-6, OW-7S/D and OW-8, where shown on Figure 4.

As discussed in Section 11.2 of this Report, both OW-2 and OW-8 are used to monitor the characteristics of leachate impacted groundwater in the shallow sand unit. Monitoring well OW-2 is located approximately 10 m downgradient of closed Area B and well OW-8 is located directly downgradient of Area A. Since the associated primary leachate indicator parameters, and/or relative magnitude thereof, identified at each leachate well differs, the downgradient water quality is evaluated based on its interpreted upgradient source. In other words, the water quality reported for wells OW-3 and OW-4 is compared to the water quality in leachate well OW-2 and in monitoring wells OW7S/D and OW-6 is compared to leachate well OW-8 (Table 4). Furthermore, although the majority of the downgradient wells monitor groundwater quality in the shallow sand unit, it is noted that wells OW-4 and OW-7D monitor groundwater quality in the silt loam unit (i.e., Unit 2) and the deeper sand unit (i.e., Unit 3), respectively.

Shallow Sand Unit - Downgradient of Area A

Monitoring wells OW-7S/D and OW-8 were installed in 2012. These wells are situated approximately 30 meters and 90 meters downgradient of Area A, respectively, and upgradient of compliance well OW-6. Groundwater quality results indicate that a similar suite of leachate indicator parameters exists at both OW-8 and OW-7S although, consistent with its location further downgradient from the landfill, concentrations at OW-7S have typically been slightly lower.

As would be expected with the completion of landfilling within Area A and the continued placement of refuse within the Phase I area (i.e., in the more southerly portion of the approved fill area), between 2015 and about 2023 concentration trends for several leachate indicator parameters at wells OW-7S and OW-8 showed a decreasing to stable concentration trend (refer to Appendix F). This reflected a shift in operations to an area that was not directly upgradient of these monitoring locations (i.e., OW-8 and OW-7S). More recently, concentrations have increased slightly. Consistent with the monitoring results from wells OW-2 and OW-3, located downgradient of Area B, the leachate 'plume' appears to extend to greater than 90 meters from the landfill footprint (i.e., OW-7S). RUC exceedances are noted for alkalinity, hardness, manganese and DOC at these locations. It is noted that in 2024, chloride concentrations approached the RUC at well OW-7S.

Monitoring results from well OW-6, located furthest downgradient from the existing landfill footprint, indicate that the leachate strength becomes greatly reduced within approximately 210 m of the landfill limits with minor landfill leachate derived impacts evident. Concentrations of several leachate indicator parameters appear to be slightly elevated, however concentration trends remain relatively stable. Chloride concentrations typically remain in the range of 20 mg/L to 45 mg/L, below the RUC of 127 mg/L. RUC exceedances were noted for hardness and alkalinity and a minor RUC exceedance of manganese was reported in the spring.

Shallow Sand Unit – Downgradient of Closed Area B

Consistent with the location of well OW-2 directly downgradient of the closed landfill footprint, indicator parameter concentrations have historically been greatest at this monitoring location. Monitoring well OW-3, situated approximately 85 m downgradient of OW-2, shows a similar suite of elevated leachate indicator parameters, although the concentrations are typically lower. Overall, groundwater quality showed a decreasing concentration trend at these monitoring locations until about 2007. Since that time, chloride concentrations at wells OW-2 and OW-3 have remained relatively stable, typically in the range of 60 mg/L to 200 mg/L and 60 mg/L to 110 mg/L, respectively, periodically exceeding the RUC of 127 mg/L at OW-2. RUC exceedances were noted for alkalinity, hardness, sulphate and manganese during the reporting period.

The most recent water quality results indicate that the leachate indicator parameter concentrations in this area to the southwest of Area B continue to remain stable. Based on our assessment it appears that, consistent with the northerly progression of waste placement, the landfill leachate plume generally appears to be stabilizing in the vicinity of OW-2 and OW-3. Periodic spikes in chloride concentrations observed may be related to the application of dust suppressants and/or road salt to the access road in this area of the Site.

Although the groundwater chemistry downgradient of the active landfilling area continues to show minor leachate influence that can extend greater than 200 m downgradient of the landfill (i.e., OW-6), considering the additional distance of greater than 300 m from the downgradient compliance wells to the western property boundary, the potential for the migration of leachate impacted groundwater beyond the western property boundary is considered to be very low.

Silt Loam Unit - Downgradient of Closed Area B

Groundwater quality in the silt loam unit, which underlies the shallow sand unit, is monitored at well OW-4 which is situated approximately 200 meters downgradient of the landfill footprint. It is noted that groundwater quality is measured from the silt loam unit as the shallow sand unit pinches out in this area (i.e., Unit 2 was reportedly encountered at an estimated 0.65 mbgs). Results show parameter concentrations similar to background indicating the absence of landfill leachate impacts within the silt loam unit at this monitoring location.

Deeper Sand Unit

Comparison of the groundwater quality from wells OW-10D and OW-12D to well OW-7D, situated upgradient and downgradient of the active landfill area, respectively, indicates that there is a slight component of downward groundwater migration through the silt loam soils resulting in minor leachate-derived influence in the deeper overburden unit. Based on the available groundwater quality data, chloride concentrations are typically less than 10 mg/L in the deeper background wells (i.e., OW-10D and OW-12D) and range between 15 to 30 mg/L in well OW-7D located 90 m downgradient of the active landfill area. In addition, the conductivity and concentrations of hardness and alkalinity are generally greater in well OW-7D. Based on the groundwater quality results reported for the deeper sand unit (i.e., Unit 3) and the presence of the silt loam soils separating the shallow sand unit (i.e., Unit-1) from the deeper sand unit, landfill-leachate derived impacts to groundwater in the deeper sand unit are considered to be low relative to those observed in the shallower soils.

11.6. South Property Boundary Condition (Cross-Gradient)

The southern property boundary is located approximately 6 meters from the approved limit for landfilling, as shown in Figure 3. As discussed in the Annual Progress Report (2007) (G&M, 2008), in response to concerns regarding an insufficient buffer zone along the southern property limit a test pit program was completed in the fall of 2007 to delineate the southern limit of buried waste more accurately. The test pit program revealed that a portion of Area B, previously thought to have contained buried waste, had not been utilized for waste placement. This unused area is outlined in Figure 3. Based on field observations, buried waste did not appear to be present within 40 meters of the southern property boundary, contrary to the 6-meter buffer area previously inferred by the topography.

OW-5 monitors groundwater quality in the shallow sand unit and is located approximately 50 meters cross-gradient and to the south of the existing landfill footprint and less than 10 meters from the southern property boundary. Based on the groundwater quality data, minor leachate influence has historically been noted at this monitoring location. Slightly elevated concentrations of leachate indicator parameters, as compared to background concentrations, have been reported for several parameters, including conductivity, alkalinity, hardness, chloride, sodium, sulphate, potassium, and manganese. Similar to the background monitoring locations, RUC exceedances were noted for hardness, manganese and alkalinity during the reporting period.

While chloride concentrations at well OW-5 prior to 2015 remained below 100 mg/L, concentrations were generally detected in the range of 150 mg/L and 270 mg/L between 2015 and the spring of 2018 and again in 2020/2021, exceeding the RUC of 127 mg/L. Chloride concentrations decreased to 77 mg/L in the Fall of 2021 and were detected at concentrations of less than 20 mg/L during the reporting period. Comparison to other leachate indicator parameters suggest that, except for a similar concentration trend for hardness, the remainder of the parameter concentrations have remained relatively stable. These results suggest that the water quality at this compliance well was likely influenced by operations at the site rather than landfill leachate generation from within closed Area B.

The use of dust-suppressants (i.e., Ca-Cl) along the nearby access road was interpreted as the cause of the change in water quality at OW-5. It is noted that the magnitude of the increase in chloride concentrations was greater at well OW-5 than that reported for other monitoring locations. The greater degree of influence was interpreted to be directly related to the layout of the Site. More specifically, dust suppressant upgradient of OW-2 was applied to the existing access road, a cross-sectional area of approximately 8 meters, whereas the access road directly upgradient of OW-5 that was in use until the spring of 2021 ran in an easterly direction resulting in a length of road covering a distance of 60 to 80 meters that sloped towards OW-5. Therefore, the area to which dust suppressant would have been applied was greater directly upgradient of OW-5 compared to OW-2.

In 2020, it was recognized that the transition of landfill operations into the southerly portion of the Phase I area could potentially be having a greater impact on the water quality along the southerly compliance limit (i.e., OW-5). As a result, an assessment of the operational practices, including road maintenance standards (i.e., salt, dust control) and site grading, particularly in the area to the south of the landfill, was completed. Mitigation measures included minor site grading efforts. Based on the groundwater quality results from well OW-5 since the fall of 2021, it appears that the operational adjustments sufficiently addressed the groundwater exceedances at this location. On-going groundwater monitoring will continue to be reviewed to evaluate the adequacy of the mitigation measures implemented. It has been recommended that the Municipality cease the use of dust-suppressants along the access road in this area of the Site, when possible.

11.7. Water Quality Summary

The overburden groundwater flow, in the vicinity of the existing landfill, is generally in a southwesterly direction towards the western property boundary. Consequently, the leachate plume from the landfill is inferred to be most prevalent in this direction and, based on the presence of the silt loam soils underlying the medium to fine sand associated with the beach ridge, is inferred to be primarily limited to the shallow groundwater. While the background groundwater quality can be described as highly mineralized with concentrations of hardness, iron, manganese and DOC typically exceeding the ODWS, the shallow groundwater quality to the east of the beach ridge (i.e., OW-10S and OW-11) is slightly different than that to the west (i.e., OW-12S and OW-13), as is indicated by the higher conductivity, alkalinity and hardness noted to the east. This suggests that some degree of variability in the groundwater quality can be expected. Therefore, to determine if leachate is impacting groundwater, individual indicator parameters were evaluated in conjunction with other indicator parameters and concentration trends.

Based on a comparison of the primary leachate indicator parameters downgradient of Areas A and B, it is evident that the indicator parameters and/or relative magnitude thereof are variable. In general, the primary leachate indicator parameters include conductivity, hardness, alkalinity, chloride, sodium and potassium. In addition, sulphate appears to be a primary indicator for leachate downgradient of closed Area B and ammonia, DOC and TKN appear to be primary indicators of leachate downgradient of Area A.

Analytical data indicates that leachate impacted groundwater is present immediately downgradient of the landfill at wells OW-2 and OW-8, with leachate-derived impacts that exceed the RUC limited to approximately 100 m downgradient of the non-active portion of the landfilled area (i.e., Area B) and extending to greater than 90 m

downgradient of the recently active landfill area (i.e., beyond OW-7S). Further downgradient of the landfill, beyond well OW-7S, leachate indicator parameter concentrations in the shallow sand unit (i.e., at OW-6) are greatly reduced relative to those wells situated within 100 m of the landfill limit (i.e., OW-2, OW-3, OW-7S, and OW-8), suggesting that significant leachate attenuation is occurring within 210 m of the landfill footprint. Considering the downgradient groundwater quality distribution in the upper sand unit, the relatively stable groundwater quality trends, and the additional distance to the western property boundary of greater than 300 meters from the most westerly compliance monitoring locations, the potential for off-site impacts to the west is considered to be very low.

12. TRIGGER MECHANISMS AND CONTINGENCY PLAN

A trigger mechanism and contingency plan entitled 'Trigger Mechanisms and Contingency Plan, Eastnor Waste Disposal Site, Municipality of Northern Bruce Peninsula' (the Plan) was prepared by GM BluePlan (now GEI) and submitted to the MECP for review and approval. This Plan was updated in December 2017, as is recognized by the ECA, as amended. Condition 5.1 outlines the trigger parameters, trigger levels, and locations for the site.

The Plan describes the conditions (i.e., trigger levels) under which contingency measures may be required and recommends the corresponding contingency and remedial action plans for the Site. The primary goal of the Contingency Plan is to provide a course of action in the event that the monitoring program indicates a potential for off-site impacts related to the production and migration of leachate. A summary of the trigger locations, parameters, and levels, compared to the recent monitoring results, is provided in Table 5, and is discussed below. The reader is referred to the Plan (December 2017) for more detail pertaining to the trigger mechanisms and for a description of the contingency and remedial action plans for the Site.

12.1. Trigger Locations

Trigger locations were selected to indicate potential off-site migration of landfill leachate impacts. At the Eastnor Waste Disposal Site it was determined that potential off-site impacts related to the migration of leachate-impacted groundwater are limited to the southerly and westerly property boundaries. Groundwater migrating towards the western and southern property boundaries is monitored at wells OW-4, OW-5 and OW-6. Consequently, these wells have been established as the trigger locations for the Site.

12.2. Trigger Levels

Trigger levels for groundwater, based on compliance with MECP Guideline B-7-1, were established to determine when the contingency plan was to be implemented. The Contingency Plan outlines measures that are to be implemented if the trigger levels are exceeded.

Based on an evaluation of the background groundwater quality, historic site data, primary indicator parameters, the Reasonable Use Criteria (RUC) for the Site, and MECP comments, it was determined that the trigger parameters would include chloride, sodium, sulphate, boron, nitrate, and alkalinity. For early detection purposes, the trigger levels were set at either:

- i. Where indicator parameters are naturally low, 80% of the RUC at monitoring locations situated in close proximity to the property boundary (i.e., OW-4 and OW-5). Although monitoring location OW-6 is located greater than 100 meters from the property boundary, a similar trigger level was outlined in the ECA.
- ii. Where the indicator parameter is naturally elevated in the groundwater at the Site (i.e., where the RUC is less than the background concentrations noted), the trigger level is based on the 95th percentile of the concentrations historically reported.

This approach ensures that contingency measures will not be implemented for trigger parameters that remain within the concentration range considered to be naturally occurring and that a reasonable timeframe will be available to implement the contingency plan prior to the occurrence of a non-compliance scenario. The trigger for the Contingency Plan is when two or more of the same trigger parameters exceed the trigger levels at the same location for two consecutive monitoring events.

12.3. Trigger Levels – Comparison and Findings

Exceedances of the established trigger concentrations for chloride of 102 mg/L and alkalinity of 284 mg/L have historically been reported for well OW-5. A comparison of the groundwater monitoring results to the trigger parameters and levels established in Table 1 of the ECA, as amended on April 15, 2019, provided as Table 5, shows that in the Fall of 2021 the indicator parameter concentrations decreased to levels below the established trigger levels. Since that time, groundwater quality parameter concentrations have continued to show a decreasing trend, with concentrations appearing to become more similar to historical levels.

Based on an assessment of the historical groundwater quality results and trends and a review of site operations, increased chloride concentrations noted at OW-5 were interpreted to be related to the application of dust suppressant along the access road to Area B. An operations related cause for the increased chloride concentrations was consistent with the absence of landfill-related activities upgradient and in closer proximity to OW-5. To alleviate this potential contributing source of chloride to the shallow aquifer, it was recommended that the Municipality cease the use of dust-suppressant along the access road in this area of the Site, when possible. In addition, the relocation of the access road was considered. Modifications to the grading in this area was completed in early 2021 to address past trigger exceedances. On-going groundwater quality monitoring will continue to be reviewed to evaluate the adequacy of the mitigation measures implemented.

13. METHANE GAS MIGRATION

Landfill gas is primarily produced by the bacterial decomposition of organic materials after the capping and closure of a landfill has been completed and is combustible if it accumulates to concentrations greater than the lower explosive limit (LEL). Landfill gas tends to migrate laterally from the landfill area when the gas is unable to escape vertically through the ground surface via dry relatively permeable soils, commonly due to an overlying low permeability geologic stratum, or when the ground surface is frozen.

At the Site, the sandy soils in the vicinity of the landfill have a relatively high permeability that permits the venting of gases to the atmosphere. In addition, the landfill is constructed above grade and the vadose zone around the perimeter of the waste is relatively thin, limiting the potential pathway for methane gas migration. Therefore, at the Eastnor Landfill site methane gas is vented passively to the surrounding atmosphere.

As there is no methane gas control system required for landfilling, ECA Condition 41(1) requires that any buildings or structures with 100 m of the landfill footprint contain adequate ventilation systems to relieve any possible landfill gas accumulation. At this time, the re-use storage building, and operator weigh scale building, are both located greater than 250 meters from the landfill footprint. Therefore, methane gas is not thought to be of concern at the Site.

14. CONCLUSIONS

- 1. The Site comprises an approved landfill area of 9.5 ha, a waste transfer station for recyclable wastes, and since 2009, an additional 1.09 ha area for the disposal of wood waste only (i.e., stumps). Of the 9.5 hectares for waste disposal, a 3.3-hectare area described as Area A and Area B, was originally approved with a capacity of 93,000 m³ for waste and interim cover. Since these areas have reached their capacity, operations have transitioned into the Phase I area. The additional capacity associated with the remaining 6.2-hectare area (i.e., Phase I and Phase II) is recognized in the ECA, as amended.
- 2. Based on the fill rate determined by annual topographical surveys of the active area, it is estimated that a volume of 3,625 m³ was used for the year 2024 with a remaining capacity for waste and daily cover estimated to be approximately 250,000 m³.
- 3. In consideration of the capacity of the Phase I area of 270,000 m³ for waste and interim cover and the anticipated use of the landfill by the entire Municipality, which will increase the annual fill rate, the site life is estimated to be 40 to 45 years.
- 4. It is important that the Municipality continue to promote the segregation and recycling of waste. Stockpiles of recyclable goods should be removed on a regular basis to prevent clutter and to maintain an aesthetically acceptable site. Items that are to be separated from the residual waste and stockpiled in designated areas include, household recyclables, white goods, scrap metal, propane tanks, batteries, tires, mattresses, bale wrap, construction materials, HSP, electronic waste, leaf and yard waste, and scrap wood and brush.
- 5. Shallow groundwater flow in the overburden aquifer is generally to the southwest across the Site. Ongoing groundwater level monitoring indicates that groundwater migration in the overburden unit is predominantly downwards in the vicinity of the landfill, as indicated by the gradient noted at OW-10S/D, becoming primarily horizontal in the vicinity of OW-7S/D. Based on the thinning of the shallow sand unit towards the west, and the wet surficial soils noted further downgradient of the former beach ridge, a predominantly horizontal gradient is inferred to exist downgradient of wells OW-4 and OW-6.
- 6. Groundwater quality data from monitoring well OW-1 indicates that the background water quality has naturally elevated concentrations of hardness, iron, manganese, and DOC.
- 7. Based on a comparison of the primary leachate indicator parameters downgradient of Areas A and B, it is evident that the indicator parameters and/or relative magnitude thereof are variable. In general, the primary leachate indicator parameters include conductivity, hardness, alkalinity, chloride, sodium, and potassium. In addition, sulphate appears to be a primary indicator for leachate downgradient of closed Area B and ammonia, DOC and TKN appear to be primary indicators of leachate downgradient of Area A.
- 8. Analytical data indicates that leachate impacted groundwater is present immediately downgradient of the landfill at wells OW-2 and OW-8, with leachate-derived impacts that exceed the RUC limited to approximately 100 m downgradient of the non-active portion of the landfilled area (i.e., Area B) and extending to greater than 90 m downgradient of the recently active landfill area (i.e., beyond OW-7S). Further downgradient of the landfill, beyond well OW-7S, leachate indicator parameter concentrations in the shallow sand unit (i.e., at OW-6) are greatly reduced, suggesting that significant leachate attenuation is occurring within 210 m of the landfill footprint. Considering the additional distance to the western property boundary of greater than 300 m, the potential for off-site impacts to the west is considered to be low.
- 9. Groundwater quality at well OW-5, located approximately 10 meters from the southern property boundary was historically indicative of minor leachate influence with concentrations typically remaining below the RUC and generally exhibiting stable to decreasing trends. The groundwater quality results measured between 2015 and 2018, and again in 2020, reported a significant increase in chloride to concentrations in exceedance of the RUC. However, these exceedances were not interpreted to be solely related to landfilling, rather were also attributed

to landfill operations. As expected, the minor changes to Site operations have resulted in decreased chloride concentrations. In 2024, the groundwater quality at OW-5 reflected concentrations similar to historical levels, with chloride concentrations reported to be less than 20 mg/L.

10. The continual and progressive placement of waste at the Site allows for the continual evaluation of impacts due to waste placement, through the twice annual groundwater monitoring program, resulting in an additional level of protection and ensuring the protection of groundwater resources.

15. RECOMMENDATIONS

Based on the findings of this Report and the Conditions of the ECA, the following recommendations are provided:

- 1. The Municipality should continue to employ the area ramp method in order to achieve optimal compaction and an increased site life.
- 2. A topographic survey of the active area of the Site should be completed in the fall of 2025 to update site conditions, the annual fill rate, and to determine remaining landfill capacity.
- 3. The application of interim or final cover to areas that have been filled to final grade should be considered to help reduce the generation and downgradient migration of leachate. As Area A and Area B have reached capacity, these landfill areas should be capped, as per the PDO for the Eastnor Landfill Site (December 2017).
- 4. The twice annual monitoring program, as outlined in Schedule B of the ECA, should continue to be completed. In consideration of the updated Trigger Mechanism and Contingency Plan, boron should continue to be included to the list of 'Indicator' parameters outlined in Schedule B. In addition, based on MECP comments received in correspondence dated August 17th, 2022, VOCs were added to the list of parameters for well OW-2. The twice annual monitoring program, including locations and parameters, is outlined in Section 9.1 of this report.
- 5. The application of road salt and or dust suppressant to the access road for Area B should be avoided, as possible.
- 6. In recognition of the past trigger exceedances at well OW-5 and the transition of landfill operations into the southerly portion of the Phase I area, attention to site conditions and operations should continue in this area. It is anticipated that the mitigation measures implemented in 2021 will continue to help alleviate the historical groundwater exceedances at this location.

Tables

- Table 1: Eastnor Landfill Volume Capacity (m³)
- Table 2: Summary of Borehole Logs and Monitoring Well Installation Details
- Table 3: Site Specific Background Concentrations & Guideline B-7-1 RUC Determination
- Table 4: Groundwater Quality Summary 2023 and 2024
- Table 5: Comparison of Groundwater Quality at the Established Trigger Locations to the Trigger Levels

TABLE 1
EASTNOR LANDFILL VOLUME CAPACITY (m³)

| | Limited to Area A and B | | | | A/B + | - Phase I | | | |
|--|-----------------------------|------------------------|------------------------------|------------------------------|---------------------|---------------------|--|------------------------------|------------------------------|
| | <u>2018</u> | | <u>2018</u> | <u>2019</u> | <u>2020</u> | <u>2021</u> | <u>2022</u> | <u>2023</u> | <u>2024</u> |
| Total Approved Capacity Total Capacity for Waste and Daily Cover Total Capacity for Final Cover Total Air space Capacity | 93,000 10,500 103,500 | s amended in | 363,000 48,000 411,000 | 363,000 48,000 411,000 | 48,000 | 48,000 | 363,000 48,000 411,000 | 363,000 48,000 411,000 | 363,000 48,000 411,000 |
| Capacity Used During Year Capacity Used for Waste and Daily Cover Capacity Used for Final Cover Total Capacity Used | 2,950 0 2,950 | as per E ld April 2 | N/A | 2,650 0 2,650 | 2,750 0 2,750 | 2,750 0 2,750 | 4,000 0 4,000 | 5,800 0 5,800 | 3,625 0 3,625 |
| Volume Filled at End of Year Volume of Waste and Daily Cover Volume of Final Cover Total Volume Filled | 91,700 0 91,700 | capacity er 2017 | 91,700 0 91,700 | 94,350 0 94,350 | 0 | 0 | 103,850 0 103,850 | 0 | 113,275 0 113,275 |
| Remaining Capacity at End of Year Capacity for Waste and Daily Cover Capacity for Final Cover Total Remaining Capacity | 1,300 10,500 11,800 | al for a | 271,300 48,000 319,300 | 268,650 48,000 316,650 | 48,000 | 48,000 | The state of the s | 48,000 | 249,725 48,000 297,725 |
| Remaining Site Life At 5-Year Average Fill Rate (3,800 m³/yr) | | ΑF | 71.4 | 70.7 | 70.0 | 69.3 | 68.2 | 66.7 | 65.7 |

Notes:

- 1. Since 2007, annual capacities used have been calculated using elevations obtained from topographic surveys of the active landfill areas conducted in the fall of each year.
- 2. In consideration of the additional approved Phase I and Phase II areas of 6.2-hectares for landfilling and 1.09-hectares for wood waste disposal, the ECA, as amended, approves a total capacity of 652,500 m³, not including final cover (613,500 m³ for refuse and daily/interim cover and 39,000 m³ for wood waste).
- 3. An additional capacity of 250,000 m³ for waste and interim cover (i.e. not including final cover and topsoil) is available in the Phase II area, subject to the submission and approval of a detailed Hydrogeological Assessment and Plan of Development and Operation.

TABLE 2 SUMMARY OF BOREHOLE LOGS AND MONITORING WELL INSTALLATION DETAILS

| | Inst | allation | ation | | | | | Well Screen | T | Depth Interval of | | | Unit | | Hydraulic Condu | ictivity (m/s) | | |
|----------|------|--|-------------|--------------|---------|--------|------------|-------------|--------------------|---|----------------|-------|---|---|------------------------|---|--|-------------------------|
| | | etails | FI | evation (ma | el) | Scree | en Interva | al (masi) | Top of Sandpack | and Sandpack | Unit | From | To | From | To | | Hazen Method | Slug Test |
| Well ID | | Method | Ground | TOC | BH Btm | Bottom | | Length (ft) | | Interval | No. | mk | | m | | Description of Unit Encountered | [sample depth mbgs] | Bouwer and Rice |
| OW-1 | | H.S.A. | 194.57 | 195.57 | 187.87 | 187.87 | | 5 | 191.07 | ilitervai | 1 | 1111 | | 194.57 | | Loose orangy-brown silty fine SAND | [campa asparange] | Dodwer and race |
| 044-1 | 2000 | 11.5.A. | assumed | measured | assumed | 107.07 | 109.57 | 3 | 191.07 | OW-1 | 1 | 1.5 | | 193.07 | | Compact brown to grey fine to medium SAND | + | |
| 014/ 2 | 2000 | LLC A | 194.28 | 195.28 | 187.58 | 188.18 | 100.60 | E | 191.28 | OVV-1 | Tanasil | 1.5 | | 193.07 | | Topsoil | + | |
| OW-2 | 2000 | H.S.A. | S SCHOOLSES | 8 8 3-9800-5 | | 188.18 | 189.68 | 5 | 191.28 | | Topsoil | 0 | 50000 | 0.000 | | s in Institute. | | |
| | | | assumed | measured | assumed | | | | | | 1 | 0.2 | A. Trotti | 194.08 | | Loose orange-brown fine SAND, some silt | - | |
| | | | | | | | | | | OW-2 | 1 | 2.9 | 5.1 | CNS89 17,-009077800 [2 | | Dense brown to grey medium SAND | | |
| | | | | | | | | | | | 2 | 5.1 | | | | Mottled olive-grey SILT, some fine sand | | |
| OW-3 | 2000 | H.S.A. | 190.79 | 191.79 | 187.14 | 187.14 | 188.69 | 5 | 189.89 | | PEAT | 0 | | 190.79 | | Black fibrous PEAT | | |
| | | | assumed | measured | assumed | | | | | OW-3 | 1 | 0.5 | | 190.29 | | Loose to compact brown medium to fine SAND | | |
| | | | | | | | | | | 0,, 0 | 2 | 3.2 | 3.65 | 100000000000000000000000000000000000000 | | Stiff brown SILT, trace fine sand | | |
| OW-4 | 2000 | H.S.A. | 188.64 | 189.64 | 181.94 | 182.54 | 184.04 | 5 | 184.64 | | PEAT | 0 | 0.45 | 188.64 | 188.19 | Black fibrous PEAT | | |
| | | | assumed | measured | assumed | | | | | | 1 | 0.45 | 0.65 | 188.19 | 187.99 | Dark brown silty fine SAND | | |
| | | | | | | | | | | OW-4 | 2 | 0.65 | 6.7 | 187.99 | 181.94 | Firm to stiff mottled olive grey grading to blueish grey SILT, some fine sand | | |
| OW-5 | 2010 | S.S.A. | 191.62 | 192.7 | 187.82 | 187.82 | 191.02 | 10 | 191.02 | | PEAT | 0 | 0.25 | | | Organics | 1 | |
| | | | | | | | | | | 16/06/19 110 | 1 | 0.25 | | | | Brown medium to coarse sand grading to grey fine to medium SAND | 1 | |
| | | | | | | | | | | OW-5 | 2 | 3.65 | 3.8 | | | Grey clayey SILT | | |
| OW-6 | 2010 | SSA | 188.62 | 189.58 | 184.82 | 184.82 | 187.82 | 10 | 188.14 | | PEAT | 0.00 | | | | Black topsoil | 1 | |
| 011-0 | 2010 | 0.0.A. | 700.02 | 700.00 | 704.02 | 104.02 | 107.02 | 10 | 100.14 | | 1 | 0.3 | 1.0 | | | Dense brown fine SAND | | |
| - | | - | | - | | - | | | | OW-6 | 2 | 1.0 | 3.8 | 200 10000000000000000000000000000000000 | | Grey-blue clayey SILT | + | 2.01 x 10 ⁻⁷ |
| OW 70 | 2012 | 11.0.4 | 101.00 | 404.0F | 475.00 | 407.00 | 400.40 | | 400.70 | | DEAT | 1.0 | | | | | + | 2.01 X 10 |
| OW-7S | 2012 | H.S.A. | 191.02 | 191.85 | 175.82 | 187.02 | 189.42 | 8 | 189.72 | | PEAT | 0 | 0.6 | A. 25 A. 30 A. | 190.42 | | - | 5 |
| OW-7D | | | | 191.73 | | 178.87 | 180.37 | 5 | 180.72 | OW-7S | 1 | 0.6 | 50,000,00 | 190.42 | | Grey/green SAND | | 2.5 x 10 ⁻⁵ |
| | | | | | | | | | | OW-7D | 2 | 2.74 | 11.6 | 0.04 (0.41 (0 | | Brown to grey/green SILT | 2.9 x 10 ⁻⁹ [6.1-6.7] | F |
| | | | | | | | | | | (((((((((((((((((((| 3 | 11.6 | 14.9 | The Research Control of the Control | | Grey/green medium to coarse SAND | 3.2 x 10 ⁻⁴ [12.2-12.8] | 2.4 x 10 ⁻⁵ |
| | | | | | | | | | | | 4 | 14.9 | 15.2 | 176.12 | | Stiff grey/brown silty CLAY with gravel | | |
| OW-8 | 2012 | H.S.A. | 191.95 | 192.75 | 188.17 | 188.35 | 190.75 | 8 | 190.98 | | PEAT | 0 | 0.6 | 191.95 | 191.35 | PEAT | | |
| | | | | | | | | | | OW-8 | 1 | 0.6 | 3.05 | 191.35 | 188.90 | Brown to grey SAND | F. 4 40 ⁻⁶ [2 0 0 0 0] | 4.1 x 10 ⁻⁵ |
| | | | | | | | | | | OVV-6 | 1 to 2 | 3.05 | 3.78 | 188.90 | 188.17 | Grey/green SAND grading to grey/green clayey SILT | 5.4 x 10 ⁻⁶ [3.0-3.6] | |
| OW-9 | 2012 | H.S.A. | 189.19 | 190.15 | 182.26 | 182.39 | 185.44 | 10 | 185.99 | | Topsoil | 0 | 0.3 | 189.19 | 188.89 | Topsoil | | |
| | | | | | | | | | | | 1 | 0.3 | 1.52 | 188.89 | 187.67 | Brown SAND | | |
| | | | | 1 | | | | | | OW-9 | 2 | 1.52 | 6.93 | 187.67 | 182.26 | Grey/green SILT and fine sand | 6.0 x 10 ⁻⁹ [1.5-2.1] | 4.1 x 10 ⁻⁷ |
| | | | | | | | | | | 100000000000000000000000000000000000000 | F | | 0.00 | | | | 2.4 x 10 ⁻⁰ [6.1-6.7] | |
| OW-10S | 2012 | HSA | 192.31 | 193.14 | 177.07 | 189.21 | 190.71 | 5 | 190.98 | | PEAT | 0 | 0.6 | 192.31 | 191.71 | PEAT | | |
| OW-10D | 2012 | 11.0.71. | 702.01 | 94.54 | 177.07 | 177.56 | 179.11 | 5 | 179.71 | OW-10S | 1 | 0.6 | | 191.71 | | Grey/green SAND | 1 | |
| OW-10D | | | | 34.34 | | 177.50 | 173.11 | | 17.5.71 | OVV-100 | 2 | 3.4 | | 188.91 | | Grey/green SILT grading to silty SAND | 5.4 x 10 ⁻⁸ [4.6-5.2] | |
| - | | - | | | | - | | | | | | 3.4 | 11.0 | 100.91 | 101.34 | Grey/green Sich grading to sitty SAND | 4.9 x 10 ⁻⁹ [7.6-8.2] | |
| | | <u> </u> | - | | | | | | | | _ | 44.0 | 44.0 | 404.04 | 470.00 | Ones and a section of CAND | | 0.0 40-5 |
| | | | | | | | | | | OW-10D | 3 | 11.0 | | | | Grey coarse grained SAND | 1.8 x 10 ⁻⁴ [12.2-12.8] | 8.8 x 10 ⁻⁵ |
| | | | | | 10010 | 122.21 | | _ | | | 4 | 14.0 | 15.2 | | | Grey limestone COBBLES | | |
| OW-11 | 2015 | H.S.A. | 192.06 | 193.01 | 186.12 | 189.01 | 190.54 | 5 | 191.15 | | PEAT | 0 | 100000000000000000000000000000000000000 | 192.06 | THE SECOND PROPERTY OF | Peat and topsoil | | |
| | | | | | | | | | | OW-11 | 1 | 0.76 | 3.12 | | | Grey fine to medium SAND with some silt. Loose. | | |
| | | | | | | | | | | | 2 | 3.12 | | | 187.49 | Grey clayey SILT with trace sand. | | |
| | | | | | | | | | | | 2 | 4.57 | | 187.49 | 186.12 | Grey-brown clayey SILT with trace sand increasingly stiff with depth. | | |
| OW-12S | 2015 | H.S.A. | 192.21 | 192.92 | 179.41 | 189.16 | 190.69 | 5 | 191.30 | | Topsoil | 0 | 0.83 | 192.21 | 191.38 | Light brown sandy topsoil | | |
| OW-12D | | | 192.16 | 192.93 | | 180.06 | 183.10 | 10 | 183.71 | OW-12S | 1 | 0.83 | | | | Brown SAND with little silt | | |
| | | | | | | | | | | UVV-125 | 1 | 2.10 | | | | Grey fine to medium SAND with some silt. Loose. | 1 | |
| | | | | | | | | | | | 2 | 4.11 | 7.62 | 188.10 | 184.59 | Grey clayey SILT with trace sand | | |
| | | | | | | | İ | 1 | | | 2 | 7.62 | | | | Grey silty fine SAND | 1 | |
| | | | | | | | | | | OW-12D | 3 | 11.26 | | | | Grey coarse grained SAND. Very loose. | | |
| OW-13 | 2015 | H.S.A. | 191.72 | 192.5 | 186.54 | 188.38 | 180 00 | 5 | 190.81 | | PEAT | 0 | | | | Peat and topsoil | † | |
| 011-13 | 2010 | 11.0.7. | 101.12 | 102.0 | 100.04 | 100.00 | 103.30 | | 150.01 | OW-13 | 1 | 0.70 | | | | Brown-grey fine to medium SAND with some silt | | |
| — | | | | + | | | | | | 5+V-15 | 2 | 3.50 | 5.00 | 100.02 | 100.22 | Grey silty Clay | + | |
| PORTUG | EC | | | | | | | | | | <u> </u> | 3.50 | 5.18 | 100.22 | 100.54 | loiey siity oldy | | |
| BOREHOL | | luo a | 404.00 | A / A | 400.04 | L NIA | N/A | I N.A | N/A | NIA. | I ₄ | , | 0.45 | 400.00 | 400.00 | II KAND | | |
| BH-1(15) | 2015 | H.S.A. | 194.08 | NA | 182.34 | NA | NA | NA | NA | NA | 1 | 1 | | | | Loose brown SAND | 1 | |
| | | | | 1 | | | | | ļ | | 1 | 3.15 | | | | Grey medium to fine SAND with some silt | ļ | |
| | | | | | | | | | | | 2 | 6.17 | | | | Grey clayey SILT with trace sand | | |
| | | | | | | | | | | | 2 | 11.20 | | | | Grey silty fine SAND. Loose. | | |
| | | | | | | | | | | | Refusal | 11.60 | | | | Auger refusal, potential bedrock surface. | | |
| BH-2(15) | 2015 | H.S.A. | 196.72 | NA | 185.44 | NA | NA | NA | NA | NA | 1 | 0 | 6.17 | 196.72 | 190.55 | Loose light brown SAND | | |
| | | | | | | | | | | | 1 | 6.17 | | | | Loose grey fine to medium SAND with some silt | | |
| | | | | | | | | | | | 2 | 8.60 | | | | Grey clayey SILT with trace sand | | |
| | | | | | | | | | | | | 0.00 | 0 | | | Processed and the first of the second second second | | |

- Notes:

 1. mbgs = meters below ground surface.
 2. TOC = top of PVC pipe (i.e. measuring point); BH btm = Bottom of Borehole.
 3. Information presented for wells OW-1 through OW-4 was obtained from borehole logs prepared by AMEC.
 4. Elevations were adjusted in 2022 to suit UTM derived coordinates and the elevation across the site was raised by 98.4 meters to reflect geodetic elevations.

TABLE 3 SITE SPECIFIC BACKGROUND CONCENTRATIONS AND GUIDELINE B-7-1 RUC DETERMINATION

| GROUNDWATER INDICATOR PARAMETERS | | | | | | | | | | | |
|----------------------------------|---------------|--------------------|----------------------|-----------------------|-----------------|-----------------|--|--|--|--|--|
| | | | NOR LANDFILL SIT | | | | | | | | |
| | Maximum | ODWS | Background | Background | 95th Percentile | Objective | | | | | |
| | Concentration | Classification | Concentration | Concentration | Concentration | Level | | | | | |
| Parameter (mg/L) | (Cr) | - Cidooiiiodaiioii | Range [n] | (Cb) | | (Cm) | | | | | |
| Conductivity (uS/cm) | ŇÝ | NV | 322 - 487 [32] | 414 | 464 | NV | | | | | |
| Chloride | 250 | AO | 1.2 - 5.4 [33] | 3.3 | 5.0 | 127 | | | | | |
| Hardness | 80 to 200 | OG | 211 - 289 [31] | 239 | 261 | 261 | | | | | |
| DOC | 5 | AO | 10.8 - 33.9 [22] | 19.2 | 30.2 | 30.2 | | | | | |
| Iron | 0.3 | AO | 0.18 - 5.07 [30] | 0.88 | 1.83 | 1.83 | | | | | |
| Manganese | 0.05 | AO | 0.14 - 0.38 [21] | 0.18 | 0.31 | 0.31 | | | | | |
| Boron | 5 | IMAC | 0.018 [1] | 0.018 | N/A | 1.26 | | | | | |
| Alkalinity | 500 | OG | 185 - 257 [33] | 210 | 249 | 355 | | | | | |
| Ammonia | NV | NV | <0.05 - 0.52 [31] | 0.22 | 0.42 | NV | | | | | |
| TKN | NV | NV | 0.64 - 2.8 [20] | 1.2 | 1.8 | NV | | | | | |
| Nitrate | 10 | MAC | <0.05 - 0.34 [27] | 0.10 | 0.27 | 2.58 | | | | | |
| Nitrite | 1 | MAC | <0.05 [23] | < 0.05 | NA | 0.25 | | | | | |
| Phosphorus | NV | NV | <0.05 - 0.54 [20] | 0.24 | 0.50 | NV | | | | | |
| Phosphate | NV | NV | <0.10 [21] | <0.10 | NA | NV | | | | | |
| Sulphate | 500 | AO | 12.7 - 42.5 [32] | 21.6 | 33.8 | 261 | | | | | |
| pH (no units) | 6.5 to 8.5 | OG | 7.48 - 8.24 [30] | 7.86 | 8.13 | 6.5 to 8.5 | | | | | |
| Potassium | NV | NV | 0.25 - 1.44 [21] | 0.53 | 1.43 | NV | | | | | |
| Sodium | 200 | AO | 0.90 - 2.42 [32] | 1.38 | 1.95 | 101 | | | | | |
| | Ca | - | ective Levels - Vola | atile Organics | | | | | | | |
| Parameter | Maximum | ODWS | | | | Objective | | | | | |
| | Concentration | Classification | Assumed | Background Con | centration | Level | | | | | |
| | (Cr) | | | (Cb) | | (Cm) | | | | | |
| Benzene | 0.005 | MAC | | 0 | | 0.00125 | | | | | |
| 1,4 Dichlorobenzene | 0.005 | MAC | | 0 | | | | | | | |
| Dichloromethane | 0.1 | MAC | | 0 | | 0.0125 | | | | | |
| Toluene | | | | | | | | | | | |
| Vinyl Chloride | 0.002 | MAC | | 0 | | 0.012 0.0005 | | | | | |

Notes:

- 1. [n] = number of data points used to determine the average background concentration.
- 2. Available data from OW-1 collected from 2001 to November 2017 was used to calculate background concentrations.
- 3. mg/L = milligrams per litre; uS/cm = microsiemens per centimetre; NV = No Value.
- 4. AO = Aesthetic Objective; OG = Operational Guideline
 - MAC = Maximum Acceptable Concentration, Parameters Related to Health
 - IMAC = Interim Maximum Acceptable Concentration, Parameters Related to Health

MOECC Procedure B-7-1

Cm = Cb + x(Cr - Cb)

Where:

Cm = Maximum concentration acceptable in groundwater beneath an adjacent property.

Cb = Background concentration.

Cr = Maximum concentration that should be present in groundwater for domestic consumption according to the Ontario Drinking Water Standards (ODWS).

x = 0.5 for non-health related parameters and 0.25 for health related parameters.

5. For parameters in which the background concentration (i.e. the average concentration) exceeds the ODWS, the 95th percentile is used to represent the RUC for the Site. These parameters are shaded and shown in **BOLD**.

TABLE 4
GROUNDWATER QUALITY SUMMARY - 2023 and 2024

| | 1 | ODWS | | RUC | | | Backg | round | | | E | Background (C | Crossgradient |) | , | |
|--------------|------------|------------|------|------------|-----------|-----------|-----------|-----------|-----------|-----------|-----------|---------------|---------------|-----------|-----------|-----------|
| Parameter | Units | | | | OW-1 [S] | | OW | -10S | OW- | -10D | OW- | 11 [S] | OW-1 | 2S [S] | OW-1: | 2D [D] |
| | | | | | 28-Nov-23 | 12-Nov-24 | 28-Nov-23 | 12-Nov-24 | 28-Nov-23 | 12-Nov-24 | 28-Nov-23 | 12-Nov-24 | 28-Nov-23 | 12-Nov-24 | 28-Nov-23 | 12-Nov-24 |
| Conductivity | (µS/cm) | NV | NA | NV | 457 | 525 | 506 | 598 | 552 | 534 | 633 | 609 | 369 | 341 | 338 | 350 |
| pН | (Unitless) | 6.5 to 8.5 | OG | 6.5 to 8.5 | 7.58 | 7.70 | 7.26 | 7.29 | 7.78 | 7.77 | 7.17 | 7.52 | 7.58 | 7.88 | 7.44 | 7.72 |
| Alkalinity | mg/L | 30-500 | OG | 355 | 262 | 295 | 310 | 324 | 323 | 339 | 408 | 373 | 238 | 234 | 234 | 360 |
| Hardness | mg/L | 80-100 | OG | 261* | 243 | 278 | 244 | 280 | 297 | 253 | 330 | 291 | 209 | 166 | 191 | 171 |
| Chloride | mg/L | 250 | AO | 127 | 3.35 | 3.69 | 4.72 | 4.68 | 3.97 | 2.58 | 5.29 | 2.90 | 7.12 | 0.74 | 1.93 | 1.57 |
| Nitrate | mg/L | 10.0 | MAC | 2.58 | <0.05 | 0.05 | < 0.05 | <0.05 | <0.05 | <0.05 | < 0.05 | <0.05 | < 0.05 | <0.05 | 0.18 | 0.24 |
| Nitrite | mg/L | 1.0 | MAC | 0.25 | <0.05 | <0.05 | <0.05 | <0.05 | <0.05 | <0.05 | < 0.05 | <0.05 | < 0.05 | <0.05 | < 0.05 | <0.05 |
| Sulphate | mg/L | 500 | AO | 261 | 19.6 | 35.2 | 10.6 | 35.5 | 13.1 | 6.45 | 3.15 | 0.31 | 4.91 | 4.18 | 1.09 | 0.78 |
| Phosphate | mg/L | NV | NA | NV | <0.10 | <0.10 | <0.10 | <0.10 | <0.10 | <0.10 | <0.10 | <0.10 | <0.10 | <0.10 | <0.10 | <0.10 |
| Phosphorus | mg/L | NV | NA | NV | 0.18 | 0.14 | 0.70 | 1.10 | 0.11 | 0.70 | 0.80 | 0.12 | 0.42 | 0.54 | 0.84 | 3.11 |
| Calcium | mg/L | NV | NA | NV | 64.7 | 73.6 | 66.8 | 74.9 | 76.5 | 65.9 | 91.7 | 82.7 | 55.4 | 42.6 | 54.5 | 48.6 |
| Magnesium | mg/L | NV | NA | NV | 19.8 | 22.8 | 18.7 | 22.5 | 25.8 | 21.4 | 24.5 | 20.4 | 17.2 | 14.5 | 13.4 | 12.1 |
| Sodium | mg/L | 200 | AO | 101 | 1.71 | 2.22 | 8.74 | 3.85 | 1.69 | 1.72 | 2.71 | 2.75 | 1.03 | 0.72 | 2.22 | 1.81 |
| Potassium | mg/L | NV | NA | NV | <0.50 | <0.50 | 0.71 | 0.53 | 0.63 | <0.50 | <0.50 | <1.0 | <0.50 | <0.50 | 1.45 | 0.71 |
| Iron | mg/L | 0.3 | AO | 1.83* | 0.55 | 0.34 | 0.24 | 0.27 | <0.010 | <0.020 | 0.91 | 0.94 | <0.010 | <0.020 | 0.018 | 0.033 |
| Manganese | mg/L | 0.05 | AO | 0.31* | 0.17 | 0.23 | 0.26 | 0.26 | 0.038 | 0.062 | 0.26 | 0.26 | 0.010 | 0.003 | 0.051 | 0.038 |
| Boron | mg/L | 5.0 | IMAC | 1.26 | 0.027 | 0.018 | 0.064 | 0.041 | 0.017 | 0.022 | 0.020 | 0.021 | <0.010 | <0.010 | 0.028 | 0.020 |
| Ammonia | mg/L | NV | NA | NV | 0.20 | 0.29 | 0.20 | 0.24 | 0.06 | 0.28 | 0.13 | 0.12 | <0.02 | <0.02 | 0.08 | 0.06 |
| DOC | mg/L | 5.0 | AO | 30.2* | 14.6 | 13.0 | 25.8 | 35.9 | 1.7 | 9.2 | 34.1 | 38.6 | 1.4 | 1.9 | 7.2 | 18.2 |
| TKN | mg/L | NV | NA | NV | 0.76 | 0.90 | 3.39 | 1.60 | <0.10 | 0.54 | 4.43 | 1.20 | 0.41 | <0.10 | 2.01 | 1.14 |

| Parameter | Units | ODWS | | RUC | Leachate OW-2 [S] | | Downg OW- | radient 3 [S] | | Crossg OW- | | | Downgradient OW-4 [SL] | | | |
|--------------|------------|------------|------|------------|----------------------|-----------|--------------|------------------|-----------|---------------|-----------|-----------|---------------------------|-----------|-----------|-----------|
| | | | | | 28-Nov-23 | 12-Nov-24 | 28-Nov-23 | 12-Nov-24 | 21-Apr-23 | 28-Nov-23 | 30-Apr-24 | 12-Nov-24 | 21-Apr-23 | 28-Nov-23 | 30-Apr-24 | 12-Nov-24 |
| Conductivity | (µS/cm) | NV | NA | NV | 2830 | 2830 | 2150 | 2590 | 789 | 794 | 952 | 1030 | 457 | 394 | 434 | 441 |
| рН | (Unitless) | 6.5 to 8.5 | OG | 6.5 to 8.5 | 7.49 | 7.48 | 7.83 | 7.47 | 7.59 | 7.56 | 7.50 | 7.53 | 7.83 | 7.76 | 7.88 | 7.83 |
| Alkalinity | mg/L | 30-500 | G | 355 | 988 | 822 | 742 | 831 | 353 | 414 | 485 | 553 | 221 | 250 | 257 | 266 |
| Hardness | mg/L | 80-100 | OG | 261* | 1325 | 1048 | 1020 | 1150 | 379 | 399 | 520 | 507 | 205 | 211 | 255 | 216 |
| Chloride | mg/L | 250 | AO | 127 | 100 | 56.5 | 74.6 | 64.3 | 19.3 | 14.7 | 14.2 | 12.7 | 1.73 | 1.72 | 1.44 | 1.48 |
| Nitrate | mg/L | 10.0 | MAC | 2.58 | <0.07 | <0.14 | 0.42 | <0.14 | 0.08 | 0.11 | <0.05 | <0.05 | 0.05 | 0.11 | <0.05 | <0.05 |
| Nitrite | mg/L | 1.0 | MAC | 0.25 | <0.05 | <0.11 | <0.05 | <0.11 | <0.05 | <0.05 | <0.05 | <0.05 | <0.05 | <0.05 | <0.05 | <0.05 |
| Sulphate | mg/L | 500 | AO | 261 | 729 | 583 | 471 | 496 | 50.4 | 57.0 | 74.8 | 89.7 | 13.4 | 11.5 | 11.6 | 10.5 |
| Phosphate | mg/L | NV | NA | NV | NM | | <0.13 | <0.26 | <0.10 | <0.10 | <0.10 | <0.10 | <0.10 | <0.10 | <0.10 | <0.10 |
| Phosphorus | mg/L | NV | NA | NV | 1.05 | 0.50 | 0.12 | 0.15 | 1.18 | 1.89 | 1.11 | 0.56 | 0.03 | 0.05 | 0.03 | 0.11 |
| Calcium | mg/L | NV | NA | NV | 232 | 193 | 184 | 209 | 103 | 110 | 137 | 137 | 53.8 | 56.9 | 66.3 | 57.4 |
| Magnesium | mg/L | NV | NA | NV | 181 | 138 | 136 | 153 | 29.6 | 30.1 | 43.1 | 40.1 | 17.1 | 16.7 | 21.8 | 17.7 |
| Sodium | mg/L | 200 | AO | 101 | 68.1 | 43.6 | 36.4 | 40.9 | 8.54 | 6.54 | 8.75 | 9.12 | 3.29 | 2.79 | 3.10 | 2.92 |
| Potassium | mg/L | NV | NA | NV | 128 | 105 | 59.6 | 62.6 | 6.24 | 5.28 | 6.96 | 6.34 | 1.01 | 1.06 | 1.26 | 0.88 |
| Iron | mg/L | 0.3 | AO | 1.83* | 5.23 | 0.033 | 0.025 | <0.020 | 0.026 | 0.046 | <0.020 | 0.025 | 0.56 | 0.18 | 0.12 | <0.020 |
| Manganese | mg/L | 0.05 | AO | 0.31* | 1.17 | 0.96 | 0.61 | 0.78 | 0.45 | 0.15 | 0.77 | 0.60 | 0.027 | 0.008 | 0.031 | 0.025 |
| Boron | mg/L | 5.0 | IMAC | 1.26 | 1.54 | 1.62 | 0.87 | 1.19 | 0.34 | 0.35 | 0.48 | 0.55 | 0.026 | 0.049 | 0.040 | 0.038 |
| Ammonia | mg/L | NV | NA | NV | 0.07 | 0.03 | <0.02 | 0.17 | <0.02 | <0.02 | 0.40 | <0.02 | <0.02 | <0.02 | 0.05 | <0.02 |
| DOC | mg/L | 5.0 | AO | 30.2* | 13.3 | 23.0 | 11.9 | 22.4 | 14 | 8.2 | 12.1 | 11.7 | 10.5 | 6.5 | 10.7 | 10.6 |
| TKN | mg/L | NV | NA | NV | 0.56 | 0.60 | 0.18 | 0.77 | 1.07 | 0.88 | 1.06 | 0.50 | 0.21 | <0.10 | 0.12 | 0.26 |

TABLE 4
GROUNDWATER QUALITY SUMMARY - 2023 and 2024

| | | its ODWS | | | | Leachate Downgradient | | | | | | | | | | Downgradient | | | | |
|--------------|------------|------------|------|------------|-----------|-----------------------|-----------|-----------|-----------|-----------|-----------|-----------|-----------|-----------|-----------|--------------|-----------|-----------|--|--|
| Parameter | Units | | | RUC | | OW- | 8 [S] | | | OW | I-7S | | OW | '-7D | | OW- | 6 [S] | | | |
| | | | | | 21-Apr-23 | 28-Nov-23 | 30-Apr-24 | 12-Nov-24 | 21-Apr-23 | 28-Nov-23 | 30-Apr-24 | 12-Nov-24 | 28-Nov-23 | 12-Nov-24 | 21-Apr-23 | 28-Nov-23 | 30-Apr-24 | 12-Nov-24 | | |
| Conductivity | (µS/cm) | NV | NA | NV | 1510 | 2150 | 2450 | 2370 | 2360 | 2240 | 3050 | 2900 | 904 | 924 | 769 | 775 | 882 | 836 | | |
| pН | (Unitless) | 6.5 to 8.5 | OG | 6.5 to 8.5 | 7.21 | 7.33 | 7.06 | 7.09 | 7.15 | 7.25 | 6.98 | 7.03 | 7.57 | 7.63 | 7.73 | 7.85 | 7.67 | 7.77 | | |
| Alkalinity | mg/L | 30-500 | OG | 355 | 635 | 988 | 937 | 961 | 1090 | 1170 | 1200 | 1220 | 455 | 496 | 345 | 420 | 416 | 512 | | |
| Hardness | mg/L | 80-100 | OG | 261* | 542 | 677 | 679 | 597 | 609 | 623 | 794 | 597 | 481 | 250 | 340 | 402 | 419 | 353 | | |
| Chloride | mg/L | 250 | AO | 127 | 103 | 122 | 115 | 118 | 95.5 | 83.0 | 128 | 126 | 20.9 | 18.2 | 21.0 | 21.7 | 20.1 | 23.1 | | |
| Nitrate | mg/L | 10.0 | MAC | 2.58 | <0.05 | < 0.07 | <0.14 | <0.14 | <0.14 | 0.78 | <0.14 | <0.14 | <0.05 | <0.05 | < 0.05 | 0.09 | <0.05 | <0.05 | | |
| Nitrite | mg/L | 1.0 | MAC | 0.25 | <0.05 | < 0.05 | <0.11 | <0.11 | <0.11 | <0.05 | <0.11 | <0.11 | <0.05 | <0.05 | < 0.05 | <0.05 | <0.05 | <0.05 | | |
| Sulphate | mg/L | 500 | AO | 261 | 51.0 | 65.4 | 55.8 | 51.1 | <0.38 | 9.55 | 2.92 | 3.08 | 84.4 | 78.9 | 38.2 | 32.9 | 34.6 | 25.6 | | |
| Phosphate | mg/L | NV | NA | NV | <0.10 | NM | <0.26 | | <0.26 | <0.13 | <0.26 | <0.26 | <0.10 | <0.10 | <0.10 | <0.10 | <0.10 | <0.10 | | |
| Phosphorus | mg/L | NV | NA | NV | 0.64 | 0.66 | 0.28 | 1.15 | 0.14 | 0.63 | 0.67 | 1.03 | 1.50 | 2.87 | 2.80 | 2.02 | 2.49 | 2.32 | | |
| Calcium | mg/L | NV | NA | NV | 161 | 219 | 198 | 179 | 185 | 191 | 235 | 182 | 129 | 65.3 | 91.8 | 112 | 113 | 97.0 | | |
| Magnesium | mg/L | NV | NA | NV | 34.0 | 31.6 | 44.8 | 36.4 | 35.7 | 35.4 | 50.2 | 34.7 | 38.5 | 21.0 | 27.0 | 29.8 | 33.2 | 26.9 | | |
| Sodium | mg/L | 200 | AO | 101 | 94.4 | 112 | 103 | 109 | 128 | 85.1 | 120 | 114 | 13.3 | 1.65 | 11.9 | 13.8 | 13.1 | 14.1 | | |
| Potassium | mg/L | NV | NA | NV | 36.8 | 43.6 | 44.0 | 34.1 | 40.8 | 56.1 | 62.3 | 53.3 | 0.81 | <0.50 | 3.80 | 4.99 | 4.53 | 4.95 | | |
| Iron | mg/L | 0.3 | AO | 1.83* | 0.049 | 40.7 | 0.082 | 0.080 | 0.081 | 0.086 | 0.15 | 0.11 | 0.035 | 0.022 | 0.017 | 0.036 | <0.020 | <0.020 | | |
| Manganese | mg/L | 0.05 | AO | 0.31* | 0.62 | 1.16 | 0.81 | 0.89 | 0.75 | 1.11 | 1.55 | 1.13 | 0.16 | 0.059 | 0.36 | 0.04 | 0.63 | 0.041 | | |
| Boron | mg/L | 5.0 | IMAC | 1.26 | 0.82 | 1.34 | 1.27 | 0.93 | 1.29 | 1.44 | 1.94 | 1.63 | 0.037 | 0.023 | 0.083 | 0.16 | 0.11 | 0.16 | | |
| Ammonia | mg/L | NV | NA | NV | 21.0 | 48.8 | 30.6 | 30.4 | 60.7 | 74.0 | 63.5 | 90.5 | 0.17 | 0.10 | 0.03 | 0.03 | 0.13 | <0.02 | | |
| DOC | mg/L | 5.0 | AO | 30.2* | 42.8 | 41.4 | 29.8 | 43.3 | 45.6 | 27.0 | 56.9 | 51.8 | 6.9 | 17.4 | 14.2 | 13.8 | 18.0 | 20.8 | | |
| TKN | mg/L | NV | NA | NV | 22.4 | 53.5 | 35.6 | 31.1 | 61.4 | 74.0 | 66.0 | 344.00 | 2.96 | 0.79 | 1.77 | 4.40 | 3.55 | 1.88 | | |

Notes:

- 1. ODWS = Ontario Drinking Water Standards (June 2003, Revised June 2006)
- 2. RUC = Reasonable Use Criteria. *RUC shown in italics represents parameters in which the background concentration exceeds the ODWS and the 95th-percentile concentration is used.
- 3. AO = Aesthetic Objective; OG = Operational Guideline; MAC = Maximum Acceptable Concentration; IMAC = Interim Maximum Acceptable Concentration
- 4. Cb = Background concentration calcuated using all available data collected from well OW-1 by various consultants from 2001 to November 2017.
- 5. NV = No Value Specified
- 6. Values in bold represent results greater than the Reasonable Use Criteria
- 7. Shaded values represent results greater than the ODWS.
- 8. Samples analyzed by AGAT Laboratories Ltd.
- 9. mg/L = milligrams per litre; μS/cm = microsiemens per centimeter
- 10. [S] = well screened primarily in the shallow sand unit; [SL] = well screened primarily in the silt loam unit; OW7S/D and OW10S/D are well couplets screened in the shallow sand (S) and deeper sand (D) units

TABLE 5
COMPARISON OF GROUNDWATER QUALITY AT THE ESTABLISHED
TRIGGER LOCATIONS TO THE TRIGGER LEVELS

| | Indicator Parame | tor | Chloride | Sodium | Sulphate | Boron | Nitrate | Alkalinity | |
|---------|------------------|------|-----------|------------|-------------|--------------|--------------|------------|--|
| | indicator Parame | eter | (in mg/L) | (in mg/L) | (in mg/L) | (in mg/L) | (in mg/L) | (in mg/L) | |
| | Background | S | 1.2 - 5.4 | 0.90 - 2.4 | 12.7 - 42.5 | <0.01 - 0.06 | <0.05 - 0.34 | 185-257 | |
| | ODWS | | 250 | 200 | 500 | 5.0 | 10 | 500 | |
| | RUC | ž | 127 | 101 | 261 | 1.26 | 2.58 | 355 | |
| | T | | 2000000 | | | | | | |
| Trigger | OW-4, OW-5 & OW | /-6 | 102 | 81 | 209 | 1.01 | 2.06 | 284 | |
| Levels | (80% RUC) | | 102 | 01 | 200 | 1.01 | 2.00 | 204 | |
| | 14-Apr-11 | | 1.11 | 3.25 | 17.2 | | <0.05 | 222 | |
| | 01-Nov-11 | | 1.38 | 3.37 | 14.3 | | <0.05 | 236 | |
| | 11-Apr-12 | | 1.23 | 3.19 | 13.4 | | < 0.05 | 220 | |
| | 01-Nov-12 | | 1.32 | 3.60 | 7.92 | | < 0.05 | 223 | |
| | 15-Apr-13 | | 1.38 | 3.27 | 14.8 | | < 0.05 | 232 | |
| | 14-Nov-13 | | 1.28 | 3.58 | 10.9 | | < 0.05 | 218 | |
| | 12-May-14 | | 1.42 | 3.75 | 13.7 | | 0.46 | 235 | |
| | 29-Oct-14 | 5 | 1.52 | 3.23 | 13.5 | | <0.10 | 222 | |
| | 23-Apr-15 | | 1.40 | 3.20 | 13.2 | | <0.05 | 218 | |
| l | 29-Oct-15 | | 2.01 | 3.26 | 13.5 | | <0.10 | 232 | |
| | 21-Apr-16 | 5 | 1.45 | 3.30 | 25.7 | | <0.05 | 229 | |
| | 01-Nov-16 | | 1.24 | 3.01 | 12.7 | | < 0.05 | 224 | |
| | 25-Apr-17 | | 0.74 | 2.63 | 10.0 | | <0.05 | 194 | |
| | 20-Sep-17 | | 1.47 | 3.16 | 10.1 | | <0.05 | 235 | |
| OW-4 | 08-May-18 | | 1.70 | 2.70 | 16.0 | | <0.10 | 200 | |
| | 20-Nov-18 | | 4.41 | 4.88 | 14.8 | 0.031 | 0.12 | 233 | |
| | 29-Apr-19 | | 1.22 | 3.17 | 11.2 | <0.10 | <0.05 | 247 | |
| | 22-Oct-19 | | 1.46 | 3.24 | 12.0 | 0.085 | 0.14 | 221 | |
| | 25-Apr-20 | | 1.66 | 3.03 | 13.8 | 0.013 | <0.05 | 230 | |
| | 28-Oct-20 | | 1.58 | 3.10 | 11.0 | <0.002 | 0.18 | 218 | |
| | 04-May-21 | | 1.63 | 3.25 | 11.7 | 0.045 | <0.05 | 218 | |
| | 06-Oct-21 | | 1.29 | 2.76 | 10.9 | 0.033 | < 0.05 | 224 | |
| | 26-Apr-22 | | 1.35 | 2.95 | 13.3 | 0.034 | <0.05 | 204 | |
| | 27-Sep-22 | | 1.68 | 4.12 | 13.0 | 0.036 | <0.05 | 233 | |
| | 21-Apr-23 | | 1.73 | 3.29 | 13.4 | 0.026 | 0.05 | 221 | |
| | 28-Nov-23 | | 1.72 | 2.79 | 11.5 | 0.049 | 0.11 | 250 | |
| | 30-Apr-24 | | 1.44 | 3.10 | 11.6 | 0.040 | <0.05 | 257 | |
| | 12-Nov-24 | | 1.48 | 2.92 | 10.5 | 0.038 | <0.05 | 266 | |

TABLE 5
COMPARISON OF GROUNDWATER QUALITY AT THE ESTABLISHED
TRIGGER LOCATIONS TO THE TRIGGER LEVELS

| | Indicator Paramete | Chloride | Sodium | Sulphate | Boron | Nitrate | Alkalinity | |
|---------|--------------------|---|------------|-------------|--------------|--------------|----------------|--|
| r. | indicator Paramete | (in mg/L) | (in mg/L) | (in mg/L) | (in mg/L) | (in mg/L) | (in mg/L) | |
| | Background ൃ | 1.2 - 5.4 | 0.90 - 2.4 | 12.7 - 42.5 | <0.01 - 0.06 | <0.05 - 0.34 | 185-257 | |
| | Background ODWS | 250 | 200 | 500 | 5.0 | 10 | 500 | |
| | RUC Z | 127 | 101 | 261 | 1.26 | 2.58 | 355 | |
| | KUC – | 127 | 101 | 201 | 1.20 | 2.30 | 333 | |
| Trigger | OW-4, OW-5 & OW-6 | 102 | 81 | 209 | 1.01 | 2.06 | 284 | |
| Levels | (80% RUC) | | • • • | S | | 2.00 | 97-77-865 V.V. | |
| P | 14-Apr-11 | 60.4 | 14.8 | 82.5 | | <0.05 | 376 | |
| l | 01-Nov-11 | 34.6 | 12.9 | 65.2 | | <0.05 | 365 | |
| l | 11-Apr-12 | 24.0 | 9.15 | 35.3 | | <0.05 | 266 | |
| l | 01-Nov-12 | 32.0 | 11.9 | 54.0 | | <0.05 | 353 | |
| l | 15-Apr-13 | 28.6 | 12.4 | 74.5 | | <0.25 | 425 | |
| l | 14-Nov-13 | 66.5 | 15.7 | 57.4 | | <0.25 | 356 | |
| l | 12-May-14 | 46.3 | 15.9 | 75.0 | | <0.25 | 407 | |
| l | 29-Oct-14 | 77.3 | 16.6 | 65.2 | | <0.25 | 376 | |
| l | 23-Apr-15 | 116 | 18.7 | 72.6 | | <0.25 | 397 | |
| l | 29-Oct-15 | 192 | 22.1 | 77.0 | | <0.25 | 393 | |
| l | 24-Nov-15 | 233 | 28.1 | 58.8 | | <0.25 | 378 | |
| l | 21-Apr-16 | 91.4 | 18.7 | 68.1 | | <0.25 | 349 | |
| l | 01-Nov-16 | 264 | 27.7 | 57.8 | | <0.25 | 376 | |
| l | 25-Apr-17 | 161 | 20.3 | 48.0 | | <0.25 | 376 | |
| | 20-Sep-17 | 205 | 23.2 | 49.2 | | <0.25 | 341 | |
| OW-5 | 08-May-18 | 150 | 26.0 | 49.0 | | <0.10 | 370 | |
| l | 20-Nov-18 | 93.7 | 14.8 | 43.1 | 0.51 | <0.25 | 331 | |
| l | 29-Apr-19 | 82.9 | 17.1 | 37.2 | 0.54 | <0.25 | 369 | |
| | 22-Oct-19 | 115 | 13.4 | 28.9 | 0.33 | <0.25 | 282 | |
| | 25-Apr-20 | 146 | 21.4 | 49.8 | 0.68 | <0.25 | 341 | |
| | 28-Oct-20 | 212 | 22.8 | 55.7 | 0.82 | <0.25 | 337 | |
| | 04-May-21 | 156 | 10.6 | 47.6 | 0.49 | <0.25 | 299 | |
| l | | Minor regrading efforts completed in the southerly area of the landfill | | | | | | |
| | 06-Oct-21 | 77.1 | 17.0 | 43.1 | 0.94 | <0.05 | 349 | |
| | 26-Apr-22 | 34.3 | 12.6 | 36.4 | 0.61 | <0.05 | 324 | |
| | 27-Sep-22 | 23.7 | 9.95 | 47.6 | 0.43 | <0.05 | 380 | |
| | 21-Apr-23 | 19.3 | 8.54 | 50.4 | 0.34 | 0.08 | 353 | |
| | 28-Nov-23 | 14.7 | 6.54 | 57.0 | 0.35 | 0.11 | 414 | |
| | 30-Apr-24 | 14.2 | 8.75 | 74.8 | 0.48 | <0.05 | 485 | |
| | 12-Nov-24 | 12.7 | 9.12 | 89.7 | 0.55 | <0.05 | 553 | |

TABLE 5 COMPARISON OF GROUNDWATER QUALITY AT THE ESTABLISHED TRIGGER LOCATIONS TO THE TRIGGER LEVELS

| | Indicator Parame | eter | Chloride | Sodium | Sulphate | Boron | Nitrate | Alkalinity |
|-----------------------------|------------------|------|-----------|------------|-------------|--------------|--------------|------------|
| | | | (in mg/L) | (in mg/L) | (in mg/L) | (in mg/L) | (in mg/L) | (in mg/L) |
| | Background | S | 1.2 - 5.4 | 0.90 - 2.4 | 12.7 - 42.5 | <0.01 - 0.06 | <0.05 - 0.34 | 185-257 |
| Background 9 to ODWS to RUC | | 250 | 200 | 500 | 5.0 | 10 | 500 | |
| RUC | | 127 | 101 | 261 | 1.26 | 2.58 | 355 | |
| Trigger | OW-4, OW-5 & OW | 16 | | | | | | |
| Trigger Levels | (80% RUC) | -6 | 102 | 81 | 209 | 1.01 | 2.06 | 284 |
| 8 | 14-Apr-11 | | 30.6 | 19.9 | 22.1 | | 0.12 | 363 |
| | 01-Nov-11 | | 22.0 | 15.4 | 12.5 | | <0.05 | 335 |
| | 11-Apr-12 | | 26.3 | 14.6 | 15.3 | | 0.15 | 337 |
| | 01-Nov-12 | | 27.1 | 13.9 | 12.8 | | 0.11 | 329 |
| | 15-Apr-13 | | 37.0 | 20.5 | 22.1 | | 0.44 | 320 |
| | 14-Nov-13 | | 29.4 | 17.9 | 16.5 | | 0.12 | 325 |
| | 12-May-14 | | 30.9 | 18.4 | 20.8 | | <0.25 | 332 |
| | 29-Oct-14 | 5 | 35.3 | 23.3 | 15.5 | | <0.25 | 361 |
| | 23-Apr-15 | | 36.4 | 23.5 | 21.0 | | <0.25 | 345 |
| | 29-Oct-15 | | 56.1 | 38.3 | 24.0 | | <0.25 | 415 |
| | 21-Apr-16 | 5 | 35.0 | 19.5 | 28.5 | | <0.25 | 352 |
| | 01-Nov-16 | | 34.8 | 25.5 | 24.4 | | 0.91 | 379 |
| | 25-Apr-17 | | 26.9 | 20.3 | 24.2 | | <0.25 | 339 |
| OW-6 | 20-Sep-17 | | 44.4 | 37.3 | 22.4 | | 0.27 | 490 |
| | 20-Nov-18 | | 31.9 | 20.2 | 34.6 | 0.16 | <0.25 | 388 |
| | 29-Apr-19 | | 25.2 | 18.9 | 28.3 | 0.114 | <0.25 | 411 |
| | 22-Oct-19 | | 23.4 | 15.9 | 33.2 | 0.176 | <0.10 | 359 |
| | 25-Apr-20 | | 23.9 | 13.0 | 43.8 | 0.111 | <0.25 | 342 |
| | 28-Oct-20 | | 24.7 | 15.0 | 35.6 | 0.163 | 0.17 | 366 |
| | 04-May-21 | | 27.2 | 14.4 | 22.3 | 0.146 | <0.10 | 325 |
| | 06-Oct-21 | | 22.7 | 15.4 | 29.6 | 0.227 | 0.11 | 367 |
| | 26-Apr-22 | | 21.0 | 17.3 | 30.7 | 0.137 | 0.21 | 306 |
| | 27-Sep-22 | | 25.8 | 15.1 | 28.9 | 0.200 | <0.05 | 388 |
| | 21-Apr-23 | | 21.0 | 11.9 | 38.2 | 0.083 | <0.05 | 345 |
| | 28-Nov-23 | | 21.7 | 13.8 | 32.9 | 0.163 | 0.09 | 420 |
| | 30-Apr-24 | | 20.1 | 13.1 | 34.6 | 0.111 | <0.05 | 416 |
| | 12-Nov-24 | | 23.1 | 14.1 | 25.6 | 0.158 | <0.05 | 512 |
| Trimeran | OW-9 | | | | | | | |
| Trigger Levels | (100% RUC) | | 127 | 101 | 261 | 1.26 | 2.58 | 355 |
| 0111.0 | 01-Nov-12 | | 1.19 | 4.66 | 4.04 | NM | <0.05 | 224 |
| OW-9 | 15-Apr-13 | | 1.16 | 4.05 | 1.28 | NM | <0.05 | 233 |

Notes:

- 1. ODWS = Ontario Drinking Water Standards
- 2. RUC = Reasonable Use Criteria
- 3. mg/L = milligrams per litre
- 4. The Contingency Plan is to be implemented when two or more of the same parameters exceed the trigger levels at the same trigger location for two consecutive monitoring events (as per Condition 5.1 of the ECA Notice 4).
- 5. Results reported appear to have been erroneously identified. Based on the analytical data, the results for OW4 and OW6 are assumed to be the reverse of that reported on the COC.

Environmental Compliance Approval No. A272301 Eastnor Landfill Site: Annual Monitoring Report (2024) Municipality of Northern Bruce Peninsula, Ontario May 20, 2025

Figures


Figure 1: Site Location Map


Figure 2: Site Layout


Figure 3: Site Layout Showing Monitoring Locations

Figure 4: Shallow Groundwater Flow & Chloride Concentration Distribution (Fall 2024)

Figure 5: Groundwater Flow: Deeper Sand Unit (Fall 2024)







2402867 Annual Monitoring Report Lots 17 & 18, Conc. 2 W.B.R. Municipality of Northern Bruce Peninsula



LEGEND

PROPERTY LINE

LIMIT OF HISTORICALLY APPROVED AND FILLED LANDFILL AREA (3.3 ha)

PROPOSED LANDFILL EXPANSION AREA

EXISTING TREELINE

MONITORING WELL

BH2 (15)

BOREHOLE (2015)

ACTIVE AREA

NOTES:

- 1. LOCATION OF PROPERTY LINES ARE APPROXIMATE.
- 2. A 0.7 ha* PORTION OF THE HISTORICALLY APPROVED 3.3 ha LANDFILL AREA WAS OBSERVED TO CONTAIN NO WASTE. THEREFORE THE HISTORICAL WASTE PLACEMENT WAS LIMITED TO AN AREA OF 2.6 ha.


SCALE = 1:2,500 APRIL 2025


SITE LAYOUT SHOWING MONITORING LOCATIONS

EASTNOR LANDFILL

Figure No. 3







Environmental Compliance Approval No. A272301 Eastnor Landfill Site: Annual Monitoring Report (2024) Municipality of Northern Bruce Peninsula, Ontario May 20, 2025 Appendix A Environmental Compliance Approval No. A272301

CONTENT COPY OF ORIGINAL



Ministry of the Environment Ministère de l'Environnement AMENDED PROVISIONAL CERTIFICATE OF APPROVAL
WASTE DISPOSAL SITE
NUMBER A272301

Issue Date: February 20, 2007

The Corporation of the Municipality of Northern Bruce Peninsula

Rural Route, No. 2

Lions Head, Ontario N0H 1W0

Site Location:

Eastnor Landfill Site

Lot 18 &17 pt., Concession 2 W.B.R.

Northern Bruce Peninsula Municipality, County of Bruce

You have applied in accordance with Section 27 of the Environmental Protection Act for approval of:

the establishment and use of a 81 hectare (200 acre) hectare Waste Disposal Site consisting of a 9.5 hectare (24 acre) landfill and a transfer station for recyclable wastes.

For the purpose of this Certificate of Approval and the terms and conditions specified below, the following definitions apply:

- (a) "Act" means the Environmental Protection Act, R.S.O. 1990, C.E-19, as amended;
- (b) "buffer" means those lands between the limit of fill and the boundaries of the property owned by the Owner,
- (c) "Certificate" means this Provisional Certificate of Approval;
- (d) "clean wood" means tree branches, leaves and brush, and wood that is not contaminated with chromated copper arsenate, ammoniacal copper arsenate, pentachlorophenol or creosote, has no hardware, fittings or attachments unless they are predominantly wood or cellulose, is not an upholstered article, and does not have any non-cellulose surfaces adhered to it;
- (e) "Director" means Director, Environmental Assessment and Approvals Branch, Ontario Ministry of the Environment;
- (f) "District Manager" means District Manager, Owen Sound Office, Ontario Ministry of Environment;
- (g) "limit of fill" means the area in which waste is approved for final disposal according to this Certificate limited to the area shown as 'limit of fill' and 'area a area of future landfilling' on Item 4 in Schedule "A" attached to this Certificate;
- (h) "Ministry" and "MOE" means the Ontario Ministry of the Environment:
- (i) "OWRA" means the Ontario Water Resources Act, R.S.O. 1990, c. O.40, as amended;
- (j) "Ontario Regulation 347" means Ontario Regulation 347 R.R.O. 1990, General Waste Management, as amended from time to time, made under the Act;
- (k) "Ontario Regulation 189" means Ontario Regulation 189/94, Refrigerants, or as amended, made under the Act;
- (l) "Ontario Regulation 903" means Ontario Regulation 903 R.R.O. 1990, Wells, amended to Ontario Regulation 128/03, made under the *OWRA*;
- (m) "Operator" means any person, other than the Owner's employees, authorized by the Owner as having access to the Site during non-operating hours for the purpose of depositing waste at the Site and has been trained in accordance with Condition 38;

CONTENT COPY OF ORIGINAL

- (n) "Owner" means the Municipality of Northern Bruce Peninsula and any person(s) contracted by the Municipality of Northern Bruce Peninsula to manage operations on the Site on behalf of the Owner;
- (o) "PWQO" means the Provincial Water Quality Objectives included in the July 1994 publication entitled Water Management Policies, Guidelines, Provincial Water Quality Objectives, as amended from time to time;
- (p) "recyclable waste" means solid, non-hazardous waste that is segregated for transfer to an end user thereby diverting it from final disposal and may include, but is not limited to, cardboard, boxboard, newspaper, used beverage/food containers, plastics, metal and bale wrap;
- (q) "RUP" means the Reasonable Use Policy (Guideline B-7) of the Ministry of the Environment;
- (r) "Site" means the 81 hectare property located at Lots 17 and 18, concession 2 WBR, Municipality of Northern Bruce Peninsula, Bruce County;
- (s) "tire units" means a tire weighing 12 kilograms or less. Each tire weighing 12 kilograms or more is the number of tire units that results from dividing 12 into the number of kilograms that the tire weighs. For tires which have been chipped, shredded or ground, each 12 kilograms is a tire unit;
- (t) "white goods which contain refrigerants" means white goods which contain, or may contain refrigerants, and which include, but is not restricted to, refrigerators, freezers and air-conditioning systems.

You are hereby notified that this approval is issued to you subject to the terms and conditions outlined below:

TERMS AND CONDITIONS

General

- 1. This Certificate supersedes and replaces Provisional Certificate Number A272301 issued September 24, 1980.
- 2. The requirements specified in this *Certificate* are requirements under the *Act*. Issuance of this *Certificate* in no way abrogates the *Owner's* legal obligations to take all reasonable steps to avoid violating other applicable provisions of this legislation and other legislation and regulations.
- 3. The requirements of this Certificate are severable. If any requirements of this Certificate, or the application of any requirement of this Certificate to any circumstance, is held invalid, the application of such requirement to other circumstances and the remainder of this Certificate shall not be affected in any way.
- 4. The *Owner* must ensure compliance with all terms and conditions of this *Certificate*. Any non-compliance constitutes a violation of the *Act* and is grounds for enforcement.
- 5. (a) The Owner shall, forthwith upon request of the Director, District Manager, or Provincial Officer (as defined in the Act), furnish any information requested by such persons with respect to compliance with this Certificate, including but not limited to, any records required to be kept under this Certificate; and
 - (b) In the event the *Owner* provides the *Ministry* with information, records, documentation or notification in accordance with this *Certificate* (for the purposes of this condition referred to as "Information"),
 - (i) the receipt of Information by the Ministry;
 - (ii) the acceptance by the *Ministry* of the Information's completeness or accuracy; or
 - (iii) the failure of the *Ministry* to prosecute the *Owner*, or to require the *Owner* to take any action, under this *Certificate* or any statute or regulation in relation to the Information; shall not be construed as an approval, excuse or justification by the *Ministry* of any act or omission of the *Owner* relating to the Information, amounting to non-compliance with this *Certificate* or any statute or regulation.



- 6. The Owner shall allow Ministry personnel, or a Ministry authorized representative(s), upon presentation of credentials, to;
 - (a) carry out any and all inspections authorized by Section 156, 157 or 158 of the *Act*, Section 15, 16 or 17 of the *OWRA*, or Section 19 or 20 of the *Pesticides Act, R.S.O. 1990*, as amended from time to time, of any place to which this *Certificate* relates; and,
 - (b) without restricting the generality of the foregoing, to:
 - (i) enter upon the premises where records required by the conditions of this Certificate are kept;
 - (ii) have access to and copy, at reasonable times, any records required by the conditions of this *Certificate*;
 - (iii) inspect at reasonable times any facilities, equipment (including monitoring and control equipment), practices, or operations required by the conditions of this *Certificate*; and
 - (iv) sample and monitor at reasonable times for the purposes of assuring compliance with the conditions of this *Certificate*.
- 7. Where there is a conflict between a provision of any document referred to in Schedule "A", and the conditions of this *Certificate*, the conditions in this *Certificate* shall take precedence. Where there is a conflict between the documents listed in Schedule "A", the document bearing the most recent date shall prevail.
- 8. Any information relating to this *Certificate* and contained in *Ministry* files may be made available to the public in accordance with the provisions of the *Freedom of Information and Protection of Privacy Act*, R.S.O. 1990, C. F-31.
- 9. All records and monitoring data required by the conditions of this *Certificate* must be kept on the *Owner's* premises for a minimum period of five (5) years from the date of their creation.

Certificate of Prohibition

- 10. (a) Pursuant to Section 197 of the *Act*, no person having an interest in the *Site* shall deal in any way with the *Site* without first giving a copy of this *Certificate* to each person acquiring an interest in the *Site* as a result of the dealing.
- (b) Two copies of a completed Certificate of Prohibition, containing a registerable description of the *Site*, shall be submitted to the *Director* for the *Director*'s signature within 90 calendar days of the date of this *Certificate*.
- (c) The Certificate of Prohibition shall be registered in the appropriate land registry office on title to the *Site* by the *Owner* within 30 calendar days of receiving the Certificate of Prohibition signed by the *Director*, and a duplicate registered copy shall be submitted to the *Director*.

Transferral or Encumbrance of Site

11. No portion of this *Site* shall be transferred or encumbered prior to or after closing of the *Site*, unless the *Director* is notified in advance in writing and is satisfied with the arrangements made to ensure that all terms and conditions of this *Certificate* will be carried out.

Landfill Design and Operations

12. Except as otherwise provided by these Conditions, the *Site* shall be designed, developed, used, maintained and operated, and all facilities, equipment and fixtures shall be built and or installed in accordance with the Application for a Certificate of Approval for a Waste Disposal Site dated December 9, 2003, and supporting documentation, and plans and specifications listed in Schedule "A".

Service Area

13. Only wastes generated from within the geographic boundaries of Municipality of Northern Bruce Peninsula and waste, limited to bale wrap, generated within the geographic boundaries of Manitoulin Island may be received at this *Site*. No waste shall be received for disposal at this *Site* from outside the approved service area.



Site Capacity

- 14. (a) The total approved waste disposal capacity of the Site shall be limited to 103,500 m³.
- (b) The Owner shall not exceed the approved capacity of 103,500 m³ unless approved by the Director, and
- (c) The Owner shall not exceed the final contours as shown in Item 6, Schedule "A".

Operating Hours

- 15. The Owner shall set operational hours which provides an adequate level of service to receive waste from the general public. The hours of operation:
- (a) shall be any day of the week during daylight hours; and
- (b) may be changed by the *Owner* at any time provided that the hours are correctly posted at the *Site* gate and that suitable public notice is given of any change.
- 16. No waste shall be received at the *Site* except under the supervision of an attendant or Operator that has been trained in accordance with Condition 38.
- 17. During non-operating hours, the Site gates will be locked or otherwise secured against access by unauthorized persons.
- 18. During non-operating hours, the *Owner* may conduct equipment maintenance, administrative functions and on-Site activity (compaction, covering, grading and similar operations) other than waste disposal by the general public as required. Transfer of *recyclable* waste during non-operating hours is permitted under the supervision of a site attendant or *Operator*.

Signage and Security

- 19. A sign shall be posted at the entrance gate of the Site with the following information:
 - (a) name of the Site and Owner;
 - (b) Certificate number for the Site;
 - (c) days and hours of operation;
 - (d) allowable and prohibited waste types;
 - (e) a 24 hours telephone number to contact the Owner in the event of an emergency or complaint;
 - (f) warning against unauthorized access and against dumping outside the Site.
- 20. The Owner shall ensure that:
 - (a) access to the Site is restricted by fencing and/or natural features;
 - (b) fencing and lockable gate are kept in good repair;
 - (c) the Site is screened from public view on all sides.
- 21. The Owner shall maintain the existing natural brush around the perimeter of the Site to provide a visual screen.


Waste Types

22. Only solid non-hazardous municipal waste shall be received for disposal at this *Site*. No liquid industrial waste or hazardous waste, as designated under *Ontario Regulation 347*, shall be disposed of at the *Site*.

Waste Placement

- 23. No waste shall be landfilled outside of the *limit of fill* area as shown on Map 3, Revision 5 Existing Conditions November 11, 2003, plotted June 3, 2004 (Item 4 in Schedule "A" attached to this *Certificate*).
- 24. The *buffer* shall not be used for waste disposal but may be used for receiving and recording waste arrivals, monitoring, surface water management, storing cover and granular type materials, the operation of other approved ancillary waste management activities or other activities not related to waste management as identified by the *Owner* in Item 8 of Schedule

CONTENT COPY OF ORIGINAL



- 25. The *Owner* shall deposit waste in the *limit of fill* using a bank dumping method and/or use of an area ramp style method as described in Section 2.1 Method of Operation referenced as Item 3 in Schedule "A".
- 26. (a) The Owner shall mark the boundary of the *limit of fill* and the markings shall be maintained so as to be visible throughout the year.
- (b) The *Owner* shall place grade stakes delineating a 4:1 slop at the active face of the landfill and the grade stakes shall be reviewed and updated at least annually to ensure that a 4:1 slope is maintained.
- 27. The Owner shall ensure that waste is deposited in the limit of fill as follows:
 - (a) no waste shall be deposited in standing water;
 - (b) no waste shall be deposited within 30 meters of the wetland or watercourse;
 - (c) waste shall be deposited in a manner that minimizes the area of exposed waste at the active face of the landfill;
 - (d) all waste shall be deposited at the active face of the landfill except for waste that is segregated for the purpose of diversion through recycling or reuse or for burning.
- 28. Recyclable waste shall be stored in clearly labelled areas, segregated by barriers where practicable, in amounts and in a manner which does not create a nuisance or danger including but not limited to:
 - (a) brush and clean lumber shall be placed in a cleared area no larger than 1000 m² and a height of 3 metres or less, with a minimum of 30 m separation distance to all other wastes, flammable materials and buildings;
 - (b) stumps shall be placed in a cleared area no larger than 2000 m² with a maximum height of 3 meters;
 - (c) white goods and marketable scrap metals, not to exceed 100 tonnes, shall be placed on the ground surface or in roll-off containers in a designated area;
 - (d) cardboard, plastic, boxboard, steel/aluminium cans and other *recyclable waste* which may become windblown litter, shall be placed in designated containers;
 - (e) propane tanks shall be stored on the ground surface in an area no larger than 500 m² in a manner which minimizes the potential for cylinder valves to be damaged/broken;
 - (f) vehicular batteries shall be stored in a segregated storage location which is covered to provide shelter from precipitation and is equipped with spill containment; and
 - (g) tires shall not exceed 700 tire units and shall be stored as follows:
 - (i) the stockpile shall not exceed a volume of 45 m³;
 - (ii) the stockpile shall be located a minimum of 15 metres from the property line, any buildings and the active landfilling area;
 - (iii) the stockpile shall be separated from other waste piles by a minimum of 6 metres; and
 - (iv) an area around stockpile of no less than 4.5 metres shall be kept free of vegetation

29. The Owner shall ensure that:

- (a) no waste other than segregated brush, lumber and clean wood shall be burned at this Site;
- (b) atmospheric conditions are suitable for burning. Specifically burning shall not take place when:
 - (i) rain or fog is present;
 - (ii) wind speeds are high or wind directions are changing frequently; or
 - (iii) a Smog Alert Advisory has been issued.
- (c) an area of no less than 4.5 m around the burn pit is kept free of vegetation;
- (d) access to the burning area by the public and other unauthorized personnel is prohibited when burning is carried out;
- (e) no burning is to occur without the continuous supervision of the attendant;
- (f) the Chief Fire Official has been notified of the designated date and time of the burn in accordance with Municipality of Northern Bruce Peninsula By-Law Number 2000-24 as amended; and



(g) the fire shall be fully extinguished at the end of the day.

30. The Owner shall ensure that:

- (a) all white goods which contain refrigerants accepted at the Site, which have not been tagged by a licensed technician to verify that the equipment no longer contains refrigerants, are stored in an upright position and in such a manner as to allow for the safe handling and removal of refrigerants as required by Ontario Regulation 189;
- (b) the Owner shall ensure that refrigerant is removed by a licensed technician, in accordance with *Ontario Regulation 189*, prior to shipping white goods which contain refrigerants off-Site; and
- (c) a detailed log of all white goods which contain refrigerants received is maintained which includes the following information:
 - (i) date of the record;
 - (ii) types, quantities and source of white goods which contain refrigerants received;
 - (iii) destination of the white goods; or
 - (iv) the details on removal of refrigerants, and the quantities and destination of the refrigerants transferred from the Site.

Cover

- 31. Cover material shall be applied as follows:
 - (a) Cover material consisting of a minimum of 0.15 m thickness of soil, or an alternate material approved in writing by the *District Manager*, shall be applied such that no waste material is exposed. Cover material shall be applied three
 - (3) times per week between June and October and once (1) per week between November and May. Any alternative cover material must be approved, in writing, by the *District Manager*;
 - (b) In landfilling areas where waste placement is below the final approved contours and landfilling is to be suspended for thirty (30) days or more, an interim cover consisting of a minimum of 0.30 m thickness of soil and/or sand shall be applied;
 - (c) In landfilling areas which are no longer in use (i.e. historical), a final cover of 0.60 m thickness of sand with an additional 0.15 m of topsoil (or equivalent which promotes natural growth) shall be applied; and
 - (d) Where existing cover material has eroded such that waste is exposed, the cover material shall be promptly replaced.
- 32. Final cover shall be applied progressively, as weather conditions permit, as each part of the *limit of fill* reaches its final grades. Vegetation of completed final cover using drought-resistant, low-nutrient requirement grass and legume blends which regenerate annually shall occur within one month of its placement and final grading, or as soon as weather permits.

Inspections

- 33. The Owner shall ensure that the following inspection schedule is adhered to:
 - (a) on each operating day, an inspection of the working face and storage areas;
 - (b) on a weekly basis, during the period between April 1st and November 30th, check the fence voltage and inspect the perimeter of the electric fencing for:
 - (i) signs of animal entry;
 - (ii) damage to fencing;
 - (iii) wire height and tension; and
 - (iv) vegetation growth.
 - (b) on a monthly basis, an inspection of the general condition of the Site, access road, signage, fencing and gate, and the amount of available cover material;
 - (c) on a semi-annual basis, an inspection of the monitoring wells and condition of the cover material; and
 - (d) on an annual basis, a field survey of the limit of fill area.

CONTENT COPY OF ORIGINAL

Nuisance Control

- 34. The *Site* shall be operated and maintained such that the vermin, vectors, dust, litter, odour, noise and traffic do not create a nuisance. Specifically, the *Owner* shall implement the vector and vermin control / management plan as described in Item 7 of Schedule "A". The plan shall remain in place until the *Site* has been closed.
- 35. The *Owner* shall minimize the amount of litter generated by placing plastic mesh fencing, or equivalent, around the active landfilling face if directed to do so, in writing, by the *District Manager*.
- 36. The *Owner* shall conduct litter pickup each operating day from June through October and as needed from November through May.
- 37. The *Owner* shall operate the electric fencing from April 1 to November 30 of each year unless environmental conditions (such as snow depth) dictate otherwise. The Owner shall maintain the electric fencing by:
 - (a) performing inspections required by Condition 33(b);
 - (b) ensuring that ground to bottom strand clearance is maintained at approximately 5 cm and no greater than 7 cm;
 - (c) ensuring proper wire tension;
 - (d) taking immediate additional deterrent approaches (use of stones, logs, electrified mats or additional wiring) where signs of animal entry are detected;
 - (e) clearing vegetation or other objects that may come in contact with charged strands.

Training

- 38. (a) The *Owner* shall ensure that all *Site* attendants and *Operators* have been adequately trained, and receive on-going annual re-fresher training, with respect to the following:
 - (i) terms, conditions and operating requirements of this Certificate;
 - (ii) use, operation, inspection and maintenance of any equipment to be used;
 - (iii) requirements of the Design and Operations manual;
 - (iv) record keeping procedures;
 - (v) Site inspection procedures;
 - (vi) emergency response procedures; and
 - (vii) complaints response procedure.
 - (b) The Owner shall maintain a written record of training provided which shall include:
 - (i) date of training;
 - (ii) name and signature of person who has been trained; and
 - (iii) description of the training provided.

Emergency Response

- 39. The Owner shall:
 - (a) have in place a written emergency response procedures which shall include, as a minimum, the following:
 - (i) response procedures to be undertaken in the event of a fire, spill or medical emergency;
 - (ii) a list of contingency equipment available in the event of an emergency;
 - (iii) names and telephone numbers of emergency responders;
 - (iv) a notification protocol, with names and telephone numbers of persons to be contacted including Municipality of Northern Bruce Peninsula personnel, MOE District Office, Spills Action Centre and fire department;
 - (v) a list of approved facilities where waste can be re-directed in the event of a process upset.
 - (b) ensure that the contingency equipment and materials outlined in Condition 39 (a) (ii) are in a good state of repair,

fully operational and immediately available to the attendant;

- (c) ensure that the *Site* attendant(s) is fully trained in the emergency response procedures and contingency equipment to be employed in the event of an emergency; and
- (d) review the contingency plan on an annual basis, as a minimum, to ensure that it is current. Specifically, the *Owner* shall ensure that the names and telephone numbers of the persons to be contacted as required under Condition 39 (a)(iii) and (iv) are up-to-date.
- 40. The *Owner* shall ensure that *Site* attendant(s) has access to a reliable means of summoning assistance (e.g. telephone, cellular phone, mobile radio) at all times.

Groundwater Monitoring

- 41. (a) Groundwater monitoring shall be conducted by the Owner in accordance with Schedule "B".
 - (b) Any future changes in the groundwater monitoring program shall be approved by the District Manager.
- 42. (a) In the event that:
 - (i) persistent leachate impacts, as defined in Section 6.1 of Item 3 of Schedule "A" are detected at well OW-4-00; or
 - (ii) the concentration of a leachate-related parameter increases for three consecutive monitoring events in well OW3; then
 - (b) the *Owner* shall install and monitor a fifth well near the southern property line and revise the leachate contingency plan accordingly.
- 43. (a) All monitoring wells which form part of any monitoring program shall be protected from damage.
- (b) Any groundwater monitoring wells that are damaged shall be repaired or replaced forthwith or properly abandoned in accordance with *Ontario Regulation 903*.
- (c) Any monitoring wells which are no longer required for monitoring or which need to be closed due to operational changes on the *Site*, shall be property abandoned in accordance with *Ontario Regulation 903*.

Record Keeping

- 44. The *Owner* shall maintain a written log of the following information:
 - (a) date;
 - (b) the type, amount and destination of recyclable waste transferred from the Site;
 - (c) waste refused and reason for refusal;
 - (d) record of inspections required under Condition 33;
 - (e) record of the litter collection required under Condition 36;
 - (f) details of any maintenance activities conducted under Condition 37;
 - (g) application of dust suppressent;
 - (h) description of any out-of service period, the reasons for the loss of service and action taken to restore and maintain service;
 - (i) details of any controlled burning;
 - (j) details of any complaints related to the operations of the Site.

Annual Monitoring Report

- 45. By May 31st of each year, the *Owner* shall submit to the *District Manager* an annual monitoring report covering the preceding calendar year. The report shall include the following:
 - (a) an estimation of the amount of waste deposited over the previous calendar year based on topographical surveys;

CONTENT COPY OF ORIGINAL

- (b) a summary of the amount of recyclable waste diverted from disposal;
- (c) an updated *Site* plan showing the location of *recyclable waste* storage areas, cover material stockpile and active landfill face;
- (d) a summary of operational problems experienced or complaints regarding operation of the *Site* received and their resolution;
- (e) a summary of the effectiveness of the electric fencing in preventing animal entry and recommendations for any changes to the electric fencing program or the vector and vermin control / management plan that may be necessary;
- (f) recommendations respecting any proposed changes in the operations of the Site;
- (g) a summary of inspections;
- (h) a plan of the Site monitoring locations;
- (i) tables outlining monitoring locations, analytical parameters sampled, and frequency of sampling;
- (j) an assessment of groundwater quality in relation to the trigger concentrations and the RUP;
- (k) conclusions of the monitoring data, a review of the adequacy of monitoring programs, recommendations for any changes to monitoring programs that may be necessary;
- (1) a summary of complaints made regarding Site operations, maintenance and monitoring; and
- (m) a statement as to compliance with all Conditions of this *Certificate* and with the inspections, monitoring and reporting requirements of the Conditions herein.
- 46. In the event that the results of the monitoring program are such that an off-site exceedance of the *RUP* or *PWQO* can reasonably be predicted to occur, the *Owner* shall include in the annual report:
 - (a) the details of any such predicted off-site exceedance, including the assumptions upon which the prediction is based:
 - (b) a discussion of the modifications, if any, to intended operations which would be necessary to prevent the predicted off-site exceedance;
 - (c) a discussion of the modifications, if any, which should be made to the monitoring program; and
 - (d) a discussion of other mitigation measures or contingency actions, if any, which may be necessary to prevent offsite impacts.

Closure Plan

- 47. Two years prior to *Site* closure, the *Owner* shall submit for the *Director's* approval a detailed closure plan. This plan shall include, but not limited to, the following subjects:
 - (a) proposed end use;
 - (b) final closure schedule;
 - (c) final contour configuration;
 - (d) landscaping;
 - (e) Site facilities (if any);
 - (f) rodent control;
 - (g) groundwater, surface water and landfill gas control; and
 - (h) post-closure inspection, maintenance, monitoring and reporting.

SCHEDULE "A"

This Schedule "A" forms part of Certificate of Approval No. A272301.

- 1. Application for a Provisional Certificate of Approval for a Waste Disposal Site, signed by Cathy Robins, CAO, Township of Eastnor, dated December 9, 2003.
- 2. Letter from W. Rydall, Public Works and Property Manager, Municipality of Northern Bruce Peninsula, to Environmental Assessment and Approvals Branch, dated February 18, 2004 re: maximum quantities for materials diverted from landfill.
- 3. Eastnor Waste Disposal Site, Municipality of Northern Bruce Peninsula, Plan of Development and Operation Addendum, prepared by Pride Schropp McComb, Inc., dated May 2004.

CONTENT COPY OF ORIGINAL

- 4. Map 3 Revision 5 Existing Conditions November 11, 2003, plotted June 3, 2004.
- 5. Township of Eastnor Waste Disposal Site, Hydrogeologic Assessment and Plan of Development and Operation, Prepared by Stanley Consulting Group Ltd., dated October 1998.
- 6. Map 5 Revision 8 Final Contours October 16, 2006, plotted November 3, 2006.
- 7. Municipality of Northern Bruce Peninsula, Eastnor Waste Disposal Site, Vector and Vermin Control/Management Plan, undated.
- 8. Letter from Mr. R. Deverell, Municipality of Northern Bruce Peninsula, to Environmental Assessment and Approvals Branch, dated January 4, 2007, providing additional comments on the draft Certificate including clarification of fire department exercises, storage of materials other than waste, municipal by-law with respect to open fires and pest control management.

SCHEDULE "B"

This Schedule "B" forms part of Certificate of Approval No. A272301.

Groundwater Monitoring Program

| Sampling Location | Parameters | Frequency | |
|------------------------------------|--|-------------------|--|
| OW-1-00, OW2-00, OW3-00, OW4-00 | water level, alkalinity, conductivity, pH, ammonia, hardness, calcium, iron, magnesium, manganese, phosphorous, potassium, sodium, chloride, nitrate, nitrite, phosphate, sulphate | spring and fall | |
| OW3-00 | BTEX | annually | |
| OW3-00 | VOC | every three years | |

The reasons for the imposition of these terms and conditions are as follows:

The reason for Condition 1 is to clarify that the previously issued Certificate of Approval No. A272301 issued on September 24, 1980 is no longer in effect and has been replaced and superseded by the Terms and Conditions stated in this Certificate.

The reason for Conditions 2, 3, 4, 5 and 8 is to clarify the legal rights and responsibilities of the Owner under this Certificate.

The reason for Condition 6 is to ensure that appropriate Ministry staff have ready access to the Site for inspection of facilities, equipment, practices and operations required by the conditions in this Certificate. This condition is supplementary to the powers of entry afforded a Provincial Officer pursuant to the Act and OWRA.

The reason for Condition 7 is to clarify how to interpret this Certificate in relation to the application and supporting documentation submitted by the Owner.

The reason for Condition 9 is to ensure the availability of records and drawings for inspection and information purposes.

Condition 10 is included, pursuant to subsection 197(1) of the Act, to provide that any persons having an interest in the Site are aware that the land has been approved and used for the purposes of waste disposal.

The reason for Condition 11 is to restrict potential transfer or encumbrance of the Site without the approval of the Director. Any transfer of encumbrance can be made only on the basis that it will not endanger compliance with this

Certificate.

The reason for Conditions 12, 44 and 45 is to ensure that the Site is designed, operated, monitored and maintained in accordance with the application and supporting documentation submitted by the Owner, and not in a manner which the Director has not been asked to consider.

The reason for Conditions 13 and 14 is to specify the approved areas from which waste may be accepted at the Site and the types and amounts of waste that may be accepted for disposal at the Site, based on the Owner's application and supporting documentation.

The reason for Condition 15 to specify the hours of operation for the Site and a mechanism for amendment of the hours of operation, as required.

The reason for Conditions 16 and 18 is to ensure that the Site is supervised and operated by properly trained staff.

Training will help ensure that operations do not result in a hazard or nuisance to the natural environment or any person.

The reason for Condition 17 is to minimize the risk of unauthorized entry and to ensure the Site is only operated in the presence of trained personnel and to ensure proper management of waste.

The reason for Condition 19 is to ensure that the public have the necessary contact information in the event of an emergency or complaint.

The reason for Condition 20 is to ensure that the Site is secure when unattended to prevent vandalism or theft.

The reason for Conditions 21, 29, 34, 35, 36 and 37 is to ensure that the Site is operated in a manner which does not result in a nuisance or a hazard to the health and safety of the environment or people.

The reason for Condition 22 is to ensure that only waste approved under this Certificate are received at the Site.

Conditions 23, 24, 25, 26, 27, 28 and 30 are included to ensure that waste storage and disposal are done in a manner which does not result in a nuisance or a hazard to the health and safety of the environment or people.

The reason for Condition 31 and 32 is to ensure that daily and intermediate cover is used to control potential nuisance effects, to facilitate vehicle access on the Site, and to ensure an acceptable appearance is maintained. The proper closure of a landfill requires the application of a final cover which is aesthetically pleasing, controls infiltration, and is suitable for the end use planned for the Site.

The reason for Conditions 33 and 43 is to ensure that all equipment and facilities are maintained in good working order.

The reason for Condition 38 is to ensure that the Owner's staff are properly trained in the operation of the equipment used at the Site and emergency response procedures.

The reason for Conditions 39 and 40 is to ensure that the Owner is prepared and properly equipment to take action in the event of a spill, fire or other operation upset.

The reason for Condition 41 is to demonstrate that the landfill impacts on the natural environment are acceptable. Regular monitoring allows for the analysis of trends over time and ensures that there is an early warning of potential problems so that any necessary remedial / contingency action can be taken.

The reason for Conditions 42 and 46 is to ensure that the Owner follows a plan with an organized set of procedures for identifying and responding to potential impacts from the operation of this Site.

The reason for Condition 47 is to ensure that the Site is closed in accordance with MOE standards and to protect the health and safety of the environment.



This Provisional Certificate of Approval revokes and replaces Certificate(s) of Approval No. A272301 issued on September 24, 1980

In accordance with Section 139 of the <u>Environmental Protection Act</u>, R.S.O. 1990, Chapter E-19, as amended, you may by written notice served upon me and the Environmental Review Tribunal within 15 days after receipt of this Notice, require a hearing by the Tribunal. Section 142 of the <u>Environmental Protection Act</u>, provides that the Notice requiring the hearing shall state:

- 1. The portions of the approval or each term or condition in the approval in respect of which the hearing is required, and;
- 2. The grounds on which you intend to rely at the hearing in relation to each portion appealed.

The Notice should also include:

- 3. The name of the appellant;
- 4. The address of the appellant;
- 5. The Certificate of Approval number;
- 6. The date of the Certificate of Approval;
- 7. The name of the Director;
- 8. The municipality within which the waste disposal site is located;

And the Notice should be signed and dated by the appellant.

This Notice must be served upon:

The Secretary* Environmental Review Tribunal 2300 Yonge St., 12th Floor P.O. Box 2382 Toronto, Ontario M4P 1E4 AND

The Director
Section 39, Environmental Protection Act
Ministry of Environment and Energy
2 St. Clair Avenue West, Floor 12A
Toronto, Ontario
M4V 1L5

* Further information on the Environmental Review Tribunal's requirements for an appeal can be obtained directly from the Tribunal at: Tel: (416) 314-4600, Fax: (416) 314-4506 or www.ert.gov.on.ca

The above noted waste disposal site is approved under Section 39 of the Environmental Protection Act.

DATED AT TORONTO this 20th day of February, 2007

Tesfaye Gebrezghi, P.Eng. Director Section 39, *Environmental Protection Act*

VP/

c: District Manager, MOE Owen Sound





Ministry of the Environment Ministère de l'Environnement

AMENDMENT TO PROVISIONAL CERTIFICATE OF APPROVAL WASTE DISPOSAL SITE

NUMBER A272301 Notice No. 1

Issue Date: December 8, 2009

The Corporation of the Municipality of Northern Bruce Peninsula

56 Lindsay Rd

Northern Bruce Peninsula, Ontario

N0H 1W0

Site Location: Eastnor Landfill Site

1252 West Road

Lot 18, part 17, Concession 2 W.B.R.

Northern Bruce Peninsula Municipality, County of Bruce

You are hereby notified that I have amended Provisional Certificate of Approval No. A272301 issued on February 20, 2007 for the establishment and use of a 81 hectare (200 acre) Waste Disposal Site consisting of a 9.5 hectare (24 acre) landfill and a transfer station for recyclable wastes., as follows:

Definition for wood waste disposal area is added to the Certificate:

"Wood Waste Disposal Area" is the area marked as "Proposed Wood Waste Disposal Area" in Figure 2 of Item 9 of Schedule "A".

Condition 14. (d) is hereby added.

14. (d) Not withstanding Condition 23, disposal of 39,000 cubic meters of wood waste in the 1.09 hectare area designated *Wood waste Disposal Area* is hereby approved. This volume of wood waste is in addition to the volume of waste approved under the Condition 14. (a).

Condition 41, 43 and Schedule "B" are revoked and replaced with the following:

41. LANDFILL MONITORING

Landfill Gas

(1) (a) The Owner shall ensure that any buildings or structures at the Site within 100 meters from the landfill foot print contain adequate ventilation systems to relieve any possible landfill gas accumulation. Routine monitoring for explosive methane gas levels shall be conducted in all buildings or structures at the Site, especially enclosed structures which at times are occupied by people located within 100 meters from the landfill foot print.

Compliance Limits

(2) The Site shall be operated in such a way as to ensure compliance with the Reasonable Use Guideline B-7 for the protection of the groundwater at the Site.

Groundwater Monitoring

- (3) The *Owner* shall monitor groundwater as per Items in Schedule "A" and approved by the Director.
- (4) A certified Professional Geoscientist or Engineer possessing appropriate hydrogeologic training and experience shall execute or directly supervise the execution of the groundwater monitoring and reporting program.

Groundwater Wells and Monitors

- (5) The *Owner* shall ensure that all groundwater monitoring wells which form part of the monitoring program are properly capped, locked and protected from damage.
- (6) Where landfilling is to proceed around monitoring wells, suitable extensions shall be added to the wells and the wells shall be properly re-secured.
- (7) Any groundwater monitoring well included in the on-going monitoring program that are damaged shall be assessed, repaired, replaced or decommissioned by the *Owner*, as required.
 - (a) The *Owner* shall repair or replace any monitoring well which is destroyed or in any way made to be inoperable for sampling such that no more than one regular sampling event is missed.
 - (b) All monitoring wells which are no longer required as part of the groundwater monitoring program, and have been approved by the *District Manager* for

abandonment, shall be decommissioned by the *Owner*, as required, in accordance with *O.Reg. 903*, that will prevent contamination through the abandoned well. A report on the decommissioning of the well shall be included in the Annual Report for the period during which the well was decommissioned.

Trigger Mechanisms and Contingency Plans

- (8) (a) Within six (6) months from the date of this Certificate, the Owner shall establish and submit to the District Manager, site-specific trigger mechanisms for surface water and groundwater at the Site.
 - (b) Within six (6) months from the date of this Certificate, the Owner shall submit to the District Manager for approval, details of a contingency plan to be implemented in the event that the surface water or groundwater quality exceeds the trigger mechanism.
 - (c) The Owner shall ensure that any proposed site-specific trigger levels for leachate impacts to groundwater and contingency plans are approved in advance by the Director via an amendment to this Certificate. The Owner may follow the same procedure as in conditions 41(12) to 41(14) to seek approval for the proposed trigger mechanisms and contingency plans.
- (9) In the event of a confirmed exceedence of a site-specific trigger level relating to leachate mounding or groundwater or surface water impacts due to leachate, the *Owner* shall immediately notify the *District Manager*, and an investigation into the cause and the need for implementation of remedial or contingency actions shall be carried out by the *Owner* in accordance with the approved trigger mechanisms and associated contingency plans.
- (10) If monitoring results, investigative activities and/or trigger mechanisms indicate the need to implement contingency measures, the *Owner* shall ensure that the following steps are taken:
 - (a) The Owner shall notify the District Manager, in writing of the need to implement contingency measures, no later than 30 days after confirmation of the exceedences;
 - (b) Detailed plans, specifications and descriptions for the design, operation and maintenance of the contingency measures shall be prepared and submitted by the *Owner* to the *District Manager* for approval; and
 - (c) The contingency measures shall be implemented by the *Owner* upon approval by the *District Manager*.
- (11) The Owner shall ensure that any proposed changes to the site-specific trigger levels for leachate impacts to groundwater, are approved in advance by the Director via an amendment to this Certificate. The Owner may follow the same procedure as in conditions 41(12) to 41(14) to seek approval for the changes to the trigger mechanisms

and contingency plans.

Changes to the Monitoring Plan

- (12) The Owner may request to make changes to the monitoring program(s) to the District

 Manager in accordance with the recommendations of the annual report. The Owner shall

 make clear reference to the proposed changes in separate letter that shall accompany the
 annual report.
- (13) Within fourteen (14) days of receiving the written correspondence from the *District Manager* confirming that the *District Manager* is in agreement with the proposed changes to the environmental monitoring program, the *Owner* shall forward a letter identifying the proposed changes and a copy of the correspondences from the *District Manager* and all other correspondences and responses related to the changes to the monitoring program, to the *Director* requesting the *Certificate* be amended to approve the proposed changes to the environmental monitoring plan prior to implementation.
- (14) In the event any other changes to the environmental monitoring program are proposed outside of the recommendation of the annual report, the *Owner* shall follow current ministry procedures for seeking approval for amending the *Certificate*.

Following items are added to the Schedule "A"

Schedule "A"

- 9. Report dated July 24, 2008 titled "Design and Operations Report, Proposed Woodwaste Disposal Site, Eastnor Landfill, Former Township of Eastnor, Municipality of Northern Bruce Penninsula, County of Bruce" prepared by Gamsby and Mannerow Limited.
- 10. 2008 Annual Progress Report for the Eastnor Waste Disposal Site, prepared by Gamsby and Mannerow, dated March 2009.
- 11. Letter dated September 14, 2009 from M.D. Nelson, M.Sc. P.Eng., Gamsby and Mannerow Limited to R. Munasinghe, Ministry of the Environment.
- 12. Letter dated October 30, 2009 from M.D. Nelson, M.Sc. P.Eng., Gamsby and Mannerow Limited to R. Munasinghe, Ministry of the Environment.

The reasons for this amendment to the Certificate of Approval are as follows:

- 1. The reason for condition 14 (d) is to approve the 1.09 hectare disposal area for wood waste.
- 2. Reasons for Condition 41 (1) are to ensure that off-site migration of landfill gas is monitored and all buildings at the *Site* are free of any landfill gas accumulation, which due to a methane gas component may be explosive and thus create a danger to any persons at the *Site*.

- 3. Condition 41(2) is included to provide the groundwater and surface water limits to prevent water pollution at the *Site*.
- 4. Conditions 41(3) and 41(4) are included to require the Owner to demonstrate that the Site is performing as designed and the impacts on the natural environment are acceptable. Regular monitoring allows for the analysis of trends over time and ensures that there is an early warning of potential problems so that any necessary remedial/contingency action can be taken.
- 5. Conditions 41(5), 41(6) and 41(7) are included to ensure the integrity of the groundwater monitoring network so that accurate monitoring results are achieved and the natural environment is protected.
- 6. Conditions 41(8) to 41(11) inclusive are added to ensure the *Owner* has a plan with an organized set of procedures for identifying and responding to potential issues relating to groundwater and surface water contamination at the *Site's* compliance point.
- 7. Reasons for conditions 41(12), 41(13) and 41(14) are included to streamline the approval of the changes to the monitoring plan, trigger mechanisms and contingency plans.

This Notice shall constitute part of the approval issued under Provisional Certificate of Approval No. A272301 dated February 20, 2007

In accordance with Section 139 of the <u>Environmental Protection Act</u>, R.S.O. 1990, Chapter E-19, as amended, you may by written notice served upon me and the Environmental Review Tribunal within 15 days after receipt of this Notice, require a hearing by the Tribunal. Section 142 of the <u>Environmental Protection Act</u>, provides that the Notice requiring the hearing shall state:

- 1. The portions of the approval or each term or condition in the approval in respect of which the hearing is required, and;
- 2. The grounds on which you intend to rely at the hearing in relation to each portion appealed.

The Notice should also include:

- The name of the appellant;
- The address of the appellant;
- The Certificate of Approval number;
- The date of the Certificate of Approval;
- The name of the Director;
- 8. The municipality within which the waste disposal site is located;

And the Notice should be signed and dated by the appellant.

This Notice must be served upon:

The Secretary*
Environmental Review Tribunal
655 Bay Street, 15th Floor
Toronto, Ontario
M5G 1E5

AND

The Director Section 39, Environmental Protection Act Ministry of the Environment 2 St. Clair Avenue West, Floor 12A

Toronto, Ontario M4V 1L5

* Further information on the Environmental Review Tribunal's requirements for an appeal can be obtained directly from the Tribunal at: Tel: (416) 314-4600, Fax: (416) 314-4506 or www.ert.gov.on.ca

The above noted waste disposal site is approved under Section 39 of the Environmental Protection Act.

DATED AT TORONTO this 8th day of December, 2009

THIS NOTICE WAS MAILED

ON Dec. 11, 2009

OC.
(Signed)

Tesfaye Gebrezghi, P.Eng.

Director

Section 39, Environmental Protection Act

RM/

e: District Manager, MOE Owen Sound Matt Nelson, Gamsby and Mannerow Limited √



Ministry of the Environment

PROVISIONAL CERTIFICATE OF APPROVAL FOR A WASTE DISPOSAL SITE

| i f 8 š | Provisional Certificate No272301 |
|---|--|
| <u> </u> | A CARLET |
| S 1 | Lion!s Head, Ontario |
| fo | r the |
| loc | cated Part. of Lot. 17. & .18., Concession 2. W.B.R., |
| •••• | Township of Eastnor |
| sut | eject to the following conditions |
| Tł | nat the operation of the disposal site be reviewed by the Waste Management Branch |
| F | |
| 3 6 | |
| G å | |
| : (1 | ;;,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,, |
| Service Pro- | This Provisional Certificate expires on the 20th to the second of the se |
| Marine series | This Provisional Certificate expires on the30th day ofJune |
| 7 2 | Dated this21stday ofDecember |
| 100 B | Director, Waste Management Branch |
| JU 10.21 | 10 1 |



PROVISIONAL CERTIFICATE OF APPROVAL This shade the summand to consider the summand of the summand to consider the summand to summand the summand to consider the summand the summand to consider the summand to consider the summand the

icate expires on the 31st



Ministry of the Environment

PROVISIONAL CERTIFICATE OF APPROVAL WASTE DISPOSAL SITE

Under The Environmental Protection Act, 1971 and the regulations and subject to the limitations thereof, this Provisional Cartificate of Approval is issued to:

> Township of Eastnor P.O. Box 40 Lion's Head, Ontario

for the use and operation of a 9.5 hectare Dump Site within a total area

all in accordance with the following plans and specifications: 1. Application and supporting information for a waste disposal site. 2. Site plan of disposal area dated Jan. 23/79. Letter to MDE S.W. Region from Township of Eastror Municipal Offices, Lion's Head, Cht. dated Jan. 25th, 1978 re: Waste Disposal Site - Twp. of Eastnor.

Located: 1ot 18 and Part of Lot 17, Concession 2 W.B.R., Eastnor Township County of Bruce

which includes the use of the site only for the disposal of the following categories of waste (NOTE: Use of the site for additional categories of wastes requires a new application and amendments to the Provisional Certificate of Approval) Domestic, commercial and 2% "other", limited to waste lumber and brush.

and subject to the following conditions:

1. No operation shall be carried out at the site after sixty days from this condition becoming enforceable unless this Certificate including the reasons for this condition has been registered by the applicant as an instrument in the appropriate Land Registry Office against title to the site and a duplicate registered copy thereof has been returned by the applicant to the Director.

Dated this 24th day of September

Director, Section 39

The Environmental Protection Act, 1971

Content Copy Of Original



Ministry of the Environment and Climate Change Ministère de l'Environnement et de l'Action en matière de changement climatique

AMENDMENT TO ENVIRONMENTAL COMPLIANCE APPROVAL

NUMBER A272301 Notice No. 2

Issue Date: June 14, 2016

Municipality of Northern Bruce Peninsula

56 Lindsay Road 5 Lions Head

Rural Route, No. 2

Northern Bruce Peninsula, Ontario

N0H 1W0

Site Location: Eastnor Landfill Site

1252 West Road

Lot 18, part 17, Concession 2 W.B.R.

Northern Bruce Peninsula Municipality, County of Bruce

You are hereby notified that I have amended Approval No. A272301 issued on September 24, 1980 for the establishment and use of a 81 hectare (200 acre) Waste Disposal Site consisting of a 9.5 hectare (24 acre) landfill and a transfer station for recyclable wastes, as follows:

I. Condition 41.(3) is hereby revoked and replaced as follows:

Groundwater Monitoring

41. (3) Groundwater monitoring shall be conducted by the Owner in accordance with Schedule "B".

II. Schedule "B" is hereby added as follows:

Schedule "B"

Groundwater Monitoring Program

| Monitoring Location and F | Monitoring Program | Parameters | | |
|---------------------------|--------------------------|-----------------|--------|---------|
| | | | Spring | Fall |
| OW-1 | Background | Fall Only | | IND* |
| OW-2 | Leachate - Closed Area | Fall Only | | COMP** |
| | В | | | |
| OW-3 | Downgradient | Fall Only | | IND |
| OW-4 | Downgradient/South | Spring and Fall | IND | IND |
| | Compliance Well | | | |
| OW-5 | South Compliance Well | Spring and Fall | IND | IND |
| OW-6 | Furthest Downgradient | Spring and Fall | IND | IND |
| | Well | | | |
| OW-7S | Downgradient of Acctive | Spring and Fall | IND | IND |
| | Area - Shallow | | | |
| OW-7D | Downgradient of Active | Fall Only | | IND |
| | Area - Deep | | | |
| OW-8 | Leachate - Active Area A | Spring and Fall | IND | COMP + |
| | | | | VOCs*** |

| OW-9 | Background | None | |
|--------|----------------------|-----------|---------|
| OW-10S | Background - Shallow | Fall Only | IND |
| OW-10D | Background - Deep | Fall Only | IND |

*IND is the Indicator List including alkalinity, conductivity, pH, ammonia, hardness, calcium, iron, magnesium, hardness, manganese, phosphorus, potassium, sodium, chloride, nitrate, nitrite, phosphate, sulphate, dissolved organic carbon and TKN.

**COMP is the Comprehensive List as per Column 1, Schedule 5: Inorganic Parameters for Groundwater and dissolved organic carbon.

***VOCs are Volatile Organics including once a year for BTEX and once every three years for VOCs. VOCs next analysis scheduled for 2018.

III. The following item is hereby added to Schedule "A":

13. Application, dated September 23, 2015, by Matthew Nelson of GM BluePlan Engineering Limited on behalf of the Municipality of Northern Bruce Peninsula, and all supporting information.

IV. The reason for this amendment to the Approval is as follows:

1. The reason for this amendment is to identify changes in the ground water monitoring program in accordance with item 13 of Schedule "A".

This Notice shall constitute part of the approval issued under Approval No. A272301 dated September 24, 1980

In accordance with Section 139 of the Environmental Protection Act, you may by written Notice served upon me and the Environmental Review Tribunal within 15 days after receipt of this Notice, require a hearing by the Tribunal. Section 142 of the Environmental Protection Act provides that the Notice requiring the hearing shall state:

- 1. The portions of the environmental compliance approval or each term or condition in the environmental compliance approval in respect of which the hearing is required, and;
- 2. The grounds on which you intend to rely at the hearing in relation to each portion appealed.

Pursuant to subsection 139(3) of the Environmental Protection Act, a hearing may not be required with respect to any terms and conditions in this environmental compliance approval, if the terms and conditions are substantially the same as those contained in an approval that is amended or revoked by this environmental compliance approval.

The Notice should also include:

- 3. The name of the appellant;
- 4. The address of the appellant;
- 5. The environmental compliance approval number;
- 6. The date of the environmental compliance approval;
- 7. The name of the Director, and;
- 8. The municipality or municipalities within which the project is to be engaged in.

And the Notice should be signed and dated by the appellant.

This Notice must be served upon:

The Secretary*
Environmental Review Tribunal
655 Bay Street, Suite 1500
Toronto, Ontario
M5G 1E5

AND

The Director appointed for the purposes of Part II.1 of the Environmental Protection Act Ministry of the Environment and Climate Change 135 St. Clair Avenue West, 1st Floor Toronto, Ontario M4V 1P5

* Further information on the Environmental Review Tribunal's requirements for an appeal can be obtained directly from the Tribunal at: Tel: (416) 212-6349, Fax: (416) 326-5370 or www.ert.gov.on.ca

The above noted activity is approved under s.20.3 of Part II.1 of the Environmental Protection Act.

DATED AT TORONTO this 14th day of June, 2016

Dale Gable, P.Eng.
Director
appointed for the purposes of Part II.1 of
the *Environmental Protection Act*

AV/

c: District Manager, MOECC Owen Sound Matthew Nelson P. Eng., GM BluePlan Engineering Limited, Municipality of Northern Bruce Peninsula



Ministry of the Environment and Climate Change Ministère de l'Environnement et de l'Action en matière de changement climatique

AMENDMENT TO ENVIRONMENTAL COMPLIANCE APPROVAL

NUMBER A272301

Notice No. 3

Issue Date: November 1, 2017

The Corporation of the Municipality of Northern Bruce Peninsula 56 Lindsay Road 5 R.R #2

Northern Bruce Peninsula, Ontario

N0H 1W0

Site Location: Eastnor Landfill Site

1252 West Road

Lots 17 and 18, Concession 2 W.B.R.

Northern Bruce Peninsula Municipality, County of Bruce

You are hereby notified that I have amended Approval No. A272301 issued on February 20, 2007 for the use and operation of a **9.5** hectare Waste Disposal Site within a total Site Area of **81** hectares, and subsequently amended by adding **1.09** ha to the approved waste Disposal Area for the disposal of wood waste, as follows:

CONTINUED USE AND DEVELOPMENT OF THE REMAINING PORTION OF THE APPROVED AREA OF THE SITE

Pursuant to Condition 14 of the Environmental Compliance Approval, A272301, dated February 20, 2007, approval is hereby granted for the continued use and development of the **remaining 6.2 ha.** waste fill area to the northwest of the Site, in accordance with the supporting documentation listed herein under Schedule "A" which forms part of this Environmental Compliance Approval, A272301, and subject to the terms and conditions listed herein.

DOCUMENTATION

The following documentation is added to Schedule "A" and forms part of the Environmental Compliance Approval No. A272301:

- 14. Letter dated March 23, 2017 from M. D. Nelson, GM Blue Plan Engineering to Dickson Odame-Osafo, Ministry of the Environment and Climate Change Re: Response to comments on this application, with the following selected relevant attachments:
 - Drawing No. 3 Existing Conditions & Conceptual Plan Eastnor Landfill, dated March 23,

2017.

- Drawing No. 5 Conceptual Final Contours Eastnor Landfill, dated March 23, 2017.
- Figure No. 8 Progression of Waste Placement Eastnor Landfill, dated November, 2015.
- 15. Environmental Compliance Approval Application, dated November 20, 2014, signed by William Rydall, Public Works and Property Manager, Municipality of Northern Bruce Peninsula
- 16. Report titled "Plan of Development and Operations Eastnor Landfill Site", dated November 28, 2014, prepared by GM Blue Plan Engineering.
- 17. Report titled "Design and Operations Report Wood Waste Disposal Site" Revised Footprint, Eastnor Landfill, dated November, 2015, prepared by GM Blue Plan Engineering.
- 18. Report titled "Hydrogeologic Investigation (Revision 1), Eastnor Landfill Site", dated November 28, 2014 (Revised December, 2015), prepared by GM Blue Plan Engineering.
- 19. Report titled "Trigger Mechanism And Contingency Plan Eastnor Landfill Site", dated May, 2010, prepared by GM Blue Plan Engineering.

For the purposes of this Environmental Compliance Approval and the terms and conditions specified herein, the following definitions apply:

DEFINITIONS

"Waste Fill Area" means the area on the surface of the waste disposal site beneath which or above which waste is disposed of by landfilling, including the existing original and north development areas of the Site, and wood waste disposal area of the Site.

You are hereby notified that this approval is issued to you subject to the terms and conditions outlined below:

TERMS AND CONDITIONS

1.0 GENERAL

Certificate of Requirement

- 1.1 Pursuant to Section 197 of the *EPA*, no person having an interest in the Site shall deal in any way with the Site without first giving a copy of this Approval to each person acquiring an interest in the Site as a result of the dealing.
- 1.2 Unless a Certificate of Requirement is otherwise registered in the Land Registry Office on title to the property, the Owner shall:

- (a) within sixty (60) calendar days from the date of issuance of this Approval, submit to the Director, a completed Certificate of Requirement containing a registerable description of the property, including any new buffer lands and supporting documents as follows:
 - (i) a plan of survey of the Site, including any new additional buffer/contaminant attenuation lands, prepared, signed and sealed by a licensed Ontario Land Surveyor;
 - (ii) proof of ownership; and
 - (iii) legal abstract of the property(s).
- (b) within fifteen (15) calendar days of receiving the Certificate of Requirement authorized by the Director, the Owner shall:
 - (i) register the Certificate of Requirement in the appropriate Land Registry Office on the title to the property(s), and
 - (ii) submit to the Director, copy to the District Manager, a written verification that the Certificate of Requirement has been duly registered on title.

2.0 <u>SITE DESIGN - CONTINUED USE AND DEVELOPMENT OF THE REMAINING</u> PORTION OF THE APPROVED AREA

Site Capacity

Condition 14 in the ECA dated February 20, 2007, is hereby revoked and replaced with New **Condition 2.1** as follows:

2.1 The total waste disposal **capacity** for the Site, including waste, wood waste, daily cover and interim cover, but excluding final cover system, shall be **652,500 cubic metres**, achieved through the development of the Site in accordance with the contours presented in Section 6.4 in Item 16 and shown on Drawing Nos. 3 and 5 dated March 23, 2017, attached to Item 14 of Schedule "A", attached to this Certificate.

Condition 23 in the ECA dated February 20, 2007, is hereby revoked and replaced with New Conditions 2.2 and 2.3 as follows:

2.2 No waste shall be landfilled outside the **limit of the 9.5 hectares waste fill area and/or the 1.09 hectares wood waste fill area.** The waste fill areas shall be surrounded by a minimum 30 metres wide buffer on all sides. The Site shall be developed in a progressive manner from south (Phase 1) to north (Phase 2), and landfilling shall be carried out sequentially in stages as shown on Figure 8, ("Progression of Waste Placement, dated July 2014), attached to Item 14 of Schedule "A", attached to this Certificate.

- No waste shall be landfilled below elevation 95.0 m base contour, within the new remaining areas of the Site, shown on Drawing No. 5, attached to Item 14 of Schedule "A" attached to this Certificate. The maximum elevation of the fill area, including final cover, shall be 105.0 metres (reference elevation). Final slopes above grade within the waste fill areas at the time of site closure, shall be within the range of 4H:1V (25%) and 20H:1V (5%) respectively on the sides and top areas.
- 2.4 Except as otherwise provided by these Conditions and subject to condition 2.5 below, the continued use of the landfill site into the new areas shall be designed, developed, operated, maintained and all facilities, including ancillary waste management facilities, equipment and fixtures, shall be installed in accordance with the supporting documentation, and plans and specifications listed in Schedule "A", attached to this Certificate.
- 2.5 Detailed hydrogeological investigation of the Site shall be prepared and submitted for the approval of the Director prior to commencement of development, use or operation of the new remaining portion of the waste fill area under consideration for this approval. The detailed hydrogeological investigation shall include as a minimum, comprehensive characterization of the Site to establish its background conditions both physically and chemically, and shall include information pertaining to the conditions and the suitability of the Site to receive waste, prior to placing waste in the new area.
- 2.6 Detailed updated plan of development and operations for the Site, shall be prepared and submitted for the approval of the Director prior to commencement of development, use and operation of the new remaining portion of the waste fill area under consideration for this approval. The detailed plan of development and operation shall replace Item 16 in Schedule A attached to this Approval and shall include, as a minimum, information pertaining to the operations of the Site and all other waste management activities on site, operational hours, nuisance management controls, monitoring and maintenance programs, service areas, etc.

3.0 SITE OPERATIONS

3.1 General - Hours of Operation

Condition 15 in the ECA dated February 20, 2007, is hereby revoked and replaced with New Condition 3.1 below.

3.1.1 The **Opening Hours** for receipt of waste for disposal at the Site shall be as described in Section 8.2 in Item 16 of Schedule "A", attached to this Certificate and summarized as follows:

November 1 to March 31:- Monday and Tuesday, 9:00 am to 5:00 pm;

April 1 to October 31:- Tuesday and Saturday, 9:00 am to 5:00 pm.

3.1.2 The hours of operation may be amended from time to time to accommodate seasonal unusual demand, subject to prior notification given to the District Manager, and the public, and the hours of operation posted at the Site gate.

3.2 Site Operations - Landfilling

Waste Placement

3.2.1 The Site development and operation by area ramp method, shall be carried forward into the development and operation of the remaining portion of the Site under consideration in this approval, as described in Section 7.1 in Item 16 of Schedule "A", attached to this Certificate. The waste in each area ramp (cell) shall be well compacted prior to placement of the next lift of waste or daily cover, or interim cover in the case of areas where landfilling is temporary discontinued for a period of 30 days or more.

Daily, Interim and Final Covers

3.2.2 Unless more frequent daily cover requirements dictate otherwise, due to increased rate of fill, the daily cover, and interim cover requirements specified in Condition 31 of the Certificate, shall be carried forward in the continued development and operation of the remaining portion of the Site under this Approval, as described in Section 7.5.1 in Item 16 of Schedule "A" attached to this Certificate.

Condition 31(c) in the ECA dated February 20, 2007, is hereby revoked and replaced with New Condition 3.2.3 as follows:

- 3.2.3 Final Cover As areas of the landfill reach final waste elevations, these areas shall be graded and final cover shall be installed progressively, and vegetated as soon as practically possible. The final cover shall consist of a 600 mm minimum thick soil having permeability not exceeding 1 x 10⁻⁶ cm/sec, or alternative, as approved by the Director, overlain by a minimum 150 mm thick organic soil (topsoil), and a vegetative cover, as described in Section 7.5.2 in Item 16 of Schedule "A", attached to this Certificate. Unless stability is confirmed otherwise, the final slopes of the final cover above grade shall not exceed 1V:4H on the sides, and not less than 1V:20H on the top.
- 3.3 <u>Site Operations Household Hazardous Waste (HHW) Facility</u>
- 3.3.1 Except as otherwise provided by these Conditions, the HHW Facility shall continue to be developed, operated, and maintained, and all facilities, equipment and fixtures shall be in accordance with Section 8.4 (iii v) in Item 16 of Schedule "A", attached to this Certificate.
- 3.3.2 The HHW Facility shall continue to receive only wastes which fall under the registered users of the Province of Ontario HWIN system, which shall include but not limited to the following:
 - (a) paints and coatings, including their thinners, lacquer, contact cement, paint strippers and degreasers and their containers;
 - (b) oil, oil filters and oil containers (30 litres or less);
 - (c) antifreeze and its containers;
 - (d) batteries, vehicular batteries to be stored in a segregated covered storage to provide shelter

- from precipitation and is equipped with spill containment;
- (e) pressurized containers, such as propane tanks, oxygen and helium tanks which shall be stored on the ground surface in an area not exceeding 500 m² in a manner which minimizes the potential for cylinder valves to be damaged; and
- (f) lawn fertilizers, pesticides and their containers.

3.3.3 The Municipality shall ensure that:

- (a) wastes received are handled, packaged, stored or secured so as not to pose any threat to the general public, Site personnel and the environment;
- (b) the operation of the HHW Facility does not interfere with any other activities associated with this Site;
- (c) trained personnel are on duty at all times during the operation of the HHW Facility.
- 3.3.4 No storage facilities other than those approved under this Approval shall be used. Fixed storage facilities shall not be moved, replaced or altered without the Director's approval.
- 3.3.5 All storage buildings and tanks shall be clearly marked indicating the type and nature of the hazardous waste stored. Signs shall be posted at points of access to the HHW Facility to warn that the area contains hazardous materials. Smoking restrictions shall be adhered to and non-smoking signs posted as required by regulation.
- 3.3.6 HHW storage buildings shall be properly ventilated and shall be constructed in compliance with fire regulations, municipal by-laws and in compliance with Ministry of Labour guidelines. All hazardous waste storage buildings shall be maintained under lock and key and access to these facilities shall be limited to Trained personnel. Access to storage tanks and waste drop-off areas by the public shall be under the supervision of Trained personnel only.
- 3.3.7 HHW storage facilities shall be inspected daily during operating hours by Site personnel who have received training in contingency measures. All inspections shall be recorded.
- 3.3.8 Wastes that are collected and stored shall be in amounts which can be safely handled in the HHW Facility. In the event that larger amounts are received than anticipated, the Municipality shall have extra drums and lab-pack containers available on the HHW premises for the storage of the additional waste collected, and arrangements made to remove the waste from the Site as soon as possible, but in any event, within five (5) working days.
- 3.3.9 Oil and oil-based paints which have been manufactured prior to 1972; or whose manufacturing date cannot be determined, may contain PCBs and shall be handled in the manner prescribed as follows:
 - (a) Oil and oil-based paints shall not be mixed (bulked) with other paints prior to testing. Paints which are lab-packed are not considered to be mixed under this Approval; and
 - (b) Oil and oil-based paints shall be tested for PCB content.

- 3.3.10 If oil or oil-based paints are found to have PCBs at or above 50 parts per million, it shall forthwith be reported to the District Manager and the waste shall be managed in accordance with Regulation 362/92 and stored or removed from the Site to an approved PCB storage site, in accordance with written instructions from the District Manager.
- 3.3.11 Paints collected at the Site may be returned or sold to the general public for re-use, provided that:
 - (a) the paint contains no measurable quantity of PCBs; and
 - (b) all transactions and volume of paint returned to the public are recorded by invoice.
- 3.3.12 Except for paints returned to the public for reuse, all waste collected at the HHW Facility shall be transported from the Site by an approved waste management system and disposed of at landfill, transfer and/or processing sites certified to accept these types of waste.

3.4 Site Operations - Complaint Management Protocol

- 3.4.1 The Municipality shall take steps to minimize and ameliorate any adverse effect on the natural environment or impairment of air quality or water quality, resulting from the operations at the Site, including such accelerated or additional inspection and/or monitoring as may be necessary to determine the nature and extent of the effect or impairment.
- 3.4.2 If at any time, the Municipality receives complaints regarding the Site and/or all other associated waste management activities on-Site, the Municipality shall respond to these complaints according to the following procedure, as described in Section 8.10 in Item 16 of Schedule "A", attached to this Certificate:
 - (a) Record each complaint, either electronically or in a separate log book, and shall include the following information:
 - (i) nature of the complaint,
 - (ii) if complaint is odour or nuisance related, the weather conditions and wind direction at the time of the complaint;
 - (iii) name, address and the telephone number and e-mail address of the complainant (if provided) and
 - (iv) date and time of the complaint;
 - (b) The Municipality, upon notification of the complaint, shall initiate appropriate steps to determine all possible causes of the complaint, proceed to take the necessary actions to eliminate the cause of the complaint and forward a formal reply to the complainant; and
 - (c) The Municipality shall complete and retain on-site a report, written within one (1) week of the complaint date, listing the actions taken to resolve the complaint and any recommendations for remedial measures, and managerial or operational changes to reasonably avoid the recurrence of similar incidents.

4.0 ENVIRONMENTAL MONITORING

4.1 The Municipality shall carry forward the existing monitoring programs for waste, groundwater, and leachate, subject to amendments as described in Items 16 and 18 of Schedule "A", attached to this Approval, and in accordance with Schedule "B" attached to this Certificate. Unless specified otherwise, any proposed changes to the monitoring programs under this Certificate shall be approved in advance by the Director via an amendment to this Approval.

4.2 Groundwater/Leachate Monitoring

Condition 41 in the Certificate dated February 20, 2007, is hereby revoked and replaced with New **Conditions 4.2.1** as follows:

- 4.2.1 The current Groundwater/leachate monitoring program for the Site, as described in Section 10.3 in Item 16 of Schedule "A", attached to this Approval, shall be carried forward, subject to changes as summarized in Schedule "B" of this Approval.
- 4.2.2 Changes and/or updates to the groundwater/leachate monitoring program for the Site, may be made based on the monitoring results to date as recommended in the monitoring report, and approved in writing by the District Manager.

5.0 TRIGGER MECHANISM AND CONTINGENCY PLANS

5.1 Within ninety days following the date of this Approval, the Municipality shall submit for the approval of the Director, a revised updated trigger mechanism for groundwater/leachate, which specifies as a minimum trigger locations, trigger parameters, and trigger mechanism/criteria.

SCHEDULE "B"

Schedule "B" of Environmental Compliance Approval, No. A272301, dated February 20, 2007, is hereby revoked and replaced with a **New Schedule "B"** as follows:

Groundwater Monitoring Program

| Monitoring | Parameters | | | | | | | |
|------------|-------------------------|-------------|--|--|--|--|--|--|
| Location | (Lists Described Below) | | | | | | | |
| | Spring | Fall | | | | | | |
| OW-1 | ** | IND | | | | | | |
| OW-2 | ** | COMP | | | | | | |
| OW-3 | ** | IND | | | | | | |
| OW-4 | ** + IND | IND | | | | | | |
| OW-5 | ** + IND | IND | | | | | | |
| OW-6 | ** + IND | IND | | | | | | |
| OW-7S | ** + IND | IND | | | | | | |
| OW-7D | ** | IND | | | | | | |
| OW-8 | ** + IND | COMP + VOCs | | | | | | |
| OW-9 | ** | ** | | | | | | |
| OW-10S | ** | IND | | | | | | |
| OW-10D | ** | IND | | | | | | |
| OW-11 | ** | IND | | | | | | |
| OW-12S | ** | IND | | | | | | |
| OW-12D | ** | IND | | | | | | |
| OW-13 | ** | ** | | | | | | |

** Water levels to be measured at all monitoring well locations during each monitoring event.

Notes: Parameter Requirements:

(a) Indicator List [IND]:

Alkalinity, conductivity, pH, ammonia, hardness,

calcium, iron, magnesium, manganese, phosphorus, potassium, sodium, chloride, nitrate, nitrite, phosphate, sulphate, DOC and TKN.

(b) Comprehensive List [COMP]:

As per Column 1, Schedule 5, Reg 232: <u>Inorganic</u> Parameters for Groundwater, and DOC.

(c) Volatile Organics [VOCs]:

Once a year for BTEX and once every three years for VOCs (starting in 2018).

REASONS

The reasons for this amendment to the Approval are as follows:

- 1. The reason for Condition 1.0 is to provide, pursuant to subsection 197(1) of the EPA, that any persons having an interest in the Site are aware that the land has been approved and used for the purposes of waste disposal.
- 2. The reason for Conditions 2.0, 3.1 and 3.2 is to specify restrictions on the extent of landfilling and operations at the Site based on the Owner's application and supporting documentation. These limits define the approved volumetric capacity, hours of operation and waste cover of the Site.
- 3. The reasons for Condition 3.3 are allow continued operation of the HHW Depot and to ensure that the Site is operated in a manner which does not result in a nuisance or a hazard to the natural environment and health and safety of people.
- 4. The reason for Condition 3.4 is to ensure that complaints regarding the operations of at the Site are responded to in a timely and efficient manner and that records are available to confirm the resolution of the complaint.
- 5. The reasons for Condition 4.0 are to demonstrate that the landfill Site is performing as designed and the impacts on the natural environment are acceptable. Regular monitoring allows for the analysis of trends over time and ensures that there is an early warning of potential problems so that any necessary remedial / contingency action can be taken.
- 6. The reason for Condition 5.0 is to ensure there is plan available to follow with an organized set of procedures for identifying and responding to potential impacts from the operation of the Site. Contingency plan is necessary to ensure protection of the natural environment and public health and safety.

This Notice shall constitute part of the approval issued under Approval No. A272301 dated February 20, 2007

In accordance with Section 139 of the Environmental Protection Act, you may by written Notice served upon me and the Environmental Review Tribunal within 15 days after receipt of this Notice, require a hearing by the Tribunal. Section 142 of the Environmental Protection Act provides that the Notice requiring the hearing shall state:

- a. The portions of the environmental compliance approval or each term or condition in the environmental compliance approval in respect of which the hearing is required, and;
- b. The grounds on which you intend to rely at the hearing in relation to each portion appealed.

Pursuant to subsection 139(3) of the Environmental Protection Act, a hearing may not be required with respect to any terms and conditions in this environmental compliance approval, if the terms and conditions are substantially the same as those contained in an approval that is amended or revoked by this environmental

compliance approval.

The Notice should also include:

- 1. The name of the appellant;
- 2. The address of the appellant;
- 3. The environmental compliance approval number;
- 4. The date of the environmental compliance approval;
- 5. The name of the Director, and;
- 6. The municipality or municipalities within which the project is to be engaged in.

And the Notice should be signed and dated by the appellant.

This Notice must be served upon:

The Secretary*
Environmental Review Tribunal
655 Bay Street, Suite 1500
Toronto, Ontario
M5G 1E5


AND

The Director appointed for the purposes of Part II.1 of the Environmental Protection Act Ministry of the Environment and Climate Change 135 St. Clair Avenue West, 1st Floor Toronto, Ontario M4V 1P5

* Further information on the Environmental Review Tribunal's requirements for an appeal can be obtained directly from the Tribunal at: Tel: (416) 212-6349, Fax: (416) 326-5370 or www.ert.gov.on.ca

The above noted activity is approved under s. 20.3 of Part II.1 of the Environmental Protection Act.

DATED AT TORONTO this 1st day of November, 2017



Dole D. Gele

Dale Gable, P.Eng.

Director

appointed for the purposes of Part II.1 of the Environmental Protection Act

DO/

c: District Manager, MOECC Owen Sound

Andrea Nelson and Matthew Nelson, GM BluePlan Engineering Limited, The Corporation of the Municipality of Northern Bruce Peninsula

Ministry of the Environment, Conservation and Parks Ministère de l'Environnement, de la Protection de la nature et des Parcs

AMENDMENT TO ENVIRONMENTAL COMPLIANCE APPROVAL

NUMBER A272301 Notice No. 4

Issue Date: April 15, 2019

Municipality of Northern Bruce Peninsula

56 Lindsay Road 5 Lions Head

Rural Route, No. 2

Northern Bruce Peninsula, Ontario

N0H 1W0

Site Location: Eastnor Landfill Site

1252 West Road

Lot 18, part 17, Concession 2 W.B.R.

Northern Bruce Peninsula Municipality, County of Bruce

You are hereby notified that I have amended Approval No. A272301 issued on February 20, 2007, and amended on December 8, 2009, June 14, 2016, and November 1, 2017 for the use and operation of a **9.5** hectare Waste Disposal Site within a total Site Area of **81** hectares, and subsequently amended by adding **1.09** ha to the approved waste Disposal Area for the disposal of wood waste, as follows:

For the purposes of this Environmental Compliance Approval and the terms and conditions specified herein, the following definitions apply:

The following conditions are hereby revoked and replaced as follows:

2.0 <u>SITE DESIGN - CONTINUED USE AND DEVELOPMENT OF THE REMAINING PORTION OF THE APPROVED AREA</u>

Site Capacity

- 2.1 The total waste disposal **capacity** for the Site, including waste, wood waste, daily cover and interim cover, but excluding final cover system, shall be **652,500 cubic metres**, achieved through the development of the Site in accordance Items 20 and 21, and final contours as shown on Drawing No. 3 dated November 2017 of Item 20 of Schedule "A" of this Approval.
- 2.2 No waste shall be landfilled outside the **limit of the 9.5 hectares waste fill area and/or the 1.09 hectares wood waste fill area.** The waste fill areas shall be surrounded by a minimum 30 metres wide buffer on all sides. The Site shall be developed in a progressive manner from south (Phase 1) to north (Phase 2), and landfilling shall be carried out sequentially in stages as shown on Figure 6, ("Progression

- of Waste Placement, Phase 1: Stage 1 Stage 6. dated November 2017), attached to Item 20 of Schedule "A" of this Approval.
- 2.3 No waste shall be landfilled below elevation **95.0 m base contour**, within the new remaining areas of the Site, shown on Drawing No. 3 of Item 20 of Schedule "A" of this Approval. The maximum elevation of the fill area, including final cover, shall be **105.0 metres (reference elevation)**. Final slopes above grade within the waste fill areas at the time of the Site closure, shall be within the range of **4H:1V (25%)** and **20H:1V (5%)** respectively on the sides and top areas.
- 2.4 Except as otherwise provided by these Conditions and subject to condition 2.5 below, the continued use of the landfill Site into the new areas shall be designed, developed, operated, maintained and all facilities, including ancillary waste management facilities, equipment and fixtures, shall be installed in accordance with the supporting documentation, and plans and specifications listed in Schedule "A" of this Approval.
- 2.5 The development of Phase 1 as described in Item 20 of Schedule "A" of this Approval is approved, however a detailed hydrogeological investigation of the Site shall be prepared and submitted for the approval of the Director prior to commencement of development, use or operation of Phase 2. The detailed hydrogeological investigation shall include as a minimum, comprehensive characterization of the Site to establish its background conditions both physically and chemically, and shall include information pertaining to the conditions and the suitability of the Site to receive waste.
- 2.6 Detailed updated plan of development and operations for the Site, shall be prepared and submitted for the approval of the Director prior to commencement of development, use and operation of Phase 2. The detailed plan of development and operation shall replace Item 20 in Schedule A of this Approval and shall include, as a minimum, information pertaining to the operations of the Site and all other waste management activities on site, operational hours, nuisance management controls, monitoring and maintenance programs, service areas, etc.

5.0 TRIGGER MECHANISM AND CONTINGENCY PLANS

- 5.1 The owner shall implement the trigger mechanism for groundwater/leachate as outlined within the Trigger Mechanism and Contingency Plan of Item 22 of Schedule A of this Approval, with the following exceptions:
 - the trigger parameters, levels and locations of Table 1 of Item 22 has been updated to the following Table 1; and
 - that the contingency plan shall be implemented when two or more of the same parameters of Table 1 exceeds the trigger levels at the same trigger location for two consecutive monitoring events.

Table 1: Summary of Groundwater Trigger Parameters, Levels, and Locations

| Parameter | | ground ng/L) | odws | RUC | Trigger Levels at OW-4, OW-5 and OW-6 | Trigger Levels at OW-9 | |
|------------|------------------|-----------------|--------|--------|--|------------------------|--|
| | Range | Average | (mg/L) | (mg/L) | (mg/L) | (mg/L) | |
| Chloride | 1.2 to 5.4 | 3.3 | 250 | 127 | 102 (80% RUC) | 127 (100% RUC) | |
| Sodium | 0.9 to 2.4 | 1.4 | 200 | 101 | 81 (80% RUC) | 101 (100% RUC) | |
| Sulphate | 12.7 to 42.5 | 21.6 | 500 | 261 | 209 (80% RUC) | 261 (100% RUC) | |
| Boron | <0.01 to 0.06 | 0.018 | 5 | 1.26 | 1.01 (80% RUC) | 1.26 (100% RUC) | |
| Nitrate | <0.05 to 0.34 | 2.58 | 10 | 2.58 | 2.06 (80% RUC) | 2.58 (100% RUC) | |
| Alkalinity | 185 - 257 | 210 | 500 | 355 | 284 (80% RUC) | 355 (100% RUC) | |

The following condition is hereby added as follows:

Prior to commencement of development, use or operation of Phase 2, the owner shall submit for the approval of the Director, a revised updated trigger mechanism for groundwater/leachate, which specifies as a minimum trigger locations, trigger parameters, and trigger mechanism/criteria that includes the Phase 2 area.

SCHEDULE "A"

The following documentation is added to Schedule "A" and forms part of the Environmental Compliance Approval No. A272301:

- 20. Municipality of Northern Bruce Peninsula, Plan of Development & Operations Eastnor Landfill Site, Lots 17&18, Concession 2 WBR, Environmental Compliance Approval No. A272301. GM Blueplan Engineering Limited. November 28, 2014 (Revised December 2017).
- 21. Municipality of Northern Bruce Peninsula, Design and Operations Report, Wood Waste Disposal Site Revised Footprint, Eastnor Landfill. GM Blueplan Engineering Limited. December 2017 Revision 2.
- 22. Trigger Mechanism and Contingency Plan. Eastnor Waste Disposal Site, Municipality of Northern Bruce Peninsula. GM Blueplan Engineering Limited. May 2010 (Revised: December 2017).
- 23. Municipality of Northern Bruce Peninsula, Hydrogeologic Investigation Eastnor Landfill (Rev. 2), Lots 17 & 18, Concession 2 WBR, MOECC Certificate of Approval No. A272301. GM Blueplan Engineering Limited. November 28, 2014 (Revised December 2017).

The reasons for this amendment to the Approval are as follows:

- 1. The reason for Condition 2.0 is to specify restrictions on the extent of landfilling and operations at the Site based on the Owner's application and supporting documentation. These limits define the approved volumetric capacity, hours of operation and waste cover of the Site.
- 2. The reason for Condition 5.0 is to ensure there is plan available to follow with an organized set of procedures for identifying and responding to potential impacts from the operation of the Site. Contingency plan is necessary to ensure protection of the natural environment and public health and safety.

This Notice shall constitute part of the approval issued under Approval No. A272301 dated February 20, 2007

In accordance with Section 139 of the Environmental Protection Act, you may by written Notice served upon me and the Environmental Review Tribunal within 15 days after receipt of this Notice, require a hearing by the Tribunal. Section 142 of the Environmental Protection Act provides that the Notice requiring the hearing shall state:

- a. The portions of the environmental compliance approval or each term or condition in the environmental compliance approval in respect of which the hearing is required, and;
- b. The grounds on which you intend to rely at the hearing in relation to each portion appealed.

Pursuant to subsection 139(3) of the Environmental Protection Act, a hearing may not be required with respect to any terms and conditions in this environmental compliance approval, if the terms and conditions are substantially the same as those contained in an approval that is amended or revoked by this environmental compliance approval.

The Notice should also include:

- 1. The name of the appellant;
- 2. The address of the appellant;
- 3. The environmental compliance approval number;
- 4. The date of the environmental compliance approval;
- 5. The name of the Director, and;
- 6. The municipality or municipalities within which the project is to be engaged in.

And the Notice should be signed and dated by the appellant.

This Notice must be served upon:

The Secretary*
Environmental Review Tribunal
655 Bay Street, Suite 1500
Toronto, Ontario
M5G 1E5

AND

The Director appointed for the purposes of Part II.1 of the Environmental Protection Act Ministry of the Environment, Conservation and Parks 135 St. Clair Avenue West, 1st Floor Toronto, Ontario M4V 1P5

* Further information on the Environmental Review Tribunal's requirements for an appeal can be obtained directly from the Tribunal at: Tel: (416) 212-6349, Fax: (416) 326-5370 or www.ert.gov.on.ca

The above noted activity is approved under s.20.3 of Part II.1 of the Environmental Protection Act.

DATED AT TORONTO this 15th day of April, 2019

Hot I

Mohsen Keyvani, P.Eng.

Director

appointed for the purposes of Part II.1 of the

Environmental Protection Act

CM/

c: District Manager, MECP Owen Sound

Matthew Nelson P. Eng., GM BluePlan Engineering Limited, Municipality of Northern Bruce Peninsula

Environmental Compliance Approval No. A272301 Eastnor Landfill Site: Annual Monitoring Report (2024) Municipality of Northern Bruce Peninsula, Ontario May 20, 2025

Appendix B Correspondence

No Correspondence was received during the reporting period

Environmental Compliance Approval No. A272301 Eastnor Landfill Site: Annual Monitoring Report (2024) Municipality of Northern Bruce Peninsula, Ontario May 20, 2025

Appendix C Vector & Vermin Control/Management Plan

Municipality of Northern Bruce Peninsula Eastnor Waste Disposal Site Vector and Vermin Control/Management Plan Ministry of the Environment Provisional Certificate of Approval Number: A272301

Introduction:

The Eastnor waste disposal site is located within an area of the Bruce Peninsula that has a cover of mixed deciduous and coniferous forest and is surrounded by a large area of general rural designated lands. The waste site is not visible from any public roads, and the access road into the facility is quite long and contains several bends. This is a very low volume waste disposal site.

This type of environment lends itself to various types of plants, animals, reptiles, and insects many of which are not, and should not be considered as vector or vermin in this case. However, for the purposes of maintaining a waste disposal site it is important to take precautions with certain types of wildlife. At the Eastnor waste site, there are four types of wildlife that are identified as requiring some form of a precautionary management plan. These are: bees & wasps; scavengers (coyotes, gulls, and turkey vultures); rodents; and black bears. Prior to addressing these concerns, it is important to note that the first step in controlling and managing vector and vermin at this waste site will be to adhere to the Development and Operation Plan.

Strategy:

In order to keep what should be an economical and clear-cut plan to follow economical and clear-cut, the following table will be utilized and a copy of this document will be kept both at the Municipal office and at the Eastnor waste site.

| Prevention | Bees/wasps | Scavengers | Rodents | Black bears |
|------------------------------------|------------|------------|----------|-------------|
| Method | | 8 | | |
| Good house- keeping | $\sqrt{}$ | √ | √ | V |
| Electric fencing | | √ | √ | √ |
| Covering practices | | √ | V | √ |
| Anti-insect sprays and rodenticide | √ | | √ | |
| Education | 1 | √ | 1 | √ √ |

Descriptions:

Good house-keeping practices include items such as daily litter pick up, site organization, and ensuring waste materials are properly segregated into their appropriate locations. These

practices also include regular site inspections by the site attendant, at which time existing and or potential vector/vermin problem areas will be identified. After identification, any required remedial actions will be carried out. It is these good house-keeping practices that are the most important component of this plan. Many vector/vermin problem areas will be most effectively resolved if identified early and remedied as soon as possible.

The <u>electric fencing</u> plan is the most sophisticated portion of the vector/vermin control management plan. This electric fence is intended to discourage black bears, coyotes, and larger rodents from entering the inner waste site area. The fenced in section will include all areas where materials are disposed of, including any recycle stations and the site attendant's shack. The Municipality has applied for and been rewarded with a \$20,000 dollar grant from the Ontario Ministry of Natural Resources via their excellent Bear Wise Funding Program. As the name implies, the main intention of this fencing will be to keep bears out of the waste area. At the present time, the Municipality has finalized the purchase of the required fencing materials from a reputable dealer, and we will be waiting for the C of A approval process to be completed, and for fairer weather prior to beginning installation.

<u>Covering processes</u> play two roles in the prevention of vector and vermin problems. Firstly, by keeping exposed garbage surfaces to a minimum both visual and odour attractants/stimulants are kept to a minimum. Secondly, cover material acts as both a barrier and a deterrent to scavenging birds and rodents.

Anti-insect and rodenticide will be used in moderation, and would include only the use of common household products such as Raid and Warfarin. In cases where wasps or bees make nests inside plastic and tin recycling bins, a product such as Raid may be used to stop the nest making activities. Likewise, if rodents became a concern moderate use of a product such as Warfarin may be applied to locations such as the site attendant's shack, and around the active area of landfilling.

Education includes ensuring that the site attendants are aware of and understand the Development and Operation Plan, are familiar with the Certificate of Approval, and appreciate the importance of properly carrying out routine maintenance and house-keeping at the site.

Conclusion:

It is the intention of this plan to be both straight forward in design, and simple for Staff to follow. It is anticipated that the electric fencing in coordination with a well kept waste site managed in accordance with the Development and Operation Plan, will ensure both control and management of vector and vermin.

Environmental Compliance Approval No. A272301 Eastnor Landfill Site: Annual Monitoring Report (2024) Municipality of Northern Bruce Peninsula, Ontario May 20, 2025

Appendix D Borehole Logs & Summary of Groundwater Elevations (2000 to Present)


LOG of BOREHOLE LW 1-00

| | DRILLING DATA |
|-------------------|--|
| Fleld Supervisor: | S. Watling |
| Method : | Hollow Stem Auger |
| | 200 mm |
| | 21 September 2000 |
| | Fleld Supervisor: Method: Diameter: Date: |

| LIMITS | | IDRAINE R STREN | | S | AMP | LES | 7 | MATERIAL DESCRIPTION | DEPTH | ELEV. | E. | | REMARKS |
|---------------------------------------|-------------|--------------------|----------------|-----|------|-------|--------|---------------------------------------|-------|---------------------------------|------------|------|--------------------------------|
| L NMC LL | Field | Field | Lab. Compr. | No. | TYPE | N | SYMBOL | MATERIAL DESCRIPTION | | | WATER | DATA | |
| 16 % % | Pen. kPa | Vane kPa | kPa | 1 | 2 | Value | S | | m | <u> </u> | \$ | | |
| | | | | | - 3 | | 1.77 | GROUND SURFACE m | | T - | ПТ | TH | Concrete surface seal |
| | | | | | | į | 1 | TOPSOIL | 4 | Ŧ | 41 | 1 | |
| | | | | | | | | Loose, orangy brown Silty fine SAND | F | | 11 | T. | |
| | | | | | | | | | F | Ŧ | | | ti ti |
| | 0 | | | 1 | SS | 9 | -[] | | F | Ŧ | - | e co | Bentonite seal |
| | | | | | | | | | - 1.0 | - | | | |
| | | | | _ | | | - - | | E | Ŧ | | | Auger curtings |
| 1 1 | | | ٠. | | | | | | E | Ξ | | | |
| | 1 | 2 | | 2 | SS | 15 | 1 | Compact, brown medium to fine SAND | E | Ŧ | | | |
| | | | i | | | | | | E | Ī | | | |
| 1 | | | | - | | - | - | | - 2.0 | \pm | -100 | | |
| | | | | | | | | | E | ± | - | | |
| | | ĺ | | 3 | SS | 13 | | | E | 土 | - 💹 | | |
| | | | ļ | 1 | 1 | | | | | ‡ | | | assertate . |
| | | 1 | | | 1 | | 1 | damp | ž | 1 | -1 | | Bentonite seal |
| | | | | _ | 000 | 1 47 | | coarse to medium sand seams saturated | - 3.0 | ± | - 10 | ¥ | Water level @ 3,0 m. at comple |
| | | | | 4 | SS | 17 | | Boarde to Mediani David South | | ‡ | -8 | | |
| | | | İ | 1 | | | | | | ‡ | 摄 | | |
| | | 1 | | | | | | | | 1 | 1:1 | | 1 |
| | 1 | | 1 | | | 1 | | | E | ± | 1.1 | | |
| 1 1 | 1 | | | | | | | | 4.0 | 1 | 1 1 | | #3 Silica Filter sand |
| | | 1 | | | | 1 | | | | <u>+</u> | 1.1 | ļ. | |
| . 1 1 | | | | 1 | | i | | some gravelly seams | Ł | + | 1: | f. | |
| 3 4 | - | i | 1 | 5 | SS | 23 | - | Some graveny assume | E | ‡ | 1 | | |
| | - | | | | | | | | - | ‡ | 1 | | |
| 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 | | | | | 1 | ļ.,, | 4 | · · | - 5.0 | <u>†</u> | 1 | 1 | |
| i | | | | | İ | | | | Ė | ++++ | 11 | ∄: | |
| 1 1 | | | ŀ | | 1 | | | | L | - | 11 | = | 50 mm diameter Slot PVC well |
| 14 | | i | | 1 | | | | | - | <u>+</u> + | | | screen |
| | | ì | | | į | | | | | | | = | |
| | | | | | | | | | 6.0 | + | 1 | = | |
| | | | | 6 | SS | 4 | | grey medium to fine SAND | - | ± * | | | |
| | | | | | i | | | methane odour | 2 | + | 1 | | |
| r [| | Ď. | Ì | | 1 | | | | | ‡ | | | |
| - E | | 1 | 1 | | | | | End of Borehole | | + | | | |
| | | | j L | | | | | 1 | 7.0 | + | 1 | | |
| | | | | | 1 | 1 | | İ | - | ‡ | 1 | | |
| | 4 | , | 4 | | - | 1 | | | | AMEC E | arth & | | Checked: SSY |
| | | | 1 | | | | | | | AMEC E Environn 440 Phill | lip Street | et | ed Silected. 331 |
| | m | - | | | | | | | | Waterloo N2L 5R9 | Ontar | io | PAGE 1 of 1 |

LOG of BOREHOLE BW 1-00

| REF. NO. : | TK20-9-3 | | DRILLING DATA |
|------------|--|-------------------|-------------------|
| CLIENT : | The Town of North Bruce Pennisula | Fleid Supervisor: | S. Watting |
| PROJECT : | Overburden Observation Well Installation | Method : | Hollow Stem Auger |
| LOCATION: | Eastnor Waste Disposal Site | Diameter : | 200 mm |
| DATUM : | | Date : | 20 September 2000 |



LOG of BOREHOLE DW 1-00

ENCL. No.: 2

| DRILLING DATA |
|------------------------------|
| Field Supervisor: S. Watting |
| Method: Hollow Stem Auger |
| Diameter: 200 mm |
| Date: 20 September 2000 |
| |

| LIMITS | | | NDRAINE | | s | AMF | LES | اير | | DEPT | - | ELEV. | œ. | | REMARKS |
|--------|-----|---------------|---------------|----------------|-----|-----|------------|--------|--|----------|---|--------------------------------------|-------|------|---------------------------------|
| L NMC | LL | Field Pen. | Field Vane | Lab. Compr. | No. | YPE | N Value | SYMBOL | MATERIAL DESCRIPTION | m | | m | WATER | DATA | 1 |
| % . % | 1 % | kPa | kPa | i Kra | _ | | | 100 | GROUND SURFACE m | | | | | | |
| | | | 1 | T | - | 100 | - | 21 | 500 mm Black fiberous PEAT | E | 1 | | 11 | | Concrete surface seal |
| 4 | | | | 1 | 1 | AS | | 4 8 | | E | + | | + | | |
| | | | | | | - | | 14 | Loose to compact, brown medium to fine | - | 1 | - | | | Bentonite seal |
| 8 | | | | | | | | | SAND wet | E | - | | | | |
| 0 | | | 1 | | 2 | SS | | | G | - 1.0 | n - | | | 4 | |
| 1 | | | | | | | | | saturated | | 1 | | 11 | | Water level @ 1.0 m. at complet |
| | | r . | ľ | | | | | | | Ė | 1 | E 80 0 | 1 | | #3 Silica Filter sand |
| ì | | | | | 3 | SS | - | - | | - | | | 1 | | |
| * | | | | | ٦ | 1 | | | i. | E | 1 | _ | | | |
| | 1 | | | | | | | | arev | - 2. | n - | | | | |
| į | | | 14 | | No. | | | | grey | - 2. | _ | 1 | | = | |
| 1 | | | | ì | | | | | | | - | | 1 | 3 | 50 mm diameter Slot PVC well |
| 4 | | | 1 | Ì | | | | | | - | - | <u>.</u> | 1 | ₫: | screen |
| 3. | | | | | | | | | V2 48 | t | - | E | | ∄: | |
| 1.0 | | | 1 | l | | | | | | - 3. | n - | <u> </u> | | | |
| | | | Ì | 1 | 4 | 55 | 1 | 7 | | | - | <u>.</u> | | ∄: | |
| 6 | | | 1 | | | 1 | i | III | Stiff, brown SILT, trace fine sand | t | - | <u> </u> | 11 | ≣: | |
| | | | İ | i | 1 | | | | moist | F | _ | <u>!</u> | | | |
| 4 | | | 1 | 8 | | | 1 | | End of Borehole | E | 0 - 0 - 0 - 0 - 0 - 0 - 0 - 0 - 0 - 0 - | <u> </u> | 1 | | |
| | 1 | | 1 | į | | | 1 | | 2 | - 4. | .0 - | Ė | | | |
| 3 | | | İ | ì | 1 | 1 | | 10 | | - | : | Ė | 1 | | |
| | Í | | 1 | 1 | 1 | ĺ | | 1 | | <u>_</u> | _ | Ė | 1 | | |
| | 1 | 1 | | | | i | | 1 | | ţ | | <u> </u> | 4 | | |
| 10 | Ī | | | | | | | | * | ţ | | ‡ | 1 | | |
| | ı | | | 1 | | | | 1 | | - 5. | .0 - | ‡ | 1 | | |
| | | | | i | | | | | | Ė | | + | 1 | | |
| 1 | 1 | | 1 | 181 | | | i | | | 1 | _ | <u>‡</u> | 4 | | * |
| | | | | | | | ĺ | 1 | | Ė | | İ | 1 | | |
| 1 | | 1 | 1 | | 1 | | | | | ţ | | ‡ | 1 | | |
| | į | | | | 1 | İ | 1 | | | - 6 | .0 - | 1 | 1 | | |
| | į | | Ĭ | | i. | | | | | | 1 | - | 7 | | |
| | 1 | | | 10 | | | ì | | | 1 | - | <u>†</u> | 1 | | |
| i i | | | | | 1 | | | | | - | - | İ. | 1 | | |
| | į | | | - | | ļ | | H. | | 1 | | ŧ | - | | |
| | | | | | | | | | | - 7 | .0 - | | - | | |
| | 1 | | | | | 1 | | | | Ŀ | _ | | Th A | | Checked: SSY |
| | | | - | 9 | | | | | <u> </u> | | | AMEC Ear Environme 440 Phillip | Stra | 30 | ed Gneckeu, 351 |
| | 0 | | ec | 4 | | | | | | | | Waterloo (N2L 5R9 | Onlar | io | PAGE 1 of 1 |

LOG of BOREHOLE DW 2-00

| | | and the second second second second | DRILLING DATA |
|------------|--|--|-------------------|
| REF. NO. : | TK20-9-3 | 10 10 10 10 10 10 10 10 10 10 10 10 10 1 | |
| CLIENT : | The Town of North Bruce Pennisula | Fleid Supervisor: | S. Watling |
| PROJECT : | Overburden Observation Well Installation | Method: | Hollow Stem Auger |
| LOCATION: | Eastnor Waste Disposal Site | Diameter: | 200 mm |
| DATUM : | Lastier Waste Present | Date : | 21 September 2000 |

| TTERBURG | UNDRAINED SHEAR STRENGT | тн | s | AMP | LES | 7 | | DEPTH | ELEV. | S. | REMARKS |
|----------|----------------------------|---------------|-----|-----|----------|--------|---|---------|--------------------------------------|-----------|--|
| L NMC LL | Fleid ! Field L | Lab. ompr. | No. | PE | N | SYMBOL | MATERIAL DESCRIPTION | 1 | | WATER | i i i i i i i i i i i i i i i i i i i |
| % % % | kPa kPa | kPa | | | Value | S | | m | m | 5 0 | |
| - (4) | | | _ | | · | 134 | GROUND SURFACE m 450 mm Black fiberous PEAT | | | ИП | Concrete surface seal |
| | | | | | | 4 3 | 450 mm Black liberous PEAT | | | 1111 | |
| | | | | 1 | | 1 | Dark brown Silly fine SAND saturated | | • | TA | <u> </u> |
| | | | | | | | Dark brown Silty fine SAND saturated Soft to firm, mottled blivey grey SILT, some | : | | 11 | Water level @ 0.6 m. at comple Bentonite seal |
| | | | 1 | SS | 4 | 1111 | fine sand | | | | Delicoline 3004 |
| | | | | | | | | 1.0 | | | |
| 1 | | | | | | 1111 | | 3 | | 10 | Auger cuttings |
| | | | 2 | SS | 12 | -[[] | | F - | _ | | Bentonite seal |
| | | | 1 | 00 | - | | wet | į : | _ | | |
| | | | - | - | | -111 | Firm to stiff, bluish grey | 2.0 - | | 10 | |
| | | | i. | | | 141 | | 1 5 | | 10 | |
| | | | 3 | SS | 11 | | | - | Ē | | |
| | 1 1 1 | | | | | | saturated | E | | | |
| | 1 1 1 | | | 1 | | 1]]. | 3312,2132 | | | | |
| | | | 1 | SS | 11 | -111 | | - 3.0 - | | | 4 |
| 1 1 | | | 1 | 33 | | | | 1 : | | | |
| | | | - | | | 111 | | | Ė | | |
| | | | 1 | | | | | 1 4 | | - | |
| | 1 | | | | | | | F | F | | |
| | | | į. | | | 11 | | 4.0 | E | 3 [| |
| | | | | | | | | | | 111 | #3 Silica Filter sand |
| | | | _ | - | | 111 | | | - | 14 | |
| 1 1 | | | 5 | SS | 7 | H | 2 | | | 1日 | |
| 1 | | | | | | | | - 5.0 - | Ī | | |
| | | | | | | | | | E | }目 | |
| | | | | | | H | | | E | | Sfi mm dismeter Slot PVC well |
| i | | | | | | | -2 | | | 計目 | screen |
| | | | | | Ì | | | | | | : |
| 1 | Paris I | | | 86 | | 41 | | - 6.0 - | | 担 | 2 |
| | | | 0 | 22 | 11 | | | i i | Ï | | |
| | | | | | | 111 | | 1 7 | Ė | 1 | |
| | | | - | - | | TH | | - 3 | - | } | |
| | | | | | | is | End of Borehole | 7.0 - | | 1 | |
| | | | | | | | | 7.0 | | 1 | |
| 1 | | | | | <u> </u> | | | - | AMERICA | 1_ | |
| 4500 | mec | y | | | | | | | AMEC Ear Environme 440 Phillip | ntal Limi | checked: SSY |
| | | | | | | | | | Waterico C N2L 5R9 | Ontario | PAGE 1 of 1 |

Project No: M-1553

Project: Overburden Observation Well Installation

Client: Town of North Bruce Penninsula

Location: Eastnor Waste Disposal Site

Log of Borehole: OW-5

Drill Date: March 19, 2010

Field Eng/Tech: EH

Drilling Company: Walker Drilling Ltd.

| | S | UBSU | IRFACE PROFILE | SAM | IPLE | 9 | |
|--|-----------|--------|---|--------|------|---|--|
| Depth | Elevation | Symbol | Description | Number | Туре | Soil Properties N-Value 20 40 60 80 | Well Installation Details |
| ft m -2 -1 -1 -1 -1 -1 -1 -1 -1 -1 -1 -1 -1 -1 | | | Ground Surface Organics Brown SAND Brown SAND, dense, wet Coarse brown and yellow SAND with some stones, wet Fine grey SAND, compact, wet Coarse brown and red SAND, dense, wet Fine to medium grey SAND, wet Clayey SILT, grey, wet Borehole Terminated | 1 2 | SS | 36 | Silica Sand 7 Silica Sand 7 Bentonite Seal |

Drill Method: Solid Stem Auger

Notes:

Gamsby and Mannerow Limited
people engineering environments
Guelph, Owen Sound, Listowel, Kitchener
1260 Second Avenue E., Unit 1. Owen Sound, ON N4K 2J3
519-376-1805 Fax 519-376-8977 www.gamsby.com



Project No: M-1553

Project: Overburden Observation Well Installation

Client: The Town of North Bruce Penninsula

Location: Eastnor Waste Disposal Site

Log of Borehole: OW-6

Drill Date: March 19, 2010

Field Eng/Tech: EH

Drilling Company: Walker Drilling Ltd.

| | 5 | SUBSI | JRFACE PROFILE | SAN | IPLE | | |
|---|-----------|--------|--|--------|------|---|--|
| Depth | Elevation | Symbol | Description | Number | Туре | Soil Properties N-Value 20 40 60 80 | Well Installation Details |
| ft m -1- 0- 1- 2- 3- 1- 1- 1- 1- 1- 1- 1- 1- 1- 1- 1- 1- 1- | | 191 | Ground Surface Black topsoil, wet Fine brown SAND, dense, wet Brown SAND, wet | - | SS | 4 | - IN The seal Leave to the sea |
| 5-1 | | | Grey blue clayey SILT, wet | 1 | | 6 | Silica Sand T |
| 6 - 2 7 - 1 8 - 1 | | | | 2 | SS | • | Silica & |
| 9 - 10 - 3 | | | | | | 11 | |
| 11-1 | | | Borehole Terminated | 3 | SS | * | |
| 14- | | | | | | | |

Drill Method: Solid Stem Auger

Notes:

Gamsby and Mannerow Limited people engineering environments

Guelph, Owen Sound, Listowel, Kitchener 1260 Second Avenue E., Unit 1. Owen Sound, ON N4K 2J3
519-376-1805 Fax 519-376-8977 www.gamsby.com




MONITORING WELL ID: OW-7S/D

PAGE 1 OF 1

GAMSBY AND MANNEROW LIMITED people engineering environments Guelph, Owen Sound, Listowel, Kitchener, Exeter 1260 Second Avenue East, Owen Sound, ON N4K 2J3 ENGINEERS 519-376-1805 Fax 519-376-8977 www.gamsby.com

CLIENT Municipality of Northern Bruce Peninsula PROJECT NAME Hydrogeological Assessment PROJECT NUMBER M-1553 PROJECT LOCATION Eastnor Landfill Site DATE COMPLETED July 12, 2012 **CONTRACTOR** Aardvark Drilling Inc. LOGGED BY DCS METHOD Hollow Stem Auger



GAMSBY AND MANNEROW LIMITED people engineering environments Guelph, Owen Sound, Listowel, Kitchener, Exeter 1260 Second Avenue East, Owen Sound, ON N4K 2J3

MONITORING WELL ID: OW-8

PAGE 1 OF 1

CLIENT Municipality of Northern Bruce Peninsula

PROJECT NUMBER M-1553

PROJECT LOCATION Eastnor Landfill Site

PROJECT NAME Hydrogeological Assessment

PROJECT NAME Hydrogeological Assessment

PROJECT NAME Hydrogeological Assessment

PROJECT NAME Hydrogeological Assessment

PROJECT NAME Hydrogeological Assessment

PROJECT NAME Hydrogeological Assessment

PROJECT NAME Hydrogeological Assessment

PROJECT NAME Hydrogeological Assessment

PROJECT NAME Hydrogeological Assessment

PROJECT NAME Hydrogeological Assessment

PROJECT NAME Hydrogeological Assessment

PROJECT NAME Hydrogeological Assessment

PROJECT NAME Hydrogeological Assessment

PROJECT NAME Hydrogeological Assessment

PROJECT NAME Hydrogeological Assessment

PROJECT NAME Hydrogeological Assessment

PROJECT NAME Hydrogeological Assessment

PROJECT NAME Hydrogeological Assessment

PROJECT NAME Hydrogeological Assessment

PROJECT NAME Hydrogeological Assessment

PROJECT NAME Hydrogeological Assessment

PROJECT NAME Hydrogeological Assessment

PROJECT NAME Hydrogeological Assessment

PROJECT NAME Hydrogeological Assessment

PROJECT NAME Hydrogeological Assessment

PROJECT NAME Hydrogeological Assessment

PROJECT NAME Hydrogeological Assessment

PROJECT NAME Hydrogeological Assessment

PROJECT NAME Hydrogeological Assessment

PROJECT NAME Hydrogeological Assessment

PROJECT NAME Hydrogeological Assessment

PROJECT NAME Hydrogeological Assessment

PROJECT NAME Hydrogeological Assessment

PROJECT NAME Hydrogeological Assessment

PROJECT NAME Hydrogeological Assessment

PROJECT NAME Hydrogeological Assessment

PROJECT NAME Hydrogeological Assessment

PROJECT NAME Hydrogeological Assessment

PROJECT NAME Hydrogeological Assessment

PROJECT NAME Hydrogeological Assessment

PROJECT NAME Hydrogeological Assessment

PROJECT NAME Hydrogeological Assessment

PROJECT NAME Hydrogeological Assessment

PROJECT NAME Hydrogeological Assessment

PROJECT NAME Hydrogeological Assessment


PROJECT NAME Hydrogeological Assessment

PROJECT NAME Hydrogeological Assessment

PROJECT NAME Hydrogeological Assessment

PROJECT NAME Hydrogeological Assessment

PROJECT NAME Hydrogeological Assessme



Borehole Terminated at 3.78 m.

GAMSBY AND MANNEROW LIMITED people engineering environments Guelph, Owen Sound, Listowel, Kitchener, Exeter 1260 Second Avenue East, Owen Sound, ON N4K 2J3 ENGINEERS 519-376-1805 Fax 519-376-8977 www.gamsby.com

MONITORING WELL ID: OW-9

PAGE 1 OF 1


 CLIENT
 Municipality of Northern Bruce Peninsula
 PROJECT NAME
 Hydrogeological Assessment

 PROJECT NUMBER
 M-1553
 PROJECT LOCATION
 Eastnor Landfill Site

 DATE COMPLETED
 July 12, 2012
 CONTRACTOR
 Aardvark Drilling Inc.

 LOGGED BY
 DCS
 METHOD
 Hollow Stem Auger


 WELL CONSTRUCTION
 0.05 m Ø PVC
 NOTES
 ¥ = 91.23 m (15-Apr-13)



GAMSBY AND MANNEROW LIMITED people engineering environments Guelph, Owen Sound, Listowel, Kitchener, Exeter 1260 Second Avenue East, Owen Sound, ON N4K 2J3

MONITORING WELL ID: OW-10S/D


PAGE 1 OF 1



Borehole ID: OW-11

PAGE 1 OF 1










PROJECT NAME Eastnor Landfill - Hydrogeological Assessment
PROJECT NUMBER 213288
PROJECT LOCATION Eastnor Landfill

DATE COMPLETED 2015/10/22
CONTRACTOR London Soil Test

METHOD Hollow Stem Auger

WELL CONSTRUCTION 0.05m Ø PVC

NOTES








PROJECT NAME Eastnor Landfill - Hydrogeological Assessment CLIENT Municipality of Northern Bruce Peninsula PROJECT NUMBER 213288 PROJECT LOCATION Eastnor Landfill DATE COMPLETED 2015/10/22 CONTRACTOR London Soil Test LOGGED BY MB METHOD Hollow Stem Auger WELL CONSTRUCTION 0.05m Ø PVC NOTES SAMPLE TYPE NUMBER ELEVATION RECOVERY (RQD) GRAPHIC LOG DEPTH SPT N VALUE MATERIAL DESCRIPTION WELL DIAGRAM 20 40 60 80 (m) (ft) (m)--2 -Top of PVC = \94.53 m 94 0 =0 TOC = 94,60 m **Ground Surface** 93.7€ 11, Light brown Sandy Topsoil, loose and dry. Concrete - 2 1/1/ Sand Fill 0.83 92.93 50 3-4-4-9 Brown SAND with little silt. Moist to wet. -4 SS (100)(8) -WL = 92.26 m (Oct 29-15) 92 67 5-6-10-13 6 SS (100) (16)2.10 91.66 Bentonite Seal Grey medium to fine SAND with some silt. - 8 83 7-8-7-10 Loose and wet SS (100)(15)- 10 4-3-4-3 71 SS - 12 (100)(7)90 83 1-2-2-2 89.65 4.11 - 14 SS Grey Clayey SILT with trace sand. Moist (100)(4) - 16 2-5-6-8 96 SS (100)(11)18 75 4-5-6-5 88 SS (100)(11)Native Sand 6 - 20 2-3-6-9 SS (100)(9) 22 2-2-2-5 46 SS - 24 (100)(4)7.62 86.14 Grey fine SAND with some silt. Loose, wet - 26 100 3-3-3-5 8 SS (100)(6) to moist. - 28 83 2-3-4-5 SS (100)(7)30 3-4-5-6 79 SS 10 ft Slot 10 PVC (100)(9)32 84 10 83 7-8-7-10 SS - 34 (100)(15)Sand Filter 6-20-13-11 67 36 SS (100)(33)11.26 82.50 Grey coarse grained SAND. Very loose and 38 100 0-1-0-0 82 wet. (No blow counts required) SS (100)(1) -40 100 0-1-0-0 SS (100)(1) Borehole Terminated at 12.80 m.




PAGE 1 OF 1


















SUMMARY OF GROUNDWATER LEVEL ELEVATIONS EASTNOR LANDFILL

| | Reference | Reference | 14-Dec-00 | | 10-Jan-01 | | 12-Jun-01 | | 13-Dec-01 | |
|---------|---------------|----------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|
| Well ID | Elevation | Elevation | Water Level | Water Level | Water Level | Water Level | Water Level | Water Level | Water Level | Water Level |
| | Top of Casing | Ground Surface | Measured | Elevation | Measured | Elevation | Measured | Elevation | Measured | Elevation |
| OW-1 | 97.17 | 96.17 | 4.20 | 92.97 | 4.14 | 93.03 | 3.78 | 93.39 | 3.89 | 93.28 |
| OW-2 | 96.88 | 95.88 | 3.30 | 93.58 | 3.70 | 93.18 | 3.41 | 93.47 | 3.51 | 93.37 |
| OW-3 | 93.39 | 92.39 | 1.22 | 92.17 | 1.24 | 92.15 | 1.16 | 92.23 | 1.15 | 92.24 |
| OW-4 | 91.24 | 90.24 | | H | 0.96 | 90.28 | 0.68 | 90.56 | 0.91 | 90.33 |

| Ī | Reference Reference | | 15-Jun-02 | | 26-Oct-02 | | 7-May-03 | | 11-Nov-03 | |
|---------|---------------------|----------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|
| Well ID | Elevation | Elevation | Water Level | Water Level | Water Level | Water Level | Water Level | Water Level | Water Level | Water Level |
| | Top of Casing | Ground Surface | Measured | Elevation | Measured | Elevation | Measured | Elevation | Measured | Elevation |
| OW-1 | 97.17 | 96.17 | 3.85 | 93.32 | 4.56 | 92.61 | 3.75 | 93.42 | 3.92 | 93.25 |
| OW-2 | 96.88 | 95.88 | 3.47 | 93.41 | 4.18 | 92.70 | 3.42 | 93.46 | 3.50 | 93.38 |
| OW-3 | 93.39 | 92.39 | 1.22 | 92.17 | 1.29 | 92.10 | 1.22 | 92.17 | 1.14 | 92.25 |
| OW-4 | 91.24 | 90.24 | 0.92 | 90.32 | 1.13 | 90.11 | 0.94 | 90.30 | 0.94 | 90.30 |

| | Reference | Reference | 28-M | ay-04 | 3-Nov-04 | | 25-May-05 | | 8-Dec-05 | |
|---------|---------------|----------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|
| Well ID | Elevation (m) | Elevation | Water Level | Water Level | Water Level | Water Level | Water Level | Water Level | Water Level | Water Level |
| | Top of Casing | Ground Surface | Measured | Elevation | Measured | Elevation | Measured | Elevation | Measured | Elevation |
| OW-1 | 97.17 | 96.17 | 3.54 | 93.63 | 4.30 | 92.87 | 3.76 | 93.41 | 4.10 | 93.07 |
| OW-2 | 96.88 | 95.88 | 3.24 | 93.64 | 3.87 | 93.01 | 3.44 | 93.44 | 3.70 | 93.18 |
| OW-3 | 93.39 | 92.39 | 1.18 | 92.21 | 1.19 | 92.20 | 1.22 | 92.17 | 1.23 | 92.16 |
| OW-4 | 91.24 | 90.24 | 0.86 | 90.38 | 0.98 | 90.26 | 0.97 | 90.27 | 0.93 | 90.31 |

| | Reference | Reference | 18-Apr-06 | | 31-Oct-06 | | 19-Apr-07 | | 20-Nov-07 | |
|---------|---------------|----------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|
| Well ID | Elevation | Elevation | Water Level | Water Level | Water Level | Water Level | Water Level | Water Level | Water Level | Water Level |
| | Top of Casing | Ground Surface | Measured | Elevation | Measured | Elevation | Measured | Elevation | Measured | Elevation |
| OW-1 | 97.17 | 96.17 | 3.38 | 93.79 | 4.19 | 92.98 | 3.54 | 93.63 | 4.55 | 92.62 |
| OW-2 | 96.88 | 95.88 | 3.15 | 93.74 | 3.75 | 93.13 | 3.26 | 93.62 | 4.18 | 92.70 |
| OW-3 | 93.39 | 92.39 | 1.12 | 92.27 | 1.20 | 92.20 | 1.13 | 92.26 | 1.24 | 92.15 |
| OW-4 | 91.24 | 90.24 | - | E | 0.97 | 90.27 | 0.69 | 90.55 | 0.88 | 90.36 |

| | Reference | Reference | 15-Apr-08 | | 7-Oct-08 | | 20-Apr-09 | | 11-Nov-09 | |
|---------|---------------|----------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|
| Well ID | Elevation | Elevation | Water Level | Water Level | Water Level | Water Level | Water Level | Water Level | Water Level | Water Level |
| | Top of Casing | Ground Surface | Measured | Elevation | Measured | Elevation | Measured | Elevation | Measured | Elevation |
| OW-1 | 97.17 | 96.17 | 3.47 | 93.70 | 4.38 | 92.79 | 3.48 | 93.69 | 4.15 | 93.02 |
| OW-2 | 96.88 | 95.88 | 3.16 | 93.72 | 4.04 | 92.84 | 3.21 | 93.67 | 3.76 | 93.12 |
| OW-3 | 93.39 | 92.39 | 1.12 | 92.27 | 1.35 | 92.04 | 1.12 | 92.27 | 1.19 | 92.20 |
| OW-4 | 91.24 | 90.24 | 0.73 | 90.51 | 0.95 | 90.29 | 0.75 | 90.49 | 0.75 | 90.49 |

| | Reference Reference | | 7-Apr-10 | | 12-Nov-10 | | 14-Apr-11 | | 1-Nov-11 | |
|---------|---------------------|----------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|
| Well ID | Elevation | Elevation | Water Level | Water Level | Water Level | Water Level | Water Level | Water Level | Water Level | Water Level |
| | Top of Casing | Ground Surface | Measured | Elevation | Measured | Elevation | Measured | Elevation | Measured | Elevation |
| OW-1 | 97.17 | 96.17 | 3.89 | 93.28 | 4.14 | 93.03 | 3.50 | 93.67 | 3.95 | 93.22 |
| OW-2 | 96.88 | 95.88 | 3.49 | 93.39 | 3.76 | 93.12 | 3.15 | 93.73 | 3.51 | 93.37 |
| OW-3 | 93.39 | 92.39 | 1.10 | 92.29 | 1.17 | 92.22 | 1.15 | 92.24 | 1.15 | 92.24 |
| OW-4 | 91.24 | 90.24 | 0.68 | 90.56 | 0.76 | 90.48 | 0.64 | 90.60 | 0.73 | 90.51 |
| OW-5 | 94.30 | 93.22 | 1.31 | 92.99 | 1.42 | 92.88 | 1.31 | 92.99 | 1.41 | 92.89 |
| OW-6 | 91.18 | 90.22 | 1.01 | 90.17 | 1.10 | 90.08 | 1.04 | 90.14 | 1.09 | 90.09 |

| | Reference | Reference | 11-A | pr-12 | 1-No | v-12 | 15-Apr-13 | | 14-Nov-13 | |
|---------|---------------|----------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|
| Well ID | Elevation | Elevation | Water Level | Water Level | Water Level | Water Level | Water Level | Water Level | Water Level | Water Level |
| | Top of Casing | Ground Surface | Measured | Elevation | Measured | Elevation | Measured | Elevation | Measured | Elevation |
| OW-1 | 97.17 | 96.17 | 3.80 | 93.37 | 4.22 | 92.95 | 3.59 | 93.58 | 3.89 | 93.28 |
| OW-2 | 96.88 | 95.88 | 3.46 | 93.42 | 3.77 | 93.11 | 3.23 | 93.65 | 3.53 | 93.35 |
| OW-3 | 93.39 | 92.39 | 1.14 | 92.25 | 1.13 | 92.26 | 1.15 | 92.24 | 1.17 | 92.22 |
| OW-4 | 91.24 | 90.24 | 0.70 | 90.54 | 0.73 | 90.51 | 0.64 | 90.60 | 0.72 | 90.52 |
| OW-5 | 94.30 | 93.22 | 1.36 | 92.94 | 1.47 | 92.83 | 1.33 | 92.97 | 1.39 | 92.91 |
| OW-6 | 91.18 | 90.22 | 1.04 | 90.14 | 1.07 | 90.11 | 1.04 | 90.14 | 1.05 | 90.13 |
| OW-7S | 93.45 | 92.62 | NI | NA | 1.05 | 92.40 | 1.00 | 92.45 | 1.04 | 92.41 |
| OW-7D | 93.33 | 92.62 | NI | NA | 1.01 | 92.32 | 0.75 | 92.58 | 0.95 | 92.38 |
| OW-8 | 94.35 | 93.55 | NI | NA | 1.31 | 93.04 | 0.97 | 93.38 | 1.15 | 93.20 |
| OW-9 | 91.75 | 90.79 | NI | NA | 0.39 | 91.36 | 0.52 | 91.23 | 0.22 | 91.53 |
| OW-10S | 94.74 | 93.91 | NI | NA | 1.09 | 93.65 | 0.78 | 93.96 | 0.84 | 93.90 |
| OW-10D | 94.54 | 93.91 | NI | NA | 1.69 | 92.85 | 1.39 | 93.15 | 1.49 | 93.05 |

SUMMARY OF GROUNDWATER LEVEL ELEVATIONS EASTNOR LANDFILL

| | Reference | Reference | 12-M | ay-14 | 29-O | ct-14 | 23-A | pr-15 | 29-0 | ct-15 |
|---------|---------------|----------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|
| Well ID | Elevation | Elevation | Water Level | Water Level | Water Level | Water Level | Water Level | Water Level | Water Level | Water Level |
| | Top of Casing | Ground Surface | Measured | Elevation | Measured | Elevation | Measured | Elevation | Measured | Elevation |
| OW-1 | 97.17 | 96.17 | 3.51 | 93.66 | 4.14 | 93.03 | 3.29** | 93.88 | 4.44 | 92.73 |
| OW-2 | 96.88 | 95.88 | 3.24 | 93.64 | 3.78 | 93.10 | 3.32 | 93.56 | 4.09 | 92.79 |
| OW-3 | 93.39 | 92.39 | 1.15 | 92.24 | NM | NA | 1.15 | 92.24 | 1.10 | 92.29 |
| OW-4 | 91.24 | 90.24 | 0.67 | 90.57 | 0.72 | 90.52 | 1.38** | 89.86 | 0.68 | 90.56 |
| OW-5 | 94.30 | 93.22 | 1.33 | 92.97 | 1.46 | 92.84 | 1.36 | 92.94 | 1.43 | 92.87 |
| OW-6 | 91.18 | 90.22 | 1.04 | 90.14 | 1.05 | 90.13 | 1.03 | 90.15 | 1.06 | 90.12 |
| OW-7S | 93.45 | 92.62 | 1.01 | 92.44 | 1.08 | 92.37 | 1.01 | 92.44 | 1.00 | 92.45 |
| OW-7D | 93.33 | 92.62 | 0.79 | 92.54 | 1.04 | 92.29 | 0.80 | 92.53 | 1.09 | 92.24 |
| OW-8 | 94.35 | 93.55 | 1.00 | 93.35 | 1.39 | 92.96 | 1.08 | 93.27 | 1.60 | 92.75 |
| OW-9 | 91.75 | 90.79 | 0.41 | 91.34 | 0.76 | 90.99 | 0.57 | 91.18 | 0.72 | 91.03 |
| OW-10S | 94.74 | 93.91 | 0.79 | 93.95 | 1.14 | 93.60 | 0.81 | 93.93 | 1.57 | 93.17 |
| OW-10D | 94.54 | 93.91 | 1.42 | 93.12 | 1.68 | 92.86 | 1.44 | 93.10 | 2.25 | 92.29 |
| OW-11 | 94.61 | 93.66 | NI | NA | NI | NA | NI | NA | 1.48 | 93.13 |
| OW-12S | 94.52 | 93.81 | NI | NA | NI | NA | NI | NA | 1.74 | 92.78 |
| OW-12D | 94.53 | 93.76 | NI | NA | NI | NA | NI | NA | 2.27 | 92.26 |
| OW-13 | 94.10 | 93.32 | NI | NA | NI | NA | NI | NA | 1.35 | 92.75 |

| | Reference | Reference | 24-N | ov-15 | 21-A | pr-16 | 1-No | v-16 | 25-A | pr-17 |
|---------|---------------|----------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|
| Well ID | Elevation | Elevation | Water Level | Water Level | Water Level | Water Level | Water Level | Water Level | Water Level | Water Level |
| | Top of Casing | Ground Surface | Measured | Elevation | Measured | Elevation | Measured | Elevation | Measured | Elevation |
| OW-1 | 97.17 | 96.17 | 4.34 | 92.83 | 3.46 | 93.71 | 3.96 | 93.21 | 3.54 | 93.63 |
| OW-2 | 96.88 | 95.88 | 4.15 | 92.73 | 3.15 | 93.73 | 3.69 | 93.19 | 3.23 | 93.65 |
| OW-3 | 93.39 | 92.39 | 1.16 | 92.24 | 1.10 | 92.29 | 1.16 | 92.23 | 1.15 | 92.24 |
| OW-4 | 91.24 | 90.24 | 0.76 | 90.48 | 0.66 | 90.58 | 0.73 | 90.51 | 1.02 | 90.22 |
| OW-5 | 94.30 | 93.22 | 1.56 | 92.74 | 1.33 | 92.97 | 1.45 | 92.85 | 1.36 | 92.94 |
| OW-6 | 91.18 | 90.22 | 1.05 | 90.14 | 1.01 | 90.17 | 1.12 | 90.06 | 1.04 | 90.14 |
| OW-7S | 93.45 | 92.62 | 1.11 | 92.34 | 1.02 | 92.43 | 1.08 | 92.37 | 1.01 | 92.44 |
| OW-7D | 93.33 | 92.62 | 1.32 | 92.01 | 0.81 | 92.52 | 0.97 | 92.36 | 0.82 | 92.51 |
| OW-8 | 94.35 | 93.55 | 1.59 | 92.77 | 1.08 | 93.27 | 1.38 | 92.97 | 1.02 | 93.33 |
| OW-9 | 91.75 | 90.79 | 0.52 | 91.23 | 0.23 | 91.52 | 0.29 | 91.46 | 0.18 | 91.57 |
| OW-10S | 94.74 | 93.91 | 1.44 | 93.30 | 0.79 | 93.95 | 0.93 | 93.81 | 1.02 | 93.72 |
| OW-10D | 94.54 | 93.91 | 1.99 | 92.56 | 1.47 | 93.07 | 1.64 | 92.90 | 1.50 | 93.04 |
| OW-11 | 94.61 | 93.66 | 1.26 | 93.35 | 0.74 | 93.87 | 0.82 | 93.79 | 0.70 | 93.91 |
| OW-12S | 94.52 | 93.81 | 1.72 | 92.81 | 1.12 | 93.40 | 1.43 | 93.09 | 1.14 | 93.38 |
| OW-12D | 94.53 | 93.76 | 2.09 | 92.44 | 1.51 | 93.02 | 1.74 | 92.79 | 1.52 | 93.01 |
| OW-13 | 94.10 | 93.32 | 1.37 | 92.74 | 1.04 | 93.06 | 1.21 | 92.89 | 1.08 | 93.02 |

| | Reference | Reference | 20-Se | ep-17 | 8-Ma | ay-18 | 20-N | ov-18 | 16-A | pr-19 |
|---------|---------------|----------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|
| Well ID | Elevation | Elevation | Water Level | Water Level | Water Level | Water Level | Water Level | Water Level | Water Level | Water Level |
| | Top of Casing | Ground Surface | Measured | Elevation | Measured | Elevation | Measured | Elevation | Measured | Elevation |
| OW-1 | 97.17 | 96.17 | 4.22 | 92.95 | NM | NA | 4.27 | 92.90 | 2.44 | 94.73 |
| OW-2 | 96.88 | 95.88 | 3.89 | 92.99 | NM | NA | 3.97 | 92.91 | 3.15 | 93.73 |
| OW-3 | 93.39 | 92.39 | 1.17 | 92.22 | NM | NA | 1.19 | 92.20 | 1.27 | 92.12 |
| OW-4 | 91.24 | 90.24 | 0.82 | 90.42 | 0.64 | 90.60 | 0.77 | 90.47 | 0.61 | 90.63 |
| OW-5 | 94.30 | 93.22 | 1.51 | 92.79 | 1.35 | 92.95 | 1.55 | 92.75 | 1.35 | 92.95 |
| OW-6 | 91.18 | 90.22 | 1.13 | 90.05 | 1.01 | 90.17 | 1.08 | 90.10 | 1.05 | 90.13 |
| OW-7S | 93.45 | 92.62 | 1.29 | 92.16 | 1.03 | 92.42 | 1.12 | 92.33 | 1.02 | 92.43 |
| OW-7D | 93.33 | 92.62 | 1.40 | 91.93 | NM | NA | 1.23 | 92.10 | 0.77 | 92.56 |
| OW-8 | 94.35 | 93.55 | 1.57 | 92.78 | 1.01 | 93.34 | 1.50 | 92.85 | 0.90 | 93.45 |
| OW-9 | 91.75 | 90.79 | 0.57 | 91.19 | NM | NA | 0.42 | 91.33 | 0.10 | 91.65 |
| OW-10S | 94.74 | 93.91 | 1.47 | 93.27 | NM | NA | 1.36 | 93.38 | 0.78 | 93.96 |
| OW-10D | 94.54 | 93.91 | 1.65 | 92.89 | NM | NA | 1.95 | 92.59 | 1.48 | 93.06 |
| OW-11 | 94.61 | 93.66 | 1.36 | 93.25 | NM | NA | 1.19 | 93.42 | 0.67 | 93.94 |
| OW-12S | 94.52 | 93.81 | 1.63 | 92.89 | NM | NA | 1.67 | 92.85 | 1.09 | 93.43 |
| OW-12D | 94.53 | 93.76 | 2.03 | 92.50 | NM | NA | 2.18 | 92.35 | 1.66 | 92.87 |
| OW-13 | 94.10 | 93.32 | 1.35 | 92.75 | NM | NA | 1.37 | 92.73 | 1.07 | 93.03 |

| | Reference | Reference | 22-0 | ct-19 | 25-A | pr-20 | 28-O | ct-20 | 4-Ma | ay-21 |
|---------|---------------|----------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|
| Well ID | Elevation | Elevation | Water Level | Water Level | Water Level | Water Level | Water Level | Water Level | Water Level | Water Level |
| | Top of Casing | Ground Surface | Measured | Elevation | Measured | Elevation | Measured | Elevation | Measured | Elevation |
| OW-1 | 97.17 | 96.17 | 4.23 | 92.94 | 3.80 | 93.37 | 4.03 | 93.14 | 3.87 | 93.30 |
| OW-2 | 96.88 | 95.88 | 3.87 | 93.01 | 3.44 | 93.44 | 3.66 | 93.22 | 3.48 | 93.40 |
| OW-3 | 93.39 | 92.39 | 1.15 | 92.24 | 1.16 | 92.23 | 1.15 | 92.24 | 1.12 | 92.27 |
| OW-4 | 91.24 | 90.24 | 0.77 | 90.47 | 0.65 | 90.59 | 0.71 | 90.53 | 0.61 | 90.63 |
| OW-5 | 94.30 | 93.22 | 1.45 | 92.85 | 1.36 | 92.94 | 1.42 | 92.88 | 1.32 | 92.98 |
| OW-6 | 91.18 | 90.22 | 1.09 | 90.09 | 1.09 | 90.09 | 1.09 | 90.09 | 1.10 | 90.08 |
| OW-7S | 93.45 | 92.62 | 1.07 | 92.38 | 1.03 | 92.42 | 1.08 | 92.37 | 1.00 | 92.45 |
| OW-7D | 93.33 | 92.62 | 1.22 | 92.11 | 0.91 | 92.42 | 0.95 | 92.38 | 0.87 | 92.46 |
| OW-8 | 94.35 | 93.55 | 1.49 | 92.86 | 1.18 | 93.17 | 1.30 | 93.05 | 1.15 | 93.20 |
| OW-9 | 91.75 | 90.79 | 0.41 | 91.34 | 0.20 | 91.55 | 0.18 | 91.57 | 0.10 | 91.65 |
| OW-10S | 94.74 | 93.91 | 1.37 | 93.37 | 0.86 | 93.88 | 0.96 | 93.78 | 0.84 | 93.90 |
| OW-10D | 94.54 | 93.91 | 1.94 | 92.60 | 1.62 | 92.92 | 1.65 | 92.89 | 1.65 | 92.89 |
| OW-11 | 94.61 | 93.66 | 1.19 | 93.42 | 0.78 | 93.83 | 0.92 | 93.69 | NM | N/A |
| OW-12S | 94.52 | 93.81 | 1.62 | 92.90 | 1.29 | 93.23 | 1.48 | 93.04 | 1.30 | 93.22 |
| OW-12D | 94.53 | 93.76 | 2.14 | 92.39 | 1.84 | 92.69 | 1.94 | 92.59 | 1.88 | 92.65 |
| OW-13 | 94.10 | 93.32 | 1.34 | 92.76 | 1.17 | 92.93 | 1.26 | 92.84 | 1.17 | 92.93 |

SUMMARY OF GROUNDWATER LEVEL ELEVATIONS **EASTNOR LANDFILL**

| | Reference | Reference | 6-0 | ct-21 |
|---------|---------------|----------------|-------------|-------------|
| Well ID | Elevation | Elevation | Water Level | Water Level |
| | Top of Casing | Ground Surface | Measured | Elevation |
| OW-1 | 97.17 | 96.17 | 4.22 | 92.95 |
| OW-2 | 96.88 | 95.88 | 3.87 | 93.01 |
| OW-3 | 93.39 | 92.39 | 1.18 | 92.21 |
| OW-4 | 91.24 | 90.24 | 0.79 | 90.45 |
| OW-5 | 94.30 | 93.22 | 1.50 | 92.80 |
| OW-6 | 91.18 | 90.22 | 1.14 | 90.04 |
| OW-7S | 93.45 | 92.62 | 1.11 | 92.34 |
| OW-7D | 93.33 | 92.62 | 1.20 | 92.13 |
| OW-8 | 94.35 | 93.55 | 1.48 | 92.87 |
| OW-9 | 91.75 | 90.79 | 0.07 | 91.68 |
| OW-10S | 94.74 | 93.91 | 1.39 | 93.35 |
| OW-10D | 94.54 | 93.91 | 1.94 | 92.60 |
| OW-11 | 94.61 | 93.66 | 1.12 | 93.49 |
| OW-12S | 94.52 | 93.81 | 1.64 | 92.88 |
| OW-12D | 94.53 | 93.76 | 2.23 | 92.30 |
| OW-13 | 94.10 | 93.32 | 1.34 | 92.76 |

| | Elevation | Elevation | 26-A | pr-22 | 27-Se | ep-22 | 21-A | pr-23 | 28-N | ov-23 |
|---------|---------------|----------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|
| Well ID | Top of Casing | Ground Surface | Water Level | Water Level | Water Level | Water Level | Water Level | Water Level | Water Level | Water Level |
| | (masl) | (masl) | Measured | Elevation | Measured | Elevation | Measured | Elevation | Measured | Elevation |
| OW-1 | 195.57 | 194.57 | 3.56 | 192.01 | 4.22 | 191.35 | 3.57 | 192.00 | 4.04 | 191.53 |
| OW-2 | 195.28 | 194.28 | 3.37 | 191.91 | 3.78 | 191.50 | 3.28 | 192.00 | 3.70 | 191.58 |
| OW-3 | 191.79 | 190.79 | 1.16 | 190.63 | 1.16 | 190.63 | 1.14 | 190.65 | 1.16 | 190.63 |
| OW-4 | 189.64 | 188.64 | 1.00 | 188.64 | 0.77 | 188.87 | 0.61 | 189.03 | 0.71 | 188.93 |
| OW-5 | 192.70 | 191.62 | 1.32 | 191.38 | 1.44 | 191.26 | 1.33 | 191.37 | 1.41 | 191.29 |
| OW-6 | 189.58 | 188.62 | 1.02 | 188.56 | 1.07 | 188.51 | 1.00 | 188.58 | 1.10 | 188.48 |
| OW-7S | 191.85 | 191.02 | 1.01 | 190.84 | 1.03 | 190.82 | 1.02 | 190.83 | 1.05 | 190.80 |
| OW-7D | 191.73 | 191.02 | 0.89 | 190.84 | 1.18 | 190.55 | 0.82 | 190.91 | 0.96 | 190.77 |
| OW-8 | 192.75 | 191.95 | 1.18 | 191.57 | 1.41 | 191.34 | 1.04 | 191.71 | 1.33 | 191.42 |
| OW-9 | 190.15 | 189.19 | 0.10 | 190.05 | 0.38 | 189.77 | 0.10 | 190.05 | NM | NA |
| OW-10S | 193.14 | 192.31 | 0.96 | 192.18 | 1.21 | 191.93 | 0.80 | 192.34 | 0.93 | 192.21 |
| OW-10D | 192.94 | 192.31 | 1.50 | 191.44 | 1.90 | 191.04 | 1.50 | 191.44 | 1.65 | 191.29 |
| OW-11 | 193.01 | 192.06 | 0.75 | 192.26 | 1.01 | 192.00 | 0.71 | 192.30 | 0.85 | 192.16 |
| OW-12S | 192.92 | 192.21 | 1.14 | 191.78 | 1.59 | 191.33 | 1.12 | 191.80 | 1.57 | 191.35 |
| OW-12D | 192.93 | 192.16 | 1.75 | 191.18 | 2.17 | 190.76 | 1.86 | 191.07 | 2.03 | 190.90 |
| OW-13 | 192.50 | 191.72 | 1.08 | 191.42 | 1.29 | 191.21 | 1.07 | 191.43 | NM | NA |

| | Elevation | Elevation | 30-A | pr-24 | 12-N | ov-24 |
|---------|---------------|----------------|-------------|-------------|-------------|-------------|
| Well ID | Top of Casing | Ground Surface | Water Level | Water Level | Water Level | Water Level |
| | (masl) | (masl) | Measured | Elevation | Measured | Elevation |
| OW-1 | 195.57 | 194.57 | 3.60 | 191.97 | 4.19 | 191.38 |
| OW-2 | 195.28 | 194.28 | 3.25 | 192.03 | 3.85 | 191.43 |
| OW-3 | 191.79 | 190.79 | 1.15 | 190.64 | 1.16 | 190.63 |
| OW-4 | 189.64 | 188.64 | 0.60 | 189.04 | 0.78 | 188.86 |
| OW-5 | 192.70 | 191.62 | 1.33 | 191.37 | 1.43 | 191.27 |
| OW-6 | 189.58 | 188.62 | 1.00 | 188.58 | 1.10 | 188.48 |
| OW-7S | 191.85 | 191.02 | 1.03 | 190.82 | 1.10 | 190.75 |
| OW-7D | 191.73 | 191.02 | 0.78 | 190.95 | 1.18 | 190.55 |
| OW-8 | 192.75 | 191.95 | 0.87 | 191.88 | 1.41 | 191.34 |
| OW-9 | 190.15 | 189.19 | 0.09 | 190.06 | 0.25 | 189.90 |
| OW-10S | 193.14 | 192.31 | 0.78 | 192.36 | 1.20 | 191.94 |
| OW-10D | 192.94 | 192.31 | 1.50 | 191.44 | 1.88 | 191.06 |
| OW-11 | 193.01 | 192.06 | 0.70 | 192.31 | 1.04 | 191.97 |
| OW-12S | 192.92 | 192.21 | 1.16 | 191.76 | 1.58 | 191.34 |
| OW-12D | 192.93 | 192.16 | 1.85 | 191.08 | 2.28 | 190.65 |
| OW-13 | 192.50 | 191.72 | 1.09 | 191.41 | 1.30 | 191.20 |


- Note:

 1. All measurements are in metres.
 2. Elevations are relative to the assumed benchmark elevation.
 3. NI = Not Installed; NA = Not Applicable.


- Water level elevations that are highlighted and shown in bold represent water levels that are <u>above</u> ground surface.
 In November 2022 the site was surveyed to reflect UTM derived coordinates and the elevation across the Site was adjusted by 98.4 meters to reflect geodetic elevations.

Environmental Compliance Approval No. A272301 Eastnor Landfill Site: Annual Monitoring Report (2024) Municipality of Northern Bruce Peninsula, Ontario May 20, 2025

Appendix E Cross-Sections A-A' through E-E'



FILE:\\os-2k8\users_private\etwining\Documents\Drawings\Z13288 HA Hydro.dwg LAYOUT.APP E1 LAST SAVED BY:Etwining, 12/19/2017 4:43:59 PM PLOTTED BY:Ed Twining - GM BluePlan 12/19/2017 4:58:28 PM



SECTION A-A'

HORZ. 1:1,500 VERT. 1:150 **CROSS-SECTION A-A'**

EASTNOR LANDFILL

Appendix E2



LEGEND

BOREHOLE (TOTAL DEPTH)

SCREENED INTERVAL


W/L EL.

WATER LEVEL ELEVATION (SEP. 2017)

PARTICLE SIZE ANALYSIS SUMMARY
10:35:52:3 (PROPORTION)
CLAY:SILT:SAND:C. SAND (CLASSIFICATION)

| Unit No. | Description of Unit Encountered |
|----------|---------------------------------|
| 1 | fine to medium SAND |
| 2 | silt loam |
| 3 | medium to coarse SAND |
| 4 | stiff silty clay |

Note: Figures were adjusted in 2022 to suit UTM derived coordinates and the elevation across the Site was raised 98.4 meters to reflect geodetic elevations (i.e., masl). Elevations on the cross sections show the former 'relative' elevations.



LEGEND

BOREHOLE (TOTAL DEPTH)

SCREENED INTERVAL

WATER LEVEL ELEVATION (SEP 2017) W/L EL

PARTICLE SIZE ANALYSIS SUMMARY 10:35:52:3 (PROPORTION) CLAY:SILT:SAND:C. SAND (CLASSIFICATION)

| Description of Unit Encountered |
|---------------------------------|
| fine to medium SAND |
| silt loam |
| medium to coarse SAND |
| stiff silty clay |
| |

CROSS-SECTION B-B'

EASTNOR LANDFILL


Appendix E3



FILE:\los-2k8\users_private\etwining\Documents\Drawings\Z13288 HA Cross Sections dwg_LAYDUT:B-B' LAST SAVED BY:Etwining, 12/19/2017 5:05:05 PM_PLOTTED BY:Ed Twining - GM BluePlan 12/19/2017 5:12:43 PM

HORZ. 1:1,500 VERT. 1:150

Note: Figures were adjusted in 2022 to suit UTM derived coordinates and the elevation across the Site was raised 98.4 meters to reflect geodetic elevations (i.e., masl). Elevations on the cross sections show the former 'relative' elevations.



SECTION C-C'

IIORZ. 1:1,500 VERT. 1:150

Note: Figures were adjusted in 2022 to suit UTM derived coordinates and the elevation across the Site was raised 98.4 meters to reflect geodetic elevations (i.e., masl). Elevations on the cross sections show the former 'relative' elevations.

LEGEND

BOREHOLE (TOTAL DEPTH)

W/L EL. WATER LEVEL ELEVATION (SEP 2017)

SCREENED INTERVAL

PARTICLE SIZE ANALYSIS SUMMARY 10:35:52:3 (PROPORTION) CLAY:SILT:SAND:C. SAND (CLASSIFICATION)


| Unit No. | Description of Unit Encountered |
|----------|---------------------------------|
| 1 | fine to medium SAND |
| 2 | silt loam |
| 3 | medium to coarse SAND |
| 4 | stiff silty clay |

CROSS-SECTION C-C'

EASTNOR LANDFILL

Appendix E4





LEGEND

BOREHOLE (TOTAL DEPTH)

SCREENED INTERVAL

W/L EL. WATER LEVEL ELEVATION (SEP 2017)

PARTICLE SIZE ANALYSIS SUMMARY
10:35:52:3 (PROPORTION)
CLAY:SILT:SAND:C. SAND (CLASSIFICATION)

| Unit No. | Description of Unit Encountered |
|----------|---------------------------------|
| 1 | fine to medium SAND |
| 2 | silt loam |
| 3 | medium to coarse SAND |
| 4 | stiff silty clay |

CROSS-SECTION D-D'

EASTNOR LANDFILL


Appendix E5



SECTION D-D'

HORZ. 1:1,500 VERT. 1:150

Note: Figures were adjusted in 2022 to suit UTM derived coordinates and the elevation across the Site was raised 98.4 meters to reflect geodetic elevations (i.e., masl). Elevations on the cross sections show the former 'relative' elevations.



LEGEND

BOREHOLE (TOTAL DEPTH)

SCREENED INTERVAL

W/L EL. WATER LEVEL ELEVATION (SEP 2017)

PARTICLE SIZE ANALYSIS SUMMARY
10:35:52:3 (PROPORTION)
CLAY:SILT:SAND:C. SAND (CLASSIFICATION)

| Unit No. | Description of Unit Encountered |
|----------|---------------------------------|
| 1 | fine to medium SAND |
| 2 | silt loam |
| 3 | medium to coarse SAND |
| 4 | stiff silty clay |

CROSS-SECTION E-E'

EASTNOR LANDFILL

Appendix E6



SECTION E-E'

HORZ. 1:1,500 VERT. 1:150

Note: Figures were adjusted in 2022 to suit UTM derived coordinates and the elevation across the Site was raised 98.4 meters to reflect geodetic elevations (i.e., masl). Elevations on the cross sections show the former 'relative' elevations.

Environmental Compliance Approval No. A272301 Eastnor Landfill Site: Annual Monitoring Report (2024) Municipality of Northern Bruce Peninsula, Ontario May 20, 2025

Appendix F Historical Groundwater Quality Results (Tables & Graphs)

Monitoring Well OW-1 (Shallow Sand Unit)

| Monitoring V | | | | | | | | | | | | | | | | | | | | |
|----------------------|--------------|------------|------------|-----------|----------|---------|-------------|----------|------------|------------|---------|-----------|--------|-----------|-------|-----------|--------|---------|------|------|
| Parameter | Conductivity | pН | Alkalinity | Hardness | Chloride | Nitrate | Nitrite | Sulphate | Phosphate | Phosphorus | Calcium | Magnesium | Sodium | Potassium | Iron | Manganese | Boron | Ammonia | DOC | TKN |
| UNITS | uS/cm | Unitless | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L |
| odws | NV | 6.5 to 8.5 | 30 to 500 | 80 to 100 | 250 | 10 | 1.0 | 500 | NV | NV | NV | NV | 200 | NV | 0.3 | 0.05 | 5 | NV | 5.0 | NV |
| 9841-1027-10900 | NA | OG | OG | OG | AO | MAC | MAC | AO | NA | NA | NA | NA | AO | NA | AO | AO | IMAC | NA | AO | NA |
| RUC | NV | 6.5 to 8.5 | 355 | 261 | 127 | 2.58 | 0.25 | 261 | NV | NV | NV | NV | 101 | NV | 1.83 | 0.31 | 1.26 | NV | 30.2 | NV |
| Jan-01 | 367 | 7.54 | 217 | 246 | 3.0 | NM | NM | 23.15 | NM | NM | NM | NM | 1.3 | NM | 1.27 | NM | | 0.12 | 24.2 | 1.25 |
| Jun-01 | 372 | 7.50 | 207 | 237 | 3.4 | 0.2 | NM | 23.7 | NM | NM | NM | NM | 1.2 | NM | 1.28 | NM | | 0.08 | 30.5 | 1.26 |
| Dec-01 | 446 | 7.59 | 257 | 246 | 4.1 | NM | NM | 24.2 | NM | NM | NM | NM | 0.9 | NM | 1.27 | NM | | 0.07 | 22.3 | 1.02 |
| Jun-02 | 479 | 7.48 | 247 | 289 | 4.5 | NM | NM | 22.7 | NM | NM | NM | NM | 1.4 | NM | 1.94 | NM | | NM | 33.9 | 2.80 |
| Oct-02 | 432 | 7.94 | 251 | 264 | 4.3 | 0.3 | NM | 22.0 | NM | NM | NM | NM | NM | NM | NM | NM | | NM | 22.3 | 1.36 |
| May-03 | 451 | 7.84 | 226 | 240 | 3.4 | NM | NM | 17.5 | NM | NM | NM | NM | 1.4 | NM | 0.27 | NM | | 0.34 | 19.8 | 0.96 |
| Nov-03 | 436 | NM | 222 | 249 | 3.6 | 0.2 | NM | 16.4 | NM | NM | NM | NM | 0.9 | NM | 1.12 | MM | | 0.27 | 16.6 | 0.86 |
| May-04 | 445 | 7.62 | 223 | 257 | 4.7 | NM | NM | 16.8 | NM | NM | NM | NM | 1.0 | NM | 1.21 | NM | | 0.24 | 19.5 | 0.89 |
| Nov-04 | NM | NM | 234 | NM | 3.6 | 0.2 | NM | 15.9 | NM | NM | NM | NM | 1.0 | NM | 1.24 | NM | | 0.28 | 20.4 | NM |
| Jun-05 | 437 | NM | 229 | NM | 1.19 | NM | NM | 2.4 | NM | NM | NM | NM | 1.2 | NM | 1.20 | NM | | 0.41 | NM | NM |
| Dec-05 | 377 | 8.10 | 226 | 230 | 4.0 | 0.06 | 0.10 | 18.0 | NM | NM | NM | NM | 1.2 | NM | 1.70 | NM | | 0.52 | 20.6 | 9* |
| Apr-06 | 389 | 7.52 | 186 | 217 | 2.12 | 0.19 | <0.05 | 12.7 | NM | NM | NM | NM | 1.56 | NM | 24.6* | NM | | 0.14 | NM | NM |
| Oct-06 | 387 | 8.12 | 209 | 223 | 3.09 | 0.08 | <0.05 | 17.0 | <0.10 | 0.20 | 57.7 | 19.2 | 1.06 | 1.44 | 0.58 | 0.166 | | 0.21 | NM | NM |
| Apr-07 | 399 | 7.57 | 189 | 218 | 2.47 | <0.05 | <0.05 | 14.5 | <0.10 | 0.14 | 56.4 | 18.8 | 0.91 | 0.25 | 0.51 | 0.170 | | 0.31 | NM | NM |
| Nov-07 | 386 | 7.75 | 194 | 238 | 2.51 | 0.10 | <0.05 | 13.6 | <0.10 | 0.50 | 62.1 | 20.1 | 0.95 | 0.35 | 6.12* | 0.382 | | 0.08 | NM | NM |
| Apr-08 | 396 | 8.07 | 203 | 215 | 1.99 | <0.05 | <0.05 | 13.0 | <0.10 | 0.15 | 55.8 | 18.4 | 1.00 | 0.39 | 0.35 | 0.141 | , | 0.42 | NM | - |
| Oct-08 | 419 | 8.14 | 202 | 232 | 1.93 | <0.05 | <0.05 | 13.5 | < 0.10 | 0.18 | 59.3 | 20.5 | 1.14 | 0.38 | 0.53 | 0.160 | | 0.24 | NM | NM |
| Apr-09 | 398 | 8.01 | 197 | 236 | 1.77 | <0.05 | <0.05 | 13.6 | <0.10 | 0.22 | 61.0 | 20.4 | 1.22 | 0.34 | 0.41 | 0.141 | | 0.06 | NM | NM |
| Nov-09 | 401 | 7.95 | 201 | 223 | 3.88 | 0.06 | <0.05 | 16.7 | <0.10 | 0.31 | 57.7 | 19.1 | 1.37 | 0.36 | 0.52 | 0.155 | | < 0.05 | NM | NM |
| Apr-10 | 394 | 8.01 | 205 | 237 | 3.95 | 0.09 | <0.05 | 20.0 | <0.10 | NM | 61.5 | 20.3 | 2.42 | 0.44 | 0.18 | 0.147 | , | 0.11 | 18.7 | 0.64 |
| Nov-10 | 383 | 8.11 | 209 | 253 | 2.21 | <0.05 | <0.05 | 18.1 | <0.10 | 0.45 | 66.5 | 21.1 | 1.86 | 0.54 | 0.40 | 0.161 | | 0.17 | NM | NM |
| Apr-11 | 404 | 7.93 | 195 | 227 | 2.64 | < 0.05 | <0.05 | 19.9 | <0.10 | 0.17 | 59.0 | 19.3 | 1.37 | 0.42 | 0.48 | 0.175 | | 0.06 | 15.5 | 1.18 |
| Nov-11 | 322 | 8.08 | 194 | 220 | 2.85 | <0.05 | <0.05 | 18.1 | <0.10 | < 0.05 | 57.2 | 18.8 | 1.56 | 0.36 | 0.54 | 0.153 | | 0.19 | 15.9 | 0.78 |
| Apr-12 | 442 | 8.08 | 210 | 252 | 5.43 | 0.07 | <0.05 | 28.5 | <0.10 | 0.13 | 66.2 | 21.1 | 1.59 | 0.39 | 0.74 | 0.156 | , | 0.16 | 17.8 | 1.16 |
| Nov-12 | 411 | 7.93 | 205 | 252 | 5.41 | <0.05 | <0.05 | 31.5 | <0.10 | 0.35 | 67.0 | 20.6 | 2.07 | 0.45 | 0.76 | 0.171 | | 0.21 | 18.8 | 1.77 |
| Apr-13 | 426 | 8.01 | 195 | 248 | 3.58 | <0.05 | <0.05 | 29.3 | <0.10 | 0.14 | 64.8 | 21.0 | 1.49 | 0.37 | 0.46 | 0.184 | | 0.11 | 13.8 | 1.14 |
| Nov-13 | 424 | 8.24 | 193 | 253 | 3.11 | <0.05 | <0.05 | 27.1 | <0.10 | 0.30 | 65.9 | 21.4 | 1.46 | 0.45 | 0.41 | 0.163 | | 0.30 | NM | NM |
| May-14 | 442 | 8.12 | 193 | 239 | 2.99 | 0.13 | <0.05 | 29.8 | <0.10 | 0.16 | 61.7 | 20.7 | 1.83 | 1.24 | 0.33 | 0.159 | , | 0.28 | 12.8 | 1.37 |
| Oct-14 | 410 | 7.60 | 185 | 233 | 3.60 | <0.10 | <0.10 | 32.8 | <0.20 | 0.29 | 61.0 | 19.5 | 1.55 | 0.44 | 0.57 | 0.171 | * | 0.32 | 15.6 | 1.20 |
| Apr-15 | 440 | 7.93 | 201 | 250 | 3.96 | <0.05 | <0.05 | 42.5 | <0.10 | 0.12 | 65.5 | 21.1 | 1.74 | 1.43 | 0.54 | 0.186 | | 0.26 | 19.9 | 1.07 |
| Oct-15 | 450 | 7.51 | 201 | 231 | 3.66 | 0.34 | <0.10 | 35.0 | <0.20 | 0.54 | 61.2 | 19.1 | 1.67 | 0.40 | 5.07 | 0.306 | | 0.29 | 14.6 | 0.84 |
| Nov-16 | 398 | 7.66 | 191 | 211 | 2.62 | 0.06 | <0.05 | 21.6 | <0.10 | 0.14 | 55.9 | 17.3 | 1.28 | 0.38 | 0.35 | 0.161 | * | 0.29 | 10.8 | 0.71 |
| Sep-17 | 487 | 7.93 | 226 | 230 | 3.37 | 0.17 | <0.05 | 22.7 | <0.10 | 0.28 | 59.6 | 19.8 | 1.56 | 0.38 | 0.24 | 0.154 | | 0.32 | 18.7 | 1.00 |
| Nov-18 | 466 | 7.67 | 249 | 244 | 4.10 | 0.07 | <0.05 | 20.9 | <0.10 | <0.05 | 63.9 | 20.5 | 2.04 | 0.49 | 0.10 | 0.153 | 0.018 | 0.28 | 17.7 | 0.75 |
| Oct-19 | 349 | 7.95 | 203 | 202 | 2.09 | <0.05 | <0.05 | 7.85 | <0.10 | 0.26 | 52.2 | 17.4 | 1.50 | 0.41 | 0.27 | 0.159 | <0.010 | 0.22 | 10.6 | 0.50 |
| Oct-20 | 413 | 7.88 | 217 | 224 | 5.16 | 0.20 | 0.08 | 16.1 | <0.10 | 0.79 | 58.2 | 19.2 | 1.75 | 0.35 | 0.27 | 0.136 | 0.062 | 0.26 | 15.6 | 0.99 |
| Oct-21 | 417 | 7.73 | 205 | 211 | 3.25 | 0.11 | 0.07 | 15.0 | <0.10 | 0.55 | 55.3 | 17.8 | 1.50 | <0.50 | 0.41 | 0.012 | 0.016 | 0.14 | 42.7 | 1.16 |
| Sep-22 | 434 | 8.01 | 210 | 221 | 3.77 | 0.24 | <0.05 | 19.1 | <0.10 | 0.71 | 58.4 | 18.2 | 2.59 | <0.05 | 0.39 | 0.125 | 0.017 | 0.17 | 21.8 | 1.39 |
| Nov-23 | 457 | 7.58 | 262 | 243 | 3.35 | <0.05 | <0.05 | 19.6 | <0.10 | 0.18 | 64.7 | 19.8 | 1.71 | <0.50 | 0.55 | 0.123 | 0.027 | 0.20 | 14.6 | 0.76 |
| Nov-24 | 525 | 7.70 | 295 | 278 | 3.69 | 0.05 | <0.05 | 35.2 | <0.10 | 0.14 | 73.6 | 22.8 | 2.22 | <0.50 | 0.34 | 0.103 | 0.027 | 0.29 | 13.0 | 0.90 |
| ,,,,,,, | 020 | 7.70 | 230 | 210 | 0.00 | 0.00 | -0.00 | 55.2 | -0.10 | 5.17 | 7 3.0 | 22.0 | 2.22 | -0.00 | 0.04 | 0.20 | 0.010 | 0.20 | 10.0 | 0.00 |
| Average | 418 | 7.85 | 214 | 237 | 3.36 | 0.10 | <0.10 | 20.7 | <0.1 | 0.30 | 61.0 | 19.8 | 1.47 | 0.52 | 0.78 | 0.170 | 0.023 | 0.22 | 19.3 | 1.10 |
| | | | | | | | | | | | | | | | | | | | 6.84 | 0.44 |
| Average Std. Dev. | 38.9 | 0.23 | 23.9 | 18.3 | 1.0 | 0.10 | <0.10 NA | 7.91 | <0.1 NA | 0.30 | 4.63 | 1.30 | 0.41 | 0.52 | 0.78 | 0.170 | 0.023 | 0.22 | | |

Monitoring Well OW-2 (Shallow Sand Unit)

| Monitoring | well Ow-2 | (Shallow) | Sand Un | it) | | | | | | | | | | | | | | | | |
|------------------|---------------------|--------------|------------|---|------------|--------------|--------------|------------|-----------|---------------|---------|-----------|--------|------------|------------|-----------|-------|---------|-----------|--------------|
| Parameter | Conductivity | рН | Alkalinity | Hardness | Chloride | Nitrate | Nitrite | Sulphate | Phosphate | Phosphorus | Calcium | Magnesium | Sodium | Potassium | Iron | Manganese | Boron | Ammonia | DOC | TKN |
| UNITS | uS/cm | Unitless | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L |
| ODWS | , NV | 6.5 to 8.5 | 30 to 500 | 80 to 100 | 250 | 10 | 1.0 | 500 | NV | NV | NV | NV | 200 | NV | 0.3 | 0.05 | 5 | NV | 5.0 | NV |
| ODWS | NA | OG | OG | OG | AO | MAC | MAC | AO | NA | NA | NA | NA | AO | NA | AO | AO | IMAC | NA | AO | NA |
| RUC | NV | 6.5 to 8.5 | 355 | 261 | 127 | 2.58 | 0.25 | 261 | NV | NV | NV | NV | 101 | NV | 1.83 | 0.31 | 1.26 | NV | 30.2 | NV |
| Jan-01 | 2970 | 7.15 | 714 | 1990 | 257 | NM | NM | 1320 | NM | NM | NM | NM | 107 | NM | 4.33 | NM | | 0.54 | 20.4 | 1.58 |
| Jun-01 | 3100 | 7.20 | 763 | 1760 | 274 | 0.2 | NM | 1390 | NM | NM | NM | NM | 87.6 | NM | 3.32 | NM | | 0.34 | 16.6 | 1.04 |
| Dec-01 | 3830 | 7.31 | 717 | 1720 | 316 | NM | NM | 1640 | NM | NM | NM | NM | 125 | NM | ND | NM | | 0.58 | 17.4 | 1.36 |
| Jun-02 | 4480 | 7.13 | 822 | 2350 | 385 | NM | NM | 1660 | NM | NM | NM | NM | 128 | NM | 2.38 | NM | | 0.36 | 21 | 3.12 |
| Oct-02 | 3500 | 7.53 | 968 | 2640 | 309 | 0.3 | NM | 1540 | NM | NM | NM | NM | NM | NM | NM | NM | | 0.29 | 19 | 1.19 |
| May-03 | 3690 | 7.39 | 1020 | 2200 | 231 | NM | NM | 1110 | NM | NM | NM | NM | 160 | NM | 4.21 | NM | | 0.27 | 17 | 1.04 |
| Nov-03 | 3670 | NM | 858 | 2010 | 216 | NM | NM | 1230 | NM | NM | NM | NM | 120 | NM | 5.40 | NM I | | 0.70 | 21 | 1.42 |
| May-04 | 3130 | 7.21 | 848 | 1810 | 188 | NM | NM | 1090 | NM | NM | NM | NM | 104 | NM | 3.69 | NM | | 0.33 | 12.5 | 1.07 |
| Nov-04 | NM | NM | 872 | NM | 139 | NM | NM | 1000 | NM | NM | NM | NM | 80.5 | NM | 2.89 | NM | | 0.58 | 15.6 | NM |
| Jun-05 | 3550 | NM | 916 | NM | 191 | 0.1 | NM | 1210 | NM | NM | NM | NM | 128 | NM | 3.6 | NM | | 1.29 | NM | NM |
| Dec-05 | 2730 | 7.90 | 879 | 1500 | 136 | NM | 0.19 | 1060 | NM | NM | NM | NM | 99 | NM | 5.1 | NM | | 0.90 | 15 | 4.00 |
| Apr-06 | 3530 | 7.40 | 1030 | 1840 | 163 | 0.27 | <0.05 | 1070 | NM | NM | NM | NM | 117 | NM | 8.9 | NM | | 0.85 | NM | NM |
| Oct-06 | 1160 | 8.02 | 427 | 520 | 39 | 0.16 | <0.05 | 210 | <0.10 | 0.23 | 102 | 64.5 | 20.3 | 61.7 | 0.25 | 0.625 | | 0.72 | NM | NM |
| Apr-07 | 2780 | 7.42 | 922 | 1400 | 102 | 0.14 | <0.05 | 725 | <0.10 | 0.44 | 245 | 192 | 76.0 | 138 | 0.59 | 1.44 | | 1.38 | NM | NM |
| Nov-07 | 2520 | 7.39 | 884 | 1550 | 84 | <0.05 | <0.05 | 718 | <0.10 | 0.44 | 277 | 209 | 66.6 | 130 | 6.8 | 1.58 | | 0.28 | NM | NM |
| Apr-08 | 2060 | 7.93 | 777 | 1040 | 89 | 0.48 | <0.05 | 444 | <0.10 | 0.34 | 216 | 121 | 52.4 | 58.2 | 0.72 | 1.21 | | 0.79 | NM | NM |
| Oct-08 | 2720 | 7.72 | 932 | 1330 | 71 | 0.08 | <0.05 | 607 | <0.10 | 0.26 | 231 | 183 | 66.5 | 122 | 0.39 | 1.17 | | 0.89 | NM | NM |
| Apr-09 | 2760 | 7.68 | 964 | 1560 | 75 | <0.05 | <0.05 | 701 | <0.10 | <0.05 | 296 | 200 | 66.4 | 103 | 0.03 | 1.38 | | 0.03 | NM | NM |
| Nov-09 | 2930 | 7.77 | 981 | 1680 | 86 | <0.05 | <0.05 | 816 | <0.10 | 0.12 | 303 | 224 | 70.2 | 135 | 0.02 | 1.36 | | 0.17 | NM | NM |
| Apr-10 | 2770 | 7.82 | 945 | 1710 | 95 | 0.08 | <0.05 | 899 | <0.10 | NM | 320 | 221 | 72.3 | 121 | <0.01 | 1.69 | | 0.06 | 12.4 | 0.94 |
| Nov-10 | 2600 | 7.70 | 940 | 1850 | 89 | <0.05 | <0.05 | 897 | <0.10 | 0.26 | 345 | 240 | 78.1 | 118 | 0.01 | 1.59 | | 0.12 | NM | NM |
| Apr-11 | 2990 | 7.63 | 950 | 1750 | 109 | <0.05 | <0.05 | 949 | <0.10 | 0.20 | 344 | 216 | 69.7 | 104 | 0.04 | 1.76 | | <0.02 | 12.5 | 1.07 |
| Nov-11 | 2550 | 7.71 | 982 | 1790 | 110 | <0.05 | <0.05 | 1100 | <0.10 | <0.05 | 303 | 251 | 76.2 | 141 | 0.07 | 1.81 | | 0.19 | 12.9 | 0.70 |
| Apr-12 | 3280 | 8.03 | 978 | 1920 | 118 | <0.05 | <0.05 | 1120 | <0.10 | 0.48 | 351 | 254 | 73.8 | 135 | 0.07 | 1.65 | | 0.13 | 10.5 | 1.05 |
| Nov-12 | 3120 | 7.82 | 1010 | 1850 | 136 | <0.05 | <0.05 | 1160 | <0.10 | 0.43 | 281 | 279 | 96.8 | 171 | 0.02 | 1.28 | | 0.30 | 14.8 | 0.96 |
| Apr-13 | 2970 | 7.95 | 978 | 1490 | 86.4 | <1.0 | <1.0 | 806 | <2.0 | 0.05 | 294 | 184 | 62.6 | 90.5 | <0.01 | 2.20 | | 0.33 | 8.4 | 1.38 |
| Nov-13 | 3000 | 7.84 | 933 | 1450 | 82.9 | <1.0 | <1.0 | 851 | <2.0 | 0.15 | 254 | 197 | 63.3 | 119 | 0.01 | 1.57 | | 0.23 | NM | NM |
| May-14 | 2990 | 7.94 | 962 | 1570 | 85.1 | <1.0 | <1.0 | 743 | <2.0 | 0.16 | 268 | 219 | 65.8 | 122 | 0.01 | 1.60 | | 0.09 | 7.7 | 1.15 |
| Oct-14 | 3230 | 7.37 | 1020 | 1560 | 120 | <1.0 | <1.0 | 968 | <2.0 | 0.14 | 248 | 219 | 68.6 | 134 | 0.02 | 1.51 | | 0.20 | 10.6 | 0.64 |
| Apr-15 | 3190 | 7.47 | 969 | 1600 | 144 | <0.5 | <0.5 | 891 | <1.0 | 0.20 | 256 | 234 | 83.6 | 132 | 0.02 | 1.71 | | 0.13 | 9.5 | 0.64 |
| Oct-15 | 3540 | 8.01 | 1090 | 1840 | 168 | <1.0 | <1.0 | 1010 | <2.0 | 0.13 | 265 | 287 | 90.6 | 183 | 3.87 | 1.71 | 1.98 | 0.08 | 10.3 | 0.71 |
| Nov-16 | 2880 | 7.89 | 913 | 1429 | 139 | <1.0 | <1.0 | 721 | NM | 0.50 | 242 | 201 | 66.1 | 118 | 3.02 | 1.49 | 1.11 | 2.83 | 9.2 | 3.57 |
| | 3650 | 7.89 | 1040 | 1688 | 192 | <0.5 | <0.5 | 954 | NM | 0.21 | 265 | 250 | 88.1 | 148 | 4.13 | 1.59 | 1.73 | 0.06 | 15.4 | 0.94 |
| Sep-17 Nov-18 | 3570 | 7.72 | 1040 | 1711 | 255 | <1.0 | <1.0 | 901 | NM | 0.13 | 258 | 260 | 120 | 162 | <0.010 | 1.38 | 1.73 | <0.02 | 13.3 | 0.94 |
| | 2960 | | 986 | 1688 | 149 | <1.0 | <1.0 | 893 | NM NM | | 258 | 236 | | | 22.5.0.5.5 | | | | 11 (0.00) | 2000000 |
| Oct-19 Oct-20 | 3160 | 7.76 7.87 | 1919/91 | 1688 | 149 162 | <1.0 <1.0 | <1.0 <1.0 | 893 875 | NM NM | <0.02 0.12 | 288 | 236 | 79.9 | 139 143 | 3.55 | 1.68 | 1.55 | 0.11 | 9.9 | 0.79 0.62 |
| | 100.000.000.000.000 | | 1050 | 100000000000000000000000000000000000000 | | 10000000 | | | 1.44.44. | | | | 103 | 100000000 | 0.034 | | | <0.02 | 11.7 | |
| Sep-22 | 2420 | 7.52 | 884 | 1440 | 52 | <0.14 | <0.11 | 627 | <0.26 | 0.23 | 360 | 131 | 52.6 | 58 | 0.049 | 1.30 | 1.48 | <0.02 | 9.1 | 0.58 |
| Nov-23 | 2830 | 7.49 | 988 | 1325 | 100 | <0.07 | <0.05 | 729 | NM | 1.05 | 232 | 181 | 68.1 | 128 | 5.23 | 1.17 | 1.54 | 0.07 | 13.3 | 0.56 |
| Nov-24 | 2830 | 7.48 | 822 | 1048 | 56.5 | <0.14 | <0.11 | 583 | NM | 0.50 | 193 | 138 | 43.6 | 105 | 0.033 | 0.96 | 1.62 | 0.03 | 23.0 | 0.60 |
| | | | | | | | | | | | | | | | | —— | | | | |
| Average | 3043 | 7.64 | 917 | 1657 | 149 | 0.25 | <1.0 | 954 | <0.10 | 0.29 | 271 | 209 | 84.1 | 123 | 1.97 | 1.47 | 1.56 | 0.48 | 13.9 | 1.22 |
| Std. Dev. | 556 | 0.27 | 121 | 366 | 81 | 0.22 | NA | 304 | NA | 0.23 | 53.6 | 50.3 | 27.6 | 30.6 | 2.40 | 0.298 | 0.23 | 0.5 | 4.24 | 0.90 |

Monitoring Well OW-3 (Shallow Sand Unit)

| Monitoring V | Well OW-3 | Shallow | Sand Un | it) | | | | | | | | | | | | | | | | |
|--------------|--------------|------------|------------|-----------|----------|---------|----------|----------|-----------|------------|---------|-----------|--------|-----------|--------|-----------|-------|---------|-------|------|
| Parameter | Conductivity | pН | Alkalinity | Hardness | Chloride | Nitrate | Nitrite | Sulphate | Phosphate | Phosphorus | Calcium | Magnesium | Sodium | Potassium | Iron | Manganese | Boron | Ammonia | DOC | TKN |
| UNITS | uS/cm | Unitless | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L |
| odws | NV | 6.5 to 8.5 | 30 to 500 | 80 to 100 | 250 | 10 | 1.0 | 500 | NV | NV | NV | NV | 200 | NV | 0.3 | 0.05 | 5 | NV | 5.0 | NV |
| ODVV3 | NA | OG | OG | OG | AO | MAC | MAC | AO | NA | NA | NA | NA | AO | NA | AO | AO | IMAC | NA | AO | NA |
| RUC | NV | 6.5 to 8.5 | 355 | 261 | 127 | 2.58 | 0.25 | 261 | NV | NV | NV | NV | 101 | NV | 1.83 | 0.31 | 1.26 | NV | 30.2 | NV |
| Jan-01 | 2180 | 7.09 | 667 | 1380 | 143 | NM | NM | 715 | NM | NM | NM | NM | 85.7 | NM | 9.15 | NM | | 0.82 | 17.2 | 1.71 |
| Jun-01 | 2000 | 7.51 | 566 | 1110 | 124 | NM | NM | 656 | NM | NM | NM | NM | 57.2 | NM | 12.15 | NM | | 0.75 | 19.65 | 1.36 |
| Dec-01 | 2770 | 7.29 | 598 | 1730 | 187 | NM | NM | 1080 | NM | NM | NM | NM | 83.1 | NM | 13.60 | NM | | 1.27 | 19.9 | 1.86 |
| Jun-02 | 2300 | 7.18 | 577 | 1360 | 161 | NM | NM | 804 | NM | NM | NM | NM | 68.4 | NM | 7.49 | NM | | 0.93 | 16.5 | 4.75 |
| Oct-02 | 2430 | 7.40 | 678 | 1710 | 198 | NM | NM | 971 | NM | NM | NM | NM | NM | NM | NM | NM | | 1.27 | 14.5 | 2.24 |
| May-03 | 2860 | 7.43 | 706 | 1680 | 169 | 0.2 | NM | 860 | NM | NM | NM | NM | 99.0 | NM | 10.2 | NM | | 0.88 | 22.9 | 1.68 |
| Nov-03 | 3090 | NM | 680 | 1660 | 209 | 0.5 | NM | 987 | NM | NM | NM | NM | 93.9 | NM | 12.2 | NM | | 0.92 | 16.4 | 1.45 |
| May-04 | 3140 | 7.21 | 735 | 1830 | 237 | 0.6 | NM | 1150 | NM | NM | NM | NM | 122 | NM | 10.8 | NM | | 0.63 | 14.8 | 1.56 |
| Nov-04 | NM | NM | 808 | NM | 184 | NM | NM | 929 | NM | NM | NM | NM | 104 | NM | 8.27 | NM | | 0.78 | 18.0 | NM |
| Jun-05 | 2490 | NM | 696 | NM | 124 | 0.1 | NM | 710 | NM | NM | NM | NM | 87.3 | NM | 9.43 | NM | | 0.75 | NM | NM |
| Dec-05 | 2580 | 8.00 | 777 | 1400 | 175 | 0.3 | 0.09 | 1120 | NM | NM | NM | NM | 110 | NM | 9.9 | NM | | 0.78 | 17.2 | 3.00 |
| Apr-06 | 2840 | 7.60 | 705 | 1460 | 148 | 0.33 | <0.05 | 823 | NM | NM | NM | NM | 91.8 | NM | 29.1 | NM | | 0.46 | NM | NM |
| Oct-06 | 2160 | 7.83 | 678 | 234 | 107 | <0.05 | <0.05 | 630 | <0.10 | 0.44 | 40.6 | 32.3 | 12.8 | 17.2 | 0.52 | 0.936 | | 1.11 | NM | NM |
| Apr-07 | 2170 | 7.59 | 688 | 1080 | 98 | <0.05 | <0.05 | 534 | <0.10 | 1.23 | 180 | 152 | 61.1 | 82.4 | 0.39 | 0.654 | | 0.94 | NM | NM |
| Nov-07 | 2280 | 7.42 | 754 | 1440 | 109 | <0.05 | <0.05 | 602 | <0.10 | 0.44 | 263 | 189 | 75.7 | 88.7 | 17.8 | 1.120 | | 0.20 | NM | NM |
| Apr-08 | 2240 | 7.97 | 818 | 1200 | 109 | 0.05 | <0.05 | 591 | <0.10 | 0.11 | 214 | 162 | 63.2 | 65.1 | 0.60 | 0.850 | | 1.73 | NM | NM |
| Oct-08 | 2640 | 7.84 | 749 | 1360 | 119 | <0.05 | <0.05 | 648 | <0.10 | 0.32 | 249 | 180 | 72.7 | 79.6 | 0.28 | 0.987 | | 1.95 | NM | NM |
| Apr-09 | 1650 | 7.85 | 553 | 779 | 62 | 0.17 | <0.05 | 259 | <0.10 | 0.08 | 129 | 111 | 38.2 | 69.0 | 0.04 | 0.449 | | 0.46 | NM | NM |
| Nov-09 | 1800 | 7.79 | 610 | 834 | 72 | <0.05 | <0.05 | 390 | <0.10 | 0.07 | 151 | 111 | 45.6 | 64.8 | 0.02 | 0.529 | | 0.20 | NM | NM |
| Apr-10 | 1990 | 7.94 | 746 | 1090 | 76 | 0.06 | < 0.05 | 480 | <0.10 | NM | 184 | 152 | 49.9 | 78.1 | <0.01 | 0.769 | | <0.05 | 13.6 | 1.34 |
| Nov-10 | 2040 | 7.65 | 737 | 1310 | 84 | <0.05 | <0.05 | 633 | <0.10 | 0.06 | 261 | 159 | 57.0 | 67.4 | 0.15 | 0.995 | | 0.84 | NM | NM |
| Apr-11 | 2250 | 7.87 | 734 | 1130 | 86 | < 0.05 | < 0.05 | 608 | <0.10 | 0.13 | 189 | 159 | 48.9 | 70.8 | 0.01 | 0.744 | | <0.02 | 10.5 | 4.26 |
| Nov-11 | 1910 | 7.77 | 725 | 1290 | 88 | < 0.05 | < 0.05 | 788 | <0.10 | <0.05 | 241 | 168 | 59.4 | 72.2 | 0.02 | 0.919 | | 1.34 | 10.4 | 2.45 |
| Apr-12 | 2150 | 8.22 | 743 | 1190 | 66 | <0.05 | < 0.05 | 542 | <0.10 | <0.05 | 203 | 167 | 48.8 | 76.3 | 0.01 | 0.651 | | 0.57 | 10.3 | 2.16 |
| Nov-12 | 2320 | 7.79 | 825 | 1510 | 101 | <0.05 | < 0.05 | 767 | <0.10 | 0.40 | 284 | 194 | 71.2 | 74.9 | 0.29 | 1.080 | | 1,11 | 10.7 | 2.26 |
| Apr-13 | 2210 | 7.88 | 744 | 1120 | 65.4 | <1.0 | <1.0 | 503 | <2.0 | < 0.05 | 197 | 153 | 44.6 | 70.4 | < 0.01 | 0.900 | | 0.60 | 9.8 | 2.66 |
| Nov-13 | 2440 | 8.04 | 716 | 1360 | 82.8 | <0.5 | <0.5 | 713 | <1.0 | 0.18 | 221 | 196 | 62.6 | 85.9 | <0.01 | 0.914 | | 0.83 | NM | NM |
| May-14 | 2330 | 7.74 | 765 | 1180 | 72.7 | <0.5 | <0.5 | 515 | <1.0 | 0.06 | 184 | 174 | 47.2 | 86.4 | 0.02 | 0.986 | | 1.06 | 9.7 | 1.62 |
| Oct-14 | 2440 | 7.40 | 663 | 1230 | 88.7 | <0.5 | <0.5 | 777 | 4.6 | <0.05 | 204 | 175 | 56.3 | 72.1 | 0.01 | 1.46 | | 0.59 | 10.8 | 1.22 |
| Apr-15 | 2170 | 7.50 | 668 | 1100 | 81.1 | <0.25 | <0.25 | 581 | <0.50 | 0.18 | 186 | 154 | 49.3 | 77.1 | 0.04 | 1.080 | | 0.40 | 11.7 | 1.21 |
| Oct-15 | 2300 | 7.93 | 587 | 1150 | 76.8 | <1.0 | <1.0 | 769 | <2.0 | 0.05 | 201 | 157 | 47.0 | 73.8 | 15 | 0.93 | | 0.85 | 10.0 | 1.46 |
| Nov-16 | 2350 | 7.82 | 549 | 1230 | 75.1 | <0.5 | <0.5 | 841 | <1.0 | 0.06 | 212 | 169 | 44.6 | 70.2 | 0.029 | 0.79 | | 0.57 | 12.1 | 1.36 |
| Sep-17 | 2450 | 7.83 | 592 | 1220 | 71.0 | <0.5 | <0.5 | 756 | <1.0 | 0.29 | 227 | 158 | 41.9 | 71.4 | 0.030 | 1.02 | | 0.80 | 14.7 | 1.83 |
| Nov-18 | 2320 | 7.90 | 615 | 1250 | 104 | 0.50 | <0.5 | 773 | <1.0 | <0.05 | 218 | 171 | 47.3 | 73.5 | <0.010 | 0.77 | 0.92 | 0.18 | 19.2 | 0.90 |
| Oct-19 | 2080 | 7.73 | 648 | 1170 | 87.8 | <0.5 | <0.5 | 639 | <2.0 | 0.08 | 198 | 165 | 47.3 | 72.8 | <0.010 | 0.94 | 1.09 | 0.97 | 11.0 | 1.58 |
| Oct-20 | 2280 | 7.87 | 723 | 1270 | 97.6 | <0.5 | <0.5 | 697 | <1.0 | 0.07 | 210 | 180 | 47.7 | 75.0 | <0.010 | 0.95 | 0.99 | 0.34 | 12.3 | 1.22 |
| Oct-21 | 2320 | 7.51 | 715 | 1200 | 76.1 | <0.14 | <0.11 | 674 | <0.26 | 0.03 | 207 | 167 | 41.8 | 74.6 | 0.031 | 1.12 | 1.27 | 0.28 | 71.5 | 1.55 |
| Sep-22 | 2290 | 7.63 | 710 | 1070 | 80.9 | <0.14 | <0.11 | 648 | <0.26 | 0.15 | 218 | 127 | 46.2 | 89.3 | 0.033 | 0.86 | 0.96 | 0.24 | 22.0 | 1.19 |
| Nov-23 | 2150 | 7.83 | 742 | 1020 | 74.6 | 0.42 | <0.05 | 471 | <0.13 | 0.12 | 184 | 136 | 36.4 | 59.6 | 0.025 | 0.61 | 0.87 | <0.02 | 11.9 | 0.18 |
| Nov-24 | 2590 | 7.47 | 831 | 1150 | 64.3 | <0.14 | <0.11 | 496 | <0.26 | 0.15 | 209 | 153 | 40.9 | 62.6 | <0.020 | 0.78 | 1.19 | 0.17 | 22.4 | 0.77 |
| | 2000 | ASSESS. | | 1,00 | 00 | V. 1 T | <u> </u> | ,,,, | 5.25 | 55 | | | ,0.0 | 02.0 | 0.020 | 5.1.5 | 11.15 | V | | |
| Average | 2460 | 7.55 | 696 | 1250 | 111 | 0.21 | <0.5 | 703 | <1.0 | 0.18 | 202 | 156 | 61.7 | 72.2 | 4.30 | 0.89 | 1.04 | 0.77 | 16.6 | 1.82 |
| Std. Dev. | 315 | 0.26 | 75.4 | 287 | 46 | 0.20 | NA | 193 | NA | 0.10 | 45.3 | 31.9 | 23.4 | 13.1 | 6.8 | 0.206 | NA | 0.77 | 11.3 | 0.96 |
| Old. Dev. | 010 | 0.20 | 73.4 | 201 | 40 | 0.20 | 14/4 | 190 | INA | 0.20 | 40.0 | 01.0 | 20.4 | 10.1 | 0.0 | 0.200 | IVA | 0.41 | 11.0 | 0.50 |

Monitoring Well OW-4 (Silt Loam Unit)

| Monitoring V | | | ո Unit) | | | | | | | | | | | | | | | | | |
|------------------|--------------|--------------|------------|------------|--------------|----------------|----------------|--------------|----------------|---------------|--------------|--------------|--------------|--------------|------------|----------------|-------|---------------|-------------|--------------|
| Parameter | Conductivity | pН | Alkalinity | Hardness | Chloride | Nitrate | Nitrite | Sulphate | Phosphate | Phosphorus | Calcium | Magnesium | Sodium | Potassium | Iron | Manganese | Boron | Ammonia | DOC | TKN |
| UNITS | uS/cm | Unitless | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L |
| odws | NV | 6.5 to 8.5 | 30 to 500 | 80 to 100 | 250 | 10 | 1.0 | 500 | NV | NV | NV | NV | 200 | NV | 0.3 | 0.05 | 5 | NV | 5.0 | NV |
| | NA | OG | OG | OG | AO | MAC | MAC | AO | NA | NA | NA | NA | AO | NA | AO | AO | IMAC | NA | AO | NA |
| RUC | NV | 6.5 to 8.5 | 355 | 261 | 127 | 2.58 | 0.25 | 261 | NV | NV | NV | NV | 101 | NV | 1.83 | 0.31 | 1.26 | NV | 30.2 | NV |
| Jan-01 | NM | NM | NM | NM | NM | NM | NM | NM | NM | NM | NM | NM | NM | NM | NM | NM | | NM | NM | NM |
| Jun-01 | 513 | 7.72 | 252 | 276 | 3.2 | NM | NM | 44.4 | NM | NM | NM | NM | 8.2 | NM | 4.65 | NM | | 0.19 | 13.5 | 0.56 |
| Dec-01 | 454 | 7.77 | 256 | 1060 | 1.7 | NM | NM | 20.9 | NM | NM | NM | NM | 6.0 | NM | 1.17 | NM | | 0.21 | 11.1 | 0.62 |
| Jun-02 | 447 | 7.66 | 232 | 254 | 1.3 | NM | NM | 12.3 | NM | NM | NM | NM | 7.8 | NM | 0.25 | NM | | 0.12 | 10.1 | 1.19 |
| Oct-02 | 420 418 | 8.05 7.92 | 238 225 | 231 216 | 1.3 1.0 | NM NM | NM NM | 17.5 8.4 | NM NM | NM NM | NM NM | NM NM | NM 4.7 | NM NM | NM 1.38 | NM NM | | 0.11 0.11 | 9.8 | 0.47 0.41 |
| May-03 Nov-03 | 446 | 7.92 NM | 227 | 267 | 7.0 | NM | NM | 6.9 | NM | NM | NM | NM | 8.3 | NM | 0.71 | NM | | 0.11 | 9.6 | 0.41 |
| May-04 | 416 | 7.81 | 227 | 232 | 1.3 | NM | NM | 6.6 | NM | NM | NM | NM | 4.5 | NM | 1.86 | NM | | 0.05 | 7.7 | 0.42 |
| Nov-04 | NM | NM | 228 | NM | 0.9 | NM | NM | 9.9 | NM | NM | NM | NM | 6.0 | NM | 0.75 | NM | | 0.13 | 10.4 | NM |
| Jun-05 | 395 | NM | 217 | NM | 4.12 | 0.20 | NM | 10.2 | NM | NM | NM | NM | 5.6 | NM | ND | NM | | 0.13 | NM | NM |
| Dec-05 | 378 | 8.20 | 239 | 210 | 2.0 | NM | NM | 9.0 | NM | NM | NM | NM | 5.5 | NM | 0.21 | NM | | NM | 8.9 | 2.00 |
| Apr-06 | 421 | 7.91 | 219 | 228 | 0.67 | <0.05 | <0.05 | 6.91 | NM | NM | NM | NM | 4.48 | NM | 4.92 | NM | | 0.08 | NM | NM |
| Oct-06 | 390 | 8.34 | 220 | 215 | 1.17 | 0.11 | <0.05 | 5.7 | <0.10 | 0.79 | 56.8 | 17.7 | 3.39 | 2.03 | 0.18 | 0.022 | | 0.00 | NM | NM |
| Apr-07 | 431 | 7.87 | 217 | 232 | 1.93 | 0.06 | <0.05 | 14.5 | <0.10 | 1.51 | 61.8 | 18.9 | 3.95 | 1.96 | 0.15 | 0.022 | | 0.10 | NM | NM |
| Nov-07 | 423 | 7.98 | 220 | 245 | 1.46 | <0.05 | <0.05 | 11.0 | <0.10 | 0.64 | 66.8 | 19.1 | 3.43 | 1.35 | 6.85 | 0.247 | | <0.05 | NM | NM |
| Apr-08 | 429 | 8.27 | 231 | 232 | 0.97 | <0.05 | <0.05 | 15.3 | <0.10 | 0.42 | 62.4 | 18.4 | 3.38 | 16.8 | 0.15 | 0.043 | | <0.05 | NM | NM |
| Oct-08 | 445 | 8.19 | 221 | 218 | 1.57 | <0.05 | <0.05 | 12.4 | <0.10 | 0.46 | 58.5 | 17.4 | 3.18 | 1.34 | 0.07 | 0.056 | | 0.12 | NM | NM |
| Apr-09 | 436 | 8.00 | 211 | 248 | 0.79 | <0.05 | <0.05 | 20.7 | <0.10 | 0.13 | 67.0 | 19.7 | 3.59 | 1.59 | 0.33 | 0.055 | | <0.05 | NM | NM |
| Nov-09 | 428 | 8.15 | 227 | 232 | 0.79 | <0.05 | <0.05 | 8.69 | <0.10 | 0.15 | 62.1 | 18.6 | 3.39 | 1.33 | 0.15 | 0.043 | | < 0.05 | NM | NM |
| Apr-10 | 415 | 8.20 | 225 | 246 | 2.00 | 0.07 | <0.05 | 16.2 | <0.10 | NM | 66.5 | 19.3 | 3.56 | 1.33 | < 0.01 | 0.041 | | <0.05 | 8.4 | 0.23 |
| Nov-10 | 394 | 8.05 | 227 | 257 | 1.02 | <0.05 | <0.05 | 12.8 | <0.10 | 0.33 | 69.9 | 20.1 | 3.87 | 1.47 | <0.01 | 0.043 | | <0.05 | NM | NM |
| Apr-11 | 439 | 8.08 | 222 | 239 | 1.11 | <0.05 | <0.05 | 17.2 | <0.10 | 0.28 | 64.3 | 19.0 | 3.25 | 1.52 | <0.01 | 0.041 | | 0.04 | 7.6 | 0.55 |
| Nov-11 | 360 | 8.07 | 236 | 236 | 1.38 | <0.05 | <0.05 | 14.3 | <0.10 | <0.05 | 63.5 | 18.9 | 3.37 | 1.62 | <0.01 | 0.040 | | 0.06 | 9.1 | 0.35 |
| Apr-12 | 417 | 8.15 | 220 | 230 | 1.23 | <0.05 | <0.05 | 13.4 | <0.10 | 0.06 | 61.8 | 18.3 | 3.19 | 1.37 | 0.06 | 0.035 | | <0.05 | 7.6 | 0.76 |
| Nov-12 | 389 | 8.08 | 223 | 228 | 1.32 | <0.05 | <0.05 | 7.92 | <0.10 | 0.09 | 61.2 | 18.3 | 3.60 | 1.28 | 0.10 | 0.049 | | <0.05 | 9.7 | 0.46 |
| Apr-13 | 458 | 8.03 | 232 | 241 | 1.38 | <0.05 | <0.05 | 14.8 | <0.10 | 0.20 | 64.7 | 19.3 | 3.27 | 1.24 | <0.01 | 0.039 | | <0.05 | 7.7 | 0.47 |
| Nov-13 | 459 | 8.24 | 218 | 262 | 1.28 | <0.05 | <0.05 | 10.9 | <0.10 | 0.14 | 70.8 | 20.8 | 3.58 | 1.46 | 0.10 | 0.046 | | <0.05 | NM | NM |
| May-14 | 459 | 8.24 | 235 | 256 | 1.42 | 0.46 | <0.05 | 13.7 | <0.10 | 0.09 | 67.7 | 21.0 | 3.75 | 2.98 | 0.02 | 0.037 | | 0.37 | 7.6 | 0.82 |
| Oct-14 10 | 433 | 7.84 | 222 | 241 | 1.52 | <0.10 | <0.10 | 13.5 | <0.20 | 0.08 | 64.5 | 19.3 | 3.23 | 1.56 | 0.22 | 0.043 | | 0.09 | 8.9 | 0.37 |
| Apr-15 | 413 | 7.87 | 218 | 211 | 1.40 | <0.05 | <0.05 | 13.2 | <0.10 | 0.25 | 56.5 | 17.1 | 3.20 | 1.58 | 0.07 | 0.033 | | 0.03 | 8.1 | 0.32 |
| Oct-15 | 446 | 7.99 | 232 | 231 | 2.01 | <0.10 | <0.10 | 13.5 | <0.20 | 0.09 | 62.5 | 18.1 | 3.26 | 1.56 | 3.56 | 0.168 | | 0.06 | 8.0 | 0.32 |
| Apr-16 10 | 439 | 8.05 | 229 | 231 | 1.45 | < 0.05 | <0.05 | 25.7 | <0.10 | 0.05 | 62.2 | 18.4 | 3.30 | 1.20 | 0.03 | 0.030 | | 0.03 | 8.8 | 0.40 |
| Nov-16 | 432 379 | 8.01 7.97 | 224 194 | 219 206 | 1.24 0.74 | <0.05 <0.05 | <0.05 <0.05 | 12.7 10.0 | <0.10 <0.10 | 0.07 <0.05 | 59.8 55.2 | 16.9 16.6 | 3.01 | 1.08 1.06 | 0.21 | 0.024 0.030 | | <0.02 0.10 | 8.2 | 0.31 0.27 |
| Apr-17 | 477 | 8.17 | 235 | 206 | 1.47 | <0.05 | <0.05 | 10.0 | <0.10 | 0.06 | 58.5 | 18.1 | 2.63 3.16 | 1.06 | 0.57 | 0.030 | | 0.10 | 7.5 11.5 | 0.27 |
| Sep-17 May-18 | 380 | 7.97 | 200 | 200 | 1.70 | <0.03 | <0.03 | 16.0 | <0.10 | <0.10 | 53.0 | 16.0 | 2.70 | 0.97 | <0.10 | 0.035 | | <0.050 | 6.9 | 0.20 |
| Nov-18 | 455 | 7.98 | 233 | 233 | 4.41 | 0.12 | <0.010 | 14.8 | <0.10 | <0.10 | 62.5 | 18.7 | 4.88 | 1.35 | 0.021 | 0.014 | 0.031 | <0.030 | 10.8 | <0.10 |
| Apr-19 | 432 | 7.55 | 247 | 216 | 1.22 | < 0.05 | <0.05 | 11.2 | <0.10 | 0.08 | 58.0 | 17.2 | 3.17 | 1.19 | 0.021 | 0.008 | <0.10 | 0.02 | 9.4 | 0.26 |
| Oct-19 | 407 | 7.63 | 221 | 229 | 1.46 | 0.14 | <0.05 | 12.0 | <0.10 | 0.08 | 61.0 | 18.7 | 3.17 | 1.32 | 0.020 | 0.030 | 0.085 | <0.02 | 9.6 | 0.26 |
| Apr-20 | 510 | 7.71 | 230 | 224 | 1.66 | < 0.05 | <0.05 | 13.8 | <0.10 | 0.09 | 59.7 | 18.3 | 3.03 | 1.14 | 0.072 | 0.010 | 0.035 | 0.02 | 11.0 | 0.41 |
| Oct-20 | 401 | 8.06 | 218 | 215 | 1.58 | 0.18 | <0.05 | 11.0 | <0.10 | 0.10 | 56.3 | 18.0 | 3.10 | 1.10 | 0.15 | <0.002 | 0.038 | <0.02 | 10.6 | 0.33 |
| May-21 | 449 | 7.85 | 218 | 230 | 1.63 | <0.05 | <0.05 | 11.7 | <0.10 | 0.07 | 61.6 | 18.5 | 3.25 | <2.50 | 1.35 | 0.024 | 0.045 | 0.03 | 6.7 | 0.42 |
| Oct-21 | 434 | 7.89 | 224 | 215 | 1.29 | <0.05 | <0.05 | 10.9 | <0.10 | 0.05 | 56.9 | 17.8 | 2.76 | 1.01 | 1.01 | 0.032 | 0.033 | <0.02 | 35.9 | 0.27 |
| Apr-22 | 472 | 7.76 | 204 | 208 | 1.35 | <0.05 | <0.05 | 13.3 | <0.10 | <0.02 | 55.4 | 17.0 | 2.95 | 1.02 | 0.51 | 0.032 | 0.034 | <0.02 | 9.5 | 0.38 |
| Sep-22 | 404 | 8.09 | 233 | 257 | 1.68 | <0.05 | <0.05 | 13.0 | <0.10 | 0.03 | 69.6 | 20.1 | 4.12 | 0.91 | 0.69 | 0.025 | 0.036 | 0.02 | 10.3 | 0.26 |
| Apr-23 | 457 | 7.83 | 221 | 205 | 1.73 | 0.05 | <0.05 | 13.4 | <0.10 | 0.03 | 53.8 | 17.1 | 3.29 | 1.01 | 0.56 | 0.027 | 0.026 | <0.02 | 10.5 | 0.21 |
| Nov-23 | 394 | 7.76 | 250 | 211 | 1.72 | 0.11 | <0.05 | 11.5 | <0.10 | 0.05 | 56.9 | 16.7 | 2.79 | 1.06 | 0.18 | 0.008 | 0.049 | <0.02 | 6.5 | <0.10 |
| Apr-24 | 434 | 7.88 | 257 | 255 | 1.44 | <0.05 | <0.05 | 11.6 | <0.10 | 0.03 | 66.3 | 21.8 | 3.10 | 1.26 | 0.12 | 0.031 | 0.040 | 0.05 | 10.7 | 0.12 |
| Nov-24 | 441 | 7.83 | 266 | 216 | 1.48 | <0.05 | <0.05 | 10.5 | <0.10 | 0.11 | 57.4 | 17.7 | 2.92 | 0.88 | < 0.020 | 0.025 | 0.038 | <0.02 | 10.6 | 0.26 |
| | | | | | | | | | | | | | | | | | | | | |
| Average | 429 | 7.97 | 228 | 249 | 1.66 | <0.05 | <0.05 | 13.2 | <0.10 | 0.19 | 61.44 | 18.46 | 3.91 | 1.78 | 0.74 | 0.042 | 0.042 | 0.07 | 9.99 | 0.46 |
| Std. Dev. | 31.8 | 0.18 | 13.8 | 123.5 | 1.06 | NA | NA | 5.94 | NA | 0.29 | 4.66 | 1.28 | 1.38 | 2.60 | 1.44 | 0.044 | 0.015 | 0.07 | 4.64 | 0.34 |

Monitoring Well OW-5 (Shallow Sand Unit)

| | ven Ovv-5 | Charles and the second | account the entire | | | | | | rea a s | | | 12.2 | | | | 1 | _ | Carl In In | | |
|-----------|--------------|------------------------|--------------------|----------|------|---------|---------|------|---------|------------|-------|------|--------|-----------|---------|-----------|------|------------|-------|------|
| Parameter | Conductivity | pН | | Hardness | 1000 | Nitrate | Nitrite | | | Phosphorus | 1,000 | | Sodium | Potassium | 7937 | Manganese | | Ammonia | DOC | TKN |
| UNITS | uS/cm | Unitless | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L |
| ODWS | NV | | 30 to 500 | | 250 | 10 | 1.0 | 500 | NV | NV | NV | NV | 200 | NV | 0.3 | 0.05 | 5 | NV | 5.0 | NV |
| | NA | OG | OG | OG | AO | MAC | MAC | AO | NA | NA | NA | NA | AO | NA | AO | AO | IMAC | NA | AO | NA |
| RUC | NV | 6.5 to 8.5 | 355 | 261 | 127 | 2.58 | 0.25 | 261 | NV | NV | NV | NV | 101 | NV | 1.83 | 0.31 | 1.26 | NV | 30.2 | NV |
| Apr-10 | 1040 | 7.98 | 368 | 512 | 103 | 0.05 | <0.05 | 79.3 | <0.10 | NM | 128 | 46.7 | 17.8 | 11.0 | 1.47 | 0.595 | | 0.07 | 11.1 | 0.58 |
| Nov-10 | 1040 | 7.86 | 421 | 613 | 104 | <0.05 | <0.05 | 82.4 | <0.10 | 1.42 | 155 | 54.9 | 18.4 | 13.0 | <0.01 | 0.597 | | 0.06 | NM | NM |
| Apr-11 | 955 | 7.83 | 376 | 483 | 60.4 | <0.05 | <0.05 | 82.5 | <0.10 | 2.41 | 119 | 45.1 | 14.8 | 11.1 | 0.02 | 0.474 | | 0.05 | 6.7 | 0.74 |
| Nov-11 | 733 | 7.81 | 365 | 436 | 34.6 | <0.05 | <0.05 | 65.2 | <0.10 | <0.05 | 109 | 39.8 | 12.9 | 11.4 | <0.01 | 0.464 | | 0.13 | 9.0 | 0.58 |
| Apr-12 | 618 | 8.05 | 266 | 305 | 24 | <0.05 | <0.05 | 35.3 | <0.10 | 0.50 | 78 | 27 | 9.15 | 7.63 | 0.08 | 0.302 | | 0.09 | 7.1 | 0.86 |
| Nov-12 | 749 | 7.90 | 353 | 420 | 32 | <0.05 | <0.05 | 54.0 | <0.10 | 0.75 | 107 | 37 | 11.9 | 9.88 | <0.01 | 0.476 | | <0.05 | 7.6 | 0.63 |
| Apr-13 | 984 | 7.95 | 425 | 497 | 28.6 | <0.25 | <0.25 | 74.5 | <0.50 | 0.22 | 121 | 47.3 | 12.4 | 11.9 | <0.01 | 0.724 | | 0.06 | 7.3 | 0.70 |
| Nov-13 | 955 | 8.13 | 356 | 512 | 66.5 | <0.25 | <0.25 | 57.4 | <0.50 | 0.51 | 126 | 47.9 | 15.7 | 14.5 | <0.01 | 0.716 | | 0.14 | NM | NM |
| May-14 | 1040 | 8.04 | 407 | 509 | 46.3 | <0.25 | <0.25 | 75.0 | <0.50 | 0.36 | 124 | 48.3 | 15.9 | 12.7 | 0.04 | 0.678 | | 0.17 | 8.3 | 0.82 |
| Oct-14 | 996 | 7.45 | 376 | 484 | 77.3 | <0.25 | <0.25 | 65.2 | <0.50 | 0.57 | 121 | 44.2 | 16.6 | 12.0 | 0.03 | 0.565 | | 0.21 | 7.9 | 0.53 |
| Apr-15 | 1170 | 7.55 | 397 | 547 | 116 | <0.25 | <0.25 | 72.6 | <0.50 | 0.39 | 138 | 49.1 | 18.7 | 13.7 | 0.03 | 0.707 | | 0.10 | 5.6 | 0.46 |
| Oct-15 | 1400 | 7.66 | 393 | 627 | 192 | <0.25 | <0.25 | 77.0 | <0.50 | 0.94 | 163 | 53.4 | 22.1 | 15.1 | 13.6 | 1.050 | | 0.06 | 5.0 | 0.27 |
| Nov-15 | 1440 | 8.14 | 378 | 678 | 233 | <0.25 | <0.25 | 58.8 | <0.50 | 0.18 | 180 | 55.6 | 28.1 | 15.7 | <0.010 | 0.929 | | 0.13 | 4.4 | 0.52 |
| Apr-16 | 961 | 7.72 | 349 | 440 | 91 | <0.25 | < 0.25 | 68.1 | <0.50 | 1.7 | 114 | 37.7 | 18.7 | 10.2 | 0.03 | 0.601 | | 0.13 | 10.0 | 0.64 |
| Nov-16 | 1460 | 7.62 | 376 | 627 | 264 | <0.25 | <0.25 | 57.8 | <0.50 | 0.52 | 167 | 51.0 | 27.7 | 14.0 | 0.014 | 0.777 | | 0.10 | 4.1 | 0.40 |
| Apr-17 | 1160 | 7.93 | 376 | 530 | 161 | < 0.25 | < 0.25 | 48.0 | < 0.50 | 1.38 | 139 | 44.5 | 20.3 | 11.6 | 0.030 | 0.444 | | 0.19 | 12.5 | 0.44 |
| Sep-17 | 1380 | 8.00 | 341 | 547 | 205 | <0.25 | <0.25 | 49.2 | <0.50 | 0.10 | 141 | 47.3 | 23.2 | 13.2 | <0.01 | 0.639 | | 0.10 | 15.7 | 0.42 |
| May-18 | 1300 | 7.77 | 370 | 580 | 150 | <0.10 | <0.010 | 49.0 | <0.010 | <0.10 | 150 | 51.0 | 26.0 | 11.0 | <0.10 | 0.710 | | 0.18 | 4.5 | 0.27 |
| Nov-18 | 914 | 7.85 | 331 | 381 | 94 | < 0.25 | < 0.25 | 43.1 | < 0.50 | < 0.05 | 99 | 32.6 | 14.8 | 8.6 | < 0.010 | 0.268 | 0.51 | 0.03 | 11.3 | 0.47 |
| Apr-19 | 932 | 7.76 | 369 | 411 | 83 | <0.25 | <0.25 | 37.2 | <0.50 | 0.61 | 108 | 34.4 | 17.1 | 8.8 | < 0.01 | 0.518 | 0.54 | 0.09 | 8.3 | 0.54 |
| Oct-19 | 855 | 7.69 | 282 | 418 | 115 | <0.25 | <0.25 | 28.9 | <0.50 | 0.51 | 110 | 34.8 | 13.4 | 7.8 | 0.032 | 0.432 | 0.33 | 0.05 | 9.2 | 0.27 |
| Apr-20 | 1280 | 7.67 | 341 | 513 | 146 | <0.25 | < 0.25 | 49.8 | <0.50 | 1.19 | 135 | 42.8 | 21.4 | 9.1 | 0.035 | 0.615 | 0.68 | 0.16 | 8.6 | 0.43 |
| Oct-20 | 1240 | 7.90 | 337 | 580 | 212 | <0.25 | <0.25 | 55.7 | <0.50 | 0.46 | 151 | 49.2 | 22.8 | 9.2 | < 0.010 | 0.661 | 0.82 | 0.08 | 5.6 | 0.39 |
| May-21 | 1050 | 7.68 | 299 | 287 | 156 | <0.25 | <0.25 | 47.6 | <0.50 | 1.03 | 75.8 | 23.7 | 10.6 | 4.2 | 2.45 | 0.516 | 0.49 | <0.02 | 8.0 | 0.42 |
| Oct-21 | 915 | 7.65 | 349 | 469 | 77.1 | <0.05 | <0.05 | 43.1 | <0.10 | 0.77 | 125 | 38.1 | 17.0 | 7.7 | 0.016 | 0.580 | 0.94 | <0.02 | 65.4 | 0.41 |
| Apr-22 | 869 | 7.70 | 324 | 353 | 34.3 | <0.05 | <0.05 | 36.4 | <0.10 | 1.02 | 95 | 28.3 | 12.6 | 6.0 | 0.031 | 0.418 | 0.61 | <0.02 | 5.6 | 0.74 |
| Sep-22 | 837 | 7.84 | 380 | 420 | 23.7 | <0.05 | 0.38 | 47.6 | <0.10 | 0.86 | 120 | 29.2 | 10.0 | 6.9 | 0.034 | 0.365 | 0.43 | <0.02 | 9.3 | 0.72 |
| Apr-23 | 789 | 7.59 | 353 | 379 | 19.3 | 0.08 | <0.05 | 50.4 | <0.10 | 1.18 | 103 | 29.6 | 8.54 | 6.24 | 0.026 | 0.448 | 0.34 | <0.02 | 14.0 | 1.07 |
| Nov-23 | 794 | 7.56 | 414 | 399 | 14.7 | 0.11 | <0.05 | 57.0 | <0.10 | 1.89 | 110 | 30.1 | 6.54 | 5.28 | 0.046 | 0.145 | 0.35 | <0.02 | 8.2 | 0.88 |
| Apr-24 | 952 | 7.50 | 485 | 520 | 14.2 | <0.05 | <0.05 | 74.8 | <0.10 | 1.11 | 137 | 43.1 | 8.75 | 6.96 | <0.020 | 0.77 | 0.48 | 0.40 | 12.1 | 1.06 |
| Nov-24 | 1030 | 7.53 | 553 | 507 | 12.7 | <0.05 | <0.05 | 89.7 | <0.10 | 0.56 | 137 | 40.1 | 9.12 | 6.34 | 0.025 | 0.60 | 0.55 | <0.02 | 11.7 | 0.50 |
| | | | | | | | | | | | | | | | | | | | | |
| Average | 1027 | 7.78 | 371 | 483 | 96.5 | <0.25 | <0.25 | 58.5 | <0.50 | 0.77 | 125 | 41.4 | 16.2 | 10.1 | 0.59 | 0.574 | 0.54 | 0.12 | 10.49 | 0.58 |
| Std. Dev. | 219 | 0.19 | 54.4 | 94 | 71.6 | NA | NA | 15.9 | NA | 0.58 | 24.3 | 8.91 | 5.80 | 3.10 | 2.47 | 0.187 | NA | 0.08 | 10.96 | 0.22 |

Monitoring Well OW-6 (Shallow Sand Unit)

| Deservator | | | | | | Oblanta | N 1'4 4 | N 124 - 24 | 10-1-1 | I Diamania d | Diameter | 0-1-1-1 | N.A | 0 - 1 | D. t | 1 | IN 4 | D | I A 1 | D00 1 | TIZA |
|------------|-----|-----------|------------|-----------|------|------------|------------|------------|------------|-----------------|-----------------|---------|-------------------|-------|--------------|--------------|----------------|----------------|---------|-------|------------|
| Parameter | | luctivity | pH | | 200 | Chloride | Nitrate | Nitrite | 1.00 | - | Phosphorus | 7000 | | | Potassium | | Manganese | Boron | Ammonia | DOC | TKN |
| UNIT | | S/cm | Unitless | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L |
| ODW | | ٧V | 6.5 to 8.5 | 30 to 500 | | 250 | 10 | 1.0 | 500 | NV | NV | NV | NV | 200 | NV | 0.3 | 0.05 | 5 | NV | 5.0 | NV |
| | _ | AV | OG | OG | OG | AO | MAC | MAC | AO | NA | NA | NA | NA | AO | NA | AO | AO | IMAC | NA | AO | NA |
| RU | _ | VV | 6.5 to 8.5 | 355 | 261 | 127 | 2.58 | 0.25 | 261 | NV | NV | NV | NV | 101 | NV | 1.83 | 0.31 | 1.26 | NV | 30.2 | NV |
| Apr-10 | 7 | '98 | 8.29 | 380 | 387 | 34.5 | 0.91 | <0.05 | 39.6 | <0.10 | NM | 105 | 30.3 | 30.2 | 18.2 | 1.32 | 0.028 | | <0.05 | 21.2 | 2.29 |
| Nov-10 | _ | 97 | 8.10 | 379 | 415 | 23.6 | 0.12 | <0.05 | 15.5 | <0.10 | 1.89 | 114 | 31.6 | 16.9 | 6.69 | <0.01 | 0.532 | | 0.17 | NM | NM |
| Apr-11 | 7 | 72 | 8.14 | 363 | 384 | 30.6 | 0.12 | <0.05 | 22.1 | <0.10 | 0.77 | 105 | 29.7 | 19.9 | 7.28 | 0.04 | 3.53 | | 0.02 | 12.0 | 1.79 |
| Nov-11 | 5 | 78 | 8.27 | 335 | 366 | 22.0 | < 0.05 | < 0.05 | 12.5 | <0.10 | < 0.05 | 100 | 28.3 | 15.4 | 6.06 | 0.09 | 1.39 | | 0.26 | 14.8 | 1.34 |
| Apr-12 | 6 | 89 | 8.26 | 337 | 345 | 26.3 | 0.15 | <0.05 | 15.3 | <0.10 | 0.70 | 94 | 26.8 | 14.6 | 5.34 | 0.04 | 1.84 | | 0.15 | 11.3 | 1.37 |
| Nov-12 | 6 | 36 | 8.07 | 329 | 341 | 27.1 | 0.11 | <0.05 | 12.8 | <0.10 | 1.66 | 93 | 26.7 | 13.9 | 4.60 | 1.02 | 1.17 | 0.10 | 0.13 | 12.4 | 1.29 |
| Apr-13 | 7 | 53 | 8.04 | 320 | 346 | 37.0 | 0.44 | <0.25 | 22.1 | < 0.50 | 9.09 | 93 | 27.4 | 20.5 | 6.79 | 1.08 | 1.67 | 0.09 | 1.42 | 9.6 | 2.5 |
| Nov-13 | 7 | '36 | 8.15 | 325 | 364 | 29.4 | 0.12 | <0.10 | 16.5 | <0.20 | 1.27 | 99.1 | 28.3 | 17.9 | 5.76 | 0.02 | 0.081 | | 0.08 | NM | NM |
| May-14 | 7 | 62 | 8.11 | 332 | 359 | 30.9 | <0.25 | <0.25 | 20.8 | <0.50 | 1.37 | 96.4 | 28.7 | 18.4 | 5.48 | 0.01 | 0.64 | | 0.46 | 9.3 | 1.28 |
| Oct-14 1 | 0 7 | 82 | 7.68 | 361 | 372 | 35.3 | <0.25 | <0.25 | 15.5 | <0.50 | 1.63 | 102 | 28.5 | 23.3 | 6.35 | 0.01 | 0.64 | | 0.17 | 11.9 | 0.80 |
| Apr-15 | 7 | '37 | 7.96 | 345 | 364 | 36.4 | <0.25 | <0.25 | 21.0 | <0.50 | 2.90 | 98.4 | 28.8 | 23.5 | 7.72 | 0.03 | 0.42 | | 0.17 | 10.2 | 1.07 |
| Oct-15 | 9 | 54 | 8.08 | 415 | 416 | 56.1 | <0.25 | <0.25 | 24.0 | < 0.50 | < 0.05 | 114 | 31.9 | 38.3 | 12.8 | 62.2 | 3.97 | | 0.17 | 10.8 | 1.01 |
| Apr-16 1 | 0 7 | '50 | 8.16 | 352 | 367 | 35.0 | <0.25 | <0.25 | 28.5 | < 0.50 | 2.86 | 99.8 | 28.6 | 19.5 | 4.6 | 0.04 | 0.10 | | 0.27 | 15.1 | 0.96 |
| Nov-16 | 8 | 38 | 8.14 | 379 | 386 | 34.8 | 0.91 | <0.25 | 24.4 | < 0.50 | 0.87 | 109 | 27.6 | 25.5 | 7.17 | 0.02 | 0.075 | | <0.02 | 9.2 | 0.81 |
| Apr-17 | 7 | 53 | 8.20 | 339 | 385 | 26.9 | <0.25 | <0.25 | 24.2 | < 0.50 | 1.30 | 106 | 29.2 | 20.3 | 6.79 | <0.01 | 0.61 | | 0.72 | 12.3 | 1.13 |
| Sep-17 | 1 | 110 | 8.15 | 490 | 433 | 44.4 | 0.27 | <0.25 | 22.4 | < 0.50 | 5.21 | 120 | 32.4 | 37.3 | 20.0 | 0.020 | 0.65 | | 0.06 | 5.5 | 2.09 |
| Nov-18 | 8 | 23 | 8.02 | 388 | 400 | 31.9 | <0.25 | <0.25 | 34.6 | < 0.50 | < 0.05 | 110 | 30.5 | 20.2 | 6.4 | 0.017 | <0.002 | 0.16 | <0.02 | 16.1 | 0.61 |
| Apr-19 | 7 | 91 | 7.86 | 411 | 366 | 25.2 | <0.25 | <0.25 | 28.3 | < 0.50 | 0.77 | 101 | 27.7 | 18.9 | 7.1 | <0.01 | 0.82 | 0.11 | 0.21 | 11.4 | 1.97 |
| Oct-19 | 7 | 22 | 7.85 | 359 | 376 | 23.4 | <0.10 | <0.10 | 33.2 | <0.20 | 3.04 | 103 | 28.9 | 15.9 | 7.1 | <0.01 | 0.14 | 0.18 | 0.04 | 13.0 | 0.72 |
| Apr-20 | 8 | 77 | 7.79 | 342 | 374 | 23.9 | <0.25 | <0.25 | 43.8 | < 0.50 | 4.55 | 101 | 29.5 | 13.0 | 4.9 | < 0.010 | 0.076 | 0.11 | 0.12 | 19.5 | 0.86 |
| Oct-20 | 7 | '39 | 8.08 | 366 | 371 | 24.7 | 0.17 | <0.10 | 35.6 | <0.20 | 2.26 | 99.4 | 29.7 | 15.0 | 6.7 | <0.010 | 0.026 | 0.16 | 0.03 | 20.1 | 0.70 |
| May-21 | 7 | 25 | 7.79 | 325 | 344 | 27.2 | <0.10 | <0.10 | 22.3 | <0.20 | 1.44 | 96 | 25.5 | 14.4 | 5.5 | 3.68 | 0.65 | 0.15 | 0.10 | 18.0 | 1.12 |
| Oct-21 | 7 | 85 | 7.77 | 367 | 366 | 22.7 | 0.11 | <0.05 | 29.6 | <0.10 | 2.67 | 100 | 28.2 | 15.4 | 6.4 | 0.016 | 0.06 | 0.23 | <0.02 | 170 | 0.96 |
| Apr-22 | 8 | 800 | 7.62 | 306 | 339 | 21.0 | 0.21 | < 0.05 | 30.7 | <0.10 | 1.06 | 94 | 25.5 | 17.3 | 7.8 | 0.035 | 0.25 | 0.14 | 0.09 | 11.3 | 0.94 |
| Sep-22 | 8 | 14 | 8.00 | 388 | 391 | 25.8 | <0.05 | 0.36 | 28.9 | <0.10 | 2.04 | 105 | 31.2 | 15.1 | 7.2 | 0.043 | 0.13 | 0.20 | 0.09 | 16.8 | 0.73 |
| Apr-23 | 7 | 69 | 7.73 | 345 | 340 | 21.0 | <0.05 | <0.05 | 38.2 | <0.10 | 2.80 | 92 | 27.0 | 11.9 | 3.80 | 0.017 | 0.36 | 0.08 | 0.03 | 14.2 | 1.77 |
| Nov-23 | 7 | 75 | 7.85 | 420 | 402 | 21.7 | 0.09 | <0.05 | 32.9 | <0.10 | 2.02 | 112 | 29.8 | 13.8 | 4.99 | 0.036 | 0.041 | 0.16 | 0.03 | 13.8 | 4.40 |
| Apr-24 | 8 | 82 | 7.67 | 416 | 419 | 20.1 | <0.05 | <0.05 | 34.6 | <0.10 | 2.49 | 113 | 33.2 | 13.1 | 4.53 | < 0.020 | 0.63 | 0.11 | 0.13 | 18.0 | 3.55 |
| Nov-24 | 8 | 36 | 7.77 | 512 | 353 | 23.1 | < 0.05 | < 0.05 | 25.6 | <0.10 | 2.32 | 97 | 26.9 | 14.1 | 4.95 | <0.020 | 0.041 | 0.16 | <0.02 | 20.8 | 1.88 |
| | | | 40000000 | | | 1000000000 | SENSON CO. | 000 O.T | 27 2040.00 | 10450ac 1001080 | two can can can | 3904 | 14 14 (5) (4) (4) | | A004170.0000 | 30049704 TUB | 1-630/21 OF 60 | - Carrier of C | | | 2004/91250 |
| Average | 7 | 82 | 7.99 | 370 | 375 | 29.0 | 0.18 | <0.25 | 26.1 | <0.5 | 2.11 | 102 | 28.9 | 19.1 | 7.21 | 2.41 | 0.73 | 0.142 | 0.18 | 19.6 | 1.48 |
| Std. Dev. | 9 | 6.5 | 0.20 | 47.6 | 25.6 | 7.97 | 0.22 | NA | 8.34 | NA | 1.84 | 7.39 | 1.95 | 6.64 | 3.68 | 11.52 | 0.989 | 0.041 | 0.28 | 30.32 | 0.90 |

Monitoring Well OW-7S (Shallow Sand Unit)

| Parameter | Conductivity | На | | Hardness | Chloride | Nitrate | Nitrite | Sulphate | Dhoenhata | Phosphorus | Calcium | Magnesium | Sodium | Potassium | Iron | Manganese | Boron | Ammonia | DOC | TKN |
|-----------|--------------|------------|-----------|------------|-------------|----------|---------------|--------------|-----------|------------|-----------|---------------|-------------|-------------|--------------|------------|-------------|-------------------------|-------|---|
| UNITS | uS/cm | Unitless | ma/L | ma/L | mg/L | ma/L | ma/L | ma/L | mg/L | mg/L | ma/L | ma/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L |
| | NV | 6.5 to 8.5 | 30 to 500 | 80 to 100 | 250 | 10 | 1.0 | 500 | NV | NV | NV | NV | 200 | NV | 0.3 | 0.05 | 5 | NV | 5.0 | NV |
| ODWS | NA NA | OG | OG | OG | AO | MAC | MAC | AO | NA. | NA | NA | NA NA | AO | NA NA | AO | AO | IMAC | NA NA | AO | NA |
| RUC | NV | 6.5 to 8.5 | 355 | 261 | 127 | 2.58 | 0.25 | 261 | NV | NV | NV | NV | 101 | NV | 1.83 | 0.31 | 1.26 | NV | 30.2 | NV |
| Nov-12 | 2110 | 7.64 | 1070 | 929 | 200 | <0.05 | < 0.05 | 3.16 | <0.10 | 16.0 | 245 | 77.0 | 158 | 32.4 | 11.2 | 1.66 | 0.81 | 9.8 | 39.7 | 13.2 |
| Apr-13 | 1910 | 7.86 | 812 | 668 | 158 | <0.5 | <0.5 | 6.55 | <1.0 | 3.94 | 182 | 51.8 | 116 | 21.1 | 9.46 | 1.14 | 0.55 | 15.3 | 26.2 | 22.8 |
| Oct-15 | 2390 | 7.83 | 1200 | 754 | 97.5 | <1.0 | <1.0 | 10.9 | <2.0 | 1.86 | 203 | 60.0 | 115 | 63.3 | 35.0 | 1.66 | 0.55 | 60.7 | 30.5 | 62.1 |
| Apr-16 | 2170 | 7.87 | 1130 | 720 | 77.1 | <0.5 | <0.5 | 20.4 | <1.0 | 3.22 | 200 | 53.6 | 106 | 57.1 | 0.07 | 0.93 | | 59.3 | 33.5 | 59.5 |
| Nov-16 | 1980 | 7.73 | 1040 | 614 | 60.1 | 0.14 | <0.05 | 4.93 | <0.10 | 1.66 | 173 | 44.1 | 71.8 | 59.5 | 0.07 | 0.60 | | 55.3 | 28.0 | 56.4 |
| Apr-17 | 2210 | 7.72 | 1120 | 729 | 87.6 | <0.5 | <0.05 | 7.7 | <1.0 | 1.38 | 189 | 62.5 | 91.2 | 51.1 | 0.03 | 0.68 | | 54.1 | 34.8 | 55.0 |
| Sep-17 | 2130 | 7.70 | 1030 | 497 | 68.9 | <0.25 | <0.25 | 16 | 0.73 | 0.06 | 133 | 40.0 | 185 | 39.5 | 0.13 | 0.65 | | 40.0 | 29.3 | 45.7 |
| May-18 | 2000 | 7.54 | 950 | 650 | 80.0 | <0.10 | <0.010 | <1.0 | <0.010 | <0.10 | 180 | 47.0 | 84 | 52.0 | <0.10 | 0.85 | | 45.0 | 28.0 | 52.0 |
| | 1680 | 7.71 | 839 | 539 | 57.3 | <0.10 | <0.010 | 10.1 | <1.0 | <0.10 | 158 | 35.0 | 122 | 43.6 | 0.02 | 0.65 | 0.74 | 32.4 | 20.6 | 32.8 |
| Nov-18 | 12.07670.353 | 600,000 00 | | 1000000000 | 2005, 100,0 | 28017070 | 1,000,000,000 | 1 1011200000 | 2.332 | 0.000,000 | 0.000.000 | (100,000 a.e. | 100,000,000 | 10000000000 | F-19/25/2011 | 7.500 3000 | UBORGE 7/21 | VIII. 12.11.11.11.11.11 | | 190000000000000000000000000000000000000 |
| Apr-19 | 1680 | 7.55 | 951 | 600 | 46.5 | <0.25 | <0.25 | 5.46 | <0.50 | 1.10 | 181 | 36.0 | 62.3 | 37.1 | <0.01 | 0.87 | 0.80 | 26.8 | 21.6 | 34.0 |
| Oct-19 | 1640 | 7.44 | 879 | 612 | 61.3 | <0.25 | <0.25 | 4.16 | <0.50 | 2.18 | 187 | 35.3 | 84.3 | 42.3 | 0.034 | 0.88 | 0.89 | 42.3 | 22.0 | 40.4 |
| Apr-20 | 2300 | 7.40 | 967 | 653 | 83.4 | <1.0 | <1.0 | 8.90 | <2.0 | 1.34 | 199 | 37.9 | 76.6 | 46.7 | 0.102 | 0.92 | 1.09 | 49.1 | 32.4 | 48.7 |
| Oct-20 | 1910 | 7.63 | 1020 | 645 | 74.6 | <0.25 | <0.25 | 2.83 | <0.50 | 0.53 | 198 | 36.6 | 90.1 | 54.0 | 0.044 | 0.69 | 1.14 | 53.0 | 30.0 | 55.5 |
| May-21 | 2010 | 7.22 | 978 | 639 | 63.6 | <0.5 | <0.5 | 6.80 | <1.0 | 0.73 | 198 | 35.1 | 71.7 | 48.5 | 29.5 | 0.87 | 1.17 | 62.9 | 31.3 | 63.8 |
| Oct-21 | 1920 | 7.24 | 972 | 611 | 55.1 | <0.07 | <0.05 | 1.56 | <0.13 | 1.52 | 183 | 37.3 | 63.9 | 51.2 | 0.061 | 0.96 | 1.20 | 50.5 | 298 | 59.0 |
| Apr-22 | 2230 | 7.26 | 980 | 709 | 76.7 | 0.38 | <0.05 | 1.99 | <0.13 | 0.18 | 217 | 40.6 | 92.5 | 47.8 | 0.055 | 1.07 | 1.57 | 53.3 | 27 | 57.1 |
| Sep-22 | 2180 | 7.34 | 1090 | 549 | 92.2 | < 0.14 | 1.55 | <0.38 | <0.26 | 0.84 | 162 | 35.1 | 93.7 | 59.9 | 0.096 | 0.76 | 1.23 | 61.0 | 43 | 76.5 |
| Apr-23 | 2360 | 7.15 | 1090 | 609 | 95.5 | <0.14 | <0.11 | <0.38 | <0.26 | 0.14 | 185 | 35.7 | 128 | 40.8 | 0.081 | 0.75 | 1.29 | 60.7 | 46 | 61.4 |
| Nov-23 | 2240 | 7.25 | 1170 | 623 | 83.0 | 0.78 | < 0.05 | 9.55 | <0.13 | 0.63 | 191 | 35.4 | 85.1 | 56.1 | 0.086 | 1.11 | 1.44 | 74.0 | 27 | 74.0 |
| Apr-24 | 3050 | 6.98 | 1200 | 794 | 128 | <0.14 | <0.11 | 2.92 | <0.26 | 0.67 | 235 | 50.2 | 120 | 62.3 | 0.15 | 1.55 | 1.94 | 63.5 | 56.9 | 66.0 |
| Nov-24 | 2900 | 7.03 | 1220 | 597 | 126 | <0.14 | <0.11 | 3.08 | <0.26 | 1.03 | 182 | 34.7 | 114 | 53.3 | 0.11 | 1.13 | 1.63 | 90.5 | 51.8 | 344 |
| | | | | | | | | | | | | | | | | | | | | |
| Average | 2143 | 7.48 | 1034 | 654 | 89.2 | <1.0 | <1.0 | 7.06 | <2.0 | 1.86 | 190 | 43.9 | 101 | 48.6 | 4.12 | 0.96 | 1.17 | 50.5 | 45.6 | 65.7 |
| Std. Dev. | 351 | 0.27 | 117 | 95 | 37.0 | NA | NA | 5.03 | NA | 3.40 | 24.5 | 11.5 | 30.6 | 10.5 | 9.9 | 0.33 | 0.38 | 18.6 | 58.63 | 65.7 |

Monitoring Well OW-7D (Deeper Sand Unit)

| Parameter | Conductivity | рН | Alkalinity | Hardness | Chloride | Nitrate | Nitrite | Sulphate | Phosphate | Phosphorus | Calcium | Magnesium | Sodium | Potassium | Iron | Manganese | Boron | Ammonia | DOC | TKN |
|-----------|--------------|------------|------------|-----------|----------|---------|---------|----------|-----------|------------|---------|-----------|--------|-----------|--------|-----------|-------|---------|------|------|
| UNITS | uS/cm | Unitless | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L |
| ODWS | NV | 6.5 to 8.5 | 30 to 500 | 80 to 100 | 250 | 10 | 1.0 | 500 | NV | NV | NV | NV | 200 | NV | 0.3 | 0.05 | 5 | NV | 5.0 | NV |
| ODWS | NA | OG | OG | OG | AO | MAC | MAC | AO | NA | NA | NA | NA | AO | NA | AO | AO | IMAC | NA | AO | NA |
| RUC | NV | 6.5 to 8.5 | 355 | 261 | 127 | 2.58 | 0.25 | 261 | NV | NV | NV | NV | 101 | NV | 1.83 | 0.31 | 1.26 | NV | 30.2 | NV |
| Nov-12 | 778 | 8.10 | 383 | 461 | 19.8 | <0.05 | <0.05 | 78.1 | <0.10 | 3.96 | 122 | 37.9 | 12 | 1.08 | 2.91 | 0.155 | 0.03 | 0.42 | 14.6 | 1.31 |
| Apr-13 | 856 | 8.05 | 387 | 470 | 17.0 | <0.25 | <0.25 | 61.4 | <0.50 | 4.19 | 123 | 39.5 | 9.77 | 1.03 | 2.55 | 0.130 | 0.02 | 0.15 | 13.8 | 1.15 |
| Oct-15 | 893 | 7.92 | 405 | 465 | 20.3 | <0.25 | < 0.25 | 74.8 | < 0.50 | 2.80 | 124 | 37.8 | 10.5 | 1.08 | 15.4 | 1.20 | | 0.32 | 14.2 | 0.87 |
| Nov-16 | 926 | 7.92 | 413 | 488 | 20.7 | < 0.25 | < 0.25 | 78.5 | < 0.50 | 2.69 | 132 | 38.4 | 11.4 | 0.95 | 0.027 | 0.139 | | 0.28 | 15.1 | 0.92 |
| Sep-17 | 994 | 8.02 | 423 | 472 | 18.7 | <0.25 | <0.25 | 76.0 | <0.50 | 1.01 | 123 | 40.1 | 10.9 | 0.88 | 0.030 | 0.152 | | 0.30 | 20.2 | 0.86 |
| Nov-18 | 963 | 7.73 | 427 | 528 | 25.8 | <0.25 | <0.25 | 101 | <0.50 | < 0.05 | 139 | 43.9 | 14.4 | 1.35 | 0.019 | 0.114 | 0.041 | 0.13 | 18.4 | 0.66 |
| Oct-19 | 841 | 7.64 | 366 | 432 | 26.3 | <0.25 | < 0.25 | 113 | < 0.50 | 1.19 | 113 | 36.3 | 29.0 | 1.76 | <0.010 | 0.089 | 0.070 | 0.16 | 16.0 | 0.75 |
| Oct-20 | 890 | 7.89 | 428 | 499 | 22.0 | <0.10 | < 0.10 | 85.2 | <0.20 | 0.78 | 130 | 42.3 | 11.6 | 0.85 | 0.015 | 0.151 | 0.079 | 0.24 | 20.9 | 1.06 |
| Oct-21 | 920 | 7.68 | 409 | 473 | 18.4 | <0.05 | <0.05 | 83.4 | <0.10 | 3.08 | 123 | 40.4 | 11.4 | <1.00 | 0.015 | 0.122 | 0.033 | 0.02 | 150 | 1.02 |
| Sep-22 | 959 | 7.89 | 373 | 449 | 28.0 | <0.05 | <0.05 | 126 | <0.10 | 2.59 | 118 | 37.6 | 19.0 | 0.07 | 0.027 | 0.143 | 0.027 | 0.11 | 16.0 | 1.10 |
| Nov-23 | 904 | 7.57 | 455 | 481 | 20.9 | < 0.05 | < 0.05 | 84.4 | <0.10 | 1.50 | 129 | 38.5 | 13.3 | 0.81 | 0.035 | 0.156 | 0.037 | 0.17 | 6.9 | 2.96 |
| Nov-24 | 924 | 7.63 | 496 | 250 | 18.2 | <0.05 | <0.05 | 78.9 | <0.10 | 2.87 | 65.3 | 21.0 | 1.65 | < 0.50 | 0.022 | 0.059 | 0.023 | 0.10 | 17.4 | 0.79 |
| | | | | | | | | | | | | | | | | | | | | |
| Average | 904 | 7.84 | 414 | 456 | 21.3 | <0.25 | <0.25 | 86.7 | <0.5 | 2.22 | 120 | 37.8 | 12.9 | 0.99 | 1.76 | 0.22 | 0.04 | 0.20 | 27.0 | 1.12 |
| Std. Dev. | 58.9 | 0.18 | 36.5 | 69.1 | 3.54 | NA | NA | 18.0 | NA | 1.30 | 18.53 | 5.70 | 6.41 | 0.43 | 4.42 | 0.31 | 0.02 | 0.11 | 38.9 | 0.61 |

Monitoring Well OW-8 (Shallow Sand Unit)

| Parameter | Conductivity | На | Alkalinity | Hardness | Chloride | Nitrate | Nitrite | Sulphate | Phosphate | Phosphorus | Calcium | Magnesium | Sodium | Potassium | Iron | Manganese | Boron | Ammonia | DOC | TKN |
|-----------|--------------|------------|------------|-----------|----------|---------|---------|----------|-----------|------------|---------|-----------|--------|-----------|-------|-----------|-------|---------|------|------|
| UNITS | uS/cm | Unitless | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L |
| ODWS | NV | 6.5 to 8.5 | 30 to 500 | 80 to 100 | 250 | 10 | 1.0 | 500 | NV | NV | NV | NV | 200 | NV | 0.3 | 0.05 | 5 | NV | 5.0 | NV |
| ODWS | NA | OG | OG | OG | AO | MAC | MAC | AO | NA | NA | NA | NA | AO | NA | AO | AO | IMAC | NA | AO | NA |
| RUC | NV | 6.5 to 8.5 | 355 | 261 | 127 | 2.58 | 0.25 | 261 | NV | NV | NV | NV | 101 | NV | 1.83 | 0.31 | 1.26 | NV | 30.2 | NV |
| Nov-12 | 1300 | 7.78 | 661 | 585 | 97.6 | <0.05 | < 0.05 | <0.10 | <0.10 | 3.02 | 166 | 41.5 | 62.4 | 27.2 | 5.96 | 0.737 | 0.26 | 13.2 | 24.7 | 14.2 |
| Apr-13 | 1950 | 7.93 | 852 | 785 | 157 | <0.5 | <0.5 | 3.39 | <1.0 | < 0.05 | 213 | 61.4 | 98.6 | 21.3 | 5.81 | 0.654 | 0.38 | 9.74 | 41.0 | 16.2 |
| May-14 | 3900 | 7.54 | 1630 | 978 | 272 | <1.0 | <1.0 | 28.5 | <2.0 | 1.27 | 272 | 72.6 | 241 | 111 | 0.20 | 0.756 | | 68.5 | 52.1 | 99.5 |
| Oct-14 | 3560 | 7.05 | 1610 | 874 | 273 | <1.0 | <1.0 | 8.7 | <2.0 | 3.98 | 238 | 68.0 | 204 | 106 | 0.46 | 0.807 | | 160 | 90.6 | 168 |
| Apr-15 | 2940 | 7.54 | 1350 | 728 | 206 | <0.5 | <0.5 | 44.2 | <1.0 | 0.41 | 186 | 64.1 | 185 | 116 | 0.43 | 0.775 | | 104 | 55.0 | 108 |
| Oct-15 | 3690 | 7.90 | 1710 | 951 | 223 | <2.5 | <2.5 | 43.3 | <5.0 | 0.51 | 249 | 79.9 | 219 | 159 | 24.9 | 0.616 | 2.06 | 122 | 55.6 | 134 |
| Apr-16 | 3420 | 7.80 | 1630 | 910 | 213 | <1.0 | <1.0 | 57 | <2.0 | 0.46 | 240 | 75.5 | 200 | 126 | 0.16 | 0.439 | | 88.7 | 53.8 | 108 |
| Nov-16 | 2890 | 7.69 | 1280 | 887 | 166 | <0.25 | <0.25 | 109 | NM | 1.02 | 250 | 63.8 | 153 | 96.2 | 23.4 | 0.568 | 1.57 | 88.2 | 51.3 | 93.0 |
| Apr-17 | 2680 | 7.75 | 1210 | 772 | 114 | <0.5 | <0.5 | 80.2 | <1.0 | 1.65 | 215 | 57.0 | 107 | 94.1 | 0.10 | 0.448 | | 92.2 | 54.2 | 94.7 |
| Sep-17 | 3170 | 7.64 | 1330 | 744 | 127 | <0.5 | <0.5 | 148 | NM | 1.27 | 197 | 61.3 | 130 | 106 | 12.9 | 0.490 | 1.65 | 89.0 | 44.3 | 100 |
| May-18 | 3000 | 7.51 | 1400 | 890 | 120 | <0.10 | <0.010 | 93 | <0.010 | <0.10 | 240 | 68.0 | 130 | 110 | 0.13 | 0.520 | | 86.0 | 38.0 | 100 |
| Nov-18 | 2510 | 7.62 | 1160 | 786 | 103 | <0.25 | <0.25 | 115 | NM | 1.54 | 221 | 57.0 | 100 | 85.8 | 25.6 | 0.805 | 1.30 | 37.6 | 16.4 | 53.0 |
| Apr-19 | 2110 | 7.67 | 1070 | 695 | 78.2 | <0.5 | <0.5 | 128 | <1.0 | 2.44 | 195 | 50.5 | 74.3 | 68.5 | 0.05 | 0.371 | 0.16 | 44.7 | 27.6 | 58.5 |
| Oct-19 | 1560 | 7.53 | 751 | 652 | 79.5 | <0.25 | <0.25 | 55.4 | NM | 1.83 | 194 | 40.7 | 52.1 | 43.5 | 1.45 | 0.541 | 0.78 | 27.6 | 28.5 | 32.2 |
| Apr-20 | 2460 | 7.47 | 1050 | 682 | 89.1 | <1.0 | <1.0 | 48.0 | <2.0 | 1.05 | 206 | 40.7 | 70.5 | 48.1 | 0.053 | 0.768 | 1.26 | 40.0 | 34.0 | 44.0 |
| Oct-20 | 2000 | 7.85 | 1020 | 746 | 110 | <0.25 | <0.25 | 20.8 | NM | 0.70 | 221 | 47.2 | 100 | 54.0 | 0.065 | 0.598 | 1.19 | 43.5 | 36.4 | 49.5 |
| May-21 | 2220 | 7.27 | 1010 | 685 | 94.5 | <0.5 | <0.5 | 19.5 | <1.0 | 0.42 | 211 | 38.5 | 80.1 | 55.6 | 21.4 | 0.991 | 1.06 | 62.1 | 35.5 | 79.0 |
| Apr-22 | 2430 | 7.37 | 997 | 697 | 98.4 | 0.82 | <0.11 | 45.8 | <0.26 | 0.97 | 207 | 43.7 | 103 | 61.0 | 0.11 | 0.683 | 1.99 | 61.2 | 34.9 | 78.0 |
| Sep-22 | 2000 | 7.45 | 932 | 683 | 106 | <0.07 | <0.05 | 20.3 | <0.13 | 0.80 | 207 | 40.4 | 94.7 | 46.7 | 37.3 | 0.927 | 1.18 | 41.4 | 48.5 | 58.5 |
| Apr-23 | 1510 | 7.21 | 635 | 542 | 103 | <0.05 | <0.05 | 51.0 | <0.10 | 0.64 | 161 | 34.0 | 94.4 | 36.8 | 0.05 | 0.624 | 0.82 | 21.0 | 42.8 | 22.4 |
| Nov-23 | 2150 | 7.33 | 988 | 677 | 122 | <0.07 | <0.05 | 65.4 | | 0.66 | 219 | 31.6 | 112 | 43.6 | 40.7 | 1.160 | 1.34 | 48.8 | 41.4 | 53.5 |
| Apr-24 | 2450 | 7.06 | 937 | 679 | 115 | <0.14 | <0.11 | 55.8 | <0.26 | 0.28 | 198 | 44.8 | 103 | 44.0 | 0.082 | 0.812 | 1.27 | 30.6 | 29.8 | 35.6 |
| Nov-24 | 2370 | 7.09 | 961 | 597 | 118 | <0.14 | <0.11 | 51.1 | | 1.15 | 179 | 36.4 | 109 | 34.1 | 0.080 | 0.889 | 0.93 | 30.4 | 43.3 | 31.1 |
| | 0500 | 7.50 | 4400 | 740 | 400 | | -1.0 | 50.7 | -1.0 | 2.11 | 040 | 50.0 | 400.7 | 70.7 | 0.70 | 0.005 | 1.10 | 01.0 | 40.0 | 70.0 |
| Average | 2533 | 7.52 | 1138 | 749 | 138 | <1.0 | <1.0 | 58.7 | <1.0 | 1.14 | 212 | 53.0 | 122.7 | 73.7 | 8.76 | 0.695 | 1.13 | 61.3 | 42.6 | 70.9 |
| Std. Dev. | 703 | 0.26 | 311 | 118 | 58.7 | NA | NA | 39.0 | NA | 0.96 | 27.4 | 14.4 | 52.6 | 37.2 | 13.15 | 0.19 | 0.54 | 37.5 | 15.0 | 39.8 |

Monitoring Well OW-9 (Silt Loam Unit)

| Parameter | Conductivity | pН | Alkalinity | Hardness | Chloride | Nitrate | Nitrite | Sulphate | Phosphate | Phosphorus | Calcium | Magnesium | Sodium | Potassium | Iron | Manganese | Boron | Ammonia | DOC | TKN |
|-----------|--------------|------------|------------|-----------|----------|---------|---------|----------|-----------|------------|---------|-----------|--------|-----------|--------|-----------|-------|---------|------|------|
| UNITS | uS/cm | Unitless | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L |
| ODWS | NV | 6.5 to 8.5 | 30 to 500 | 80 to 100 | 250 | 10 | 1.0 | 500 | NV | NV | NV | NV | 200 | NV | 0.3 | 0.05 | 5 | NV | 5.0 | NV |
| ODWS | NA | OG | OG | OG | AO | MAC | MAC | AO | NA | NA | NA | NA | AO | NA | AO | AO | IMAC | NA | AO | NA |
| RUC | NV | 6.5 to 8.5 | 355 | 261 | 127 | 2.58 | 0.25 | 261 | NV | NV | NV | NV | 101 | NV | 1.83 | 0.31 | 1.26 | NV | 30.2 | NV |
| Nov-12 | 384 | 8.08 | 224 | 216 | 1.19 | < 0.05 | < 0.05 | 4.04 | <0.10 | < 0.05 | 60.2 | 15.9 | 4.66 | 3.05 | 0.03 | 0.023 | | 1.35 | 9.2 | 1.54 |
| Apr-13 | 426 | 8.02 | 233 | 223 | 1.16 | <0.05 | <0.05 | 1.28 | <0.10 | 13.1 | 61.3 | 17.0 | 4.05 | 1.71 | < 0.01 | 0.014 | | 0.49 | 9.7 | 1.62 |
| | | | | | | | | | | | | | | | | | | | | |
| Average | 405 | 8.05 | 229 | 220 | 1.18 | <0.05 | <0.05 | 2.66 | <0.10 | 6.55 | 61 | 16.45 | 4.36 | 2.38 | 0.03 | 0.019 | | 0.92 | 9.45 | 1.58 |
| Std. Dev. | 29.7 | 0.04 | 6.4 | 4.9 | 0.02 | NA | NA | 1.95 | NA | NA | 0.78 | 0.78 | 0.43 | 0.95 | NA | 0.01 | | 0.61 | 0.35 | 0.06 |

Monitoring Well OW-10S (Shallow Sand Unit)

| Parameter | Conductivity | рН | Alkalinity | Hardness | Chloride | Nitrate | Nitrite | Sulphate | Phosphate | Phosphorus | Calcium | Magnesium | Sodium | Potassium | Iron | Manganese | Boron | Ammonia | DOC | TKN |
|-----------|--------------|------------|------------|-----------|----------|---------|---------|----------|-----------|------------|---------|-----------|--------|-----------|------|-----------|-------|---------|------|------|
| UNITS | uS/cm | Unitless | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L |
| opws | NV | 6.5 to 8.5 | 30 to 500 | 80 to 100 | 250 | 10 | 1.0 | 500 | NV | NV | NV | NV | 200 | NV | 0.3 | 0.05 | 5 | NV | 5.0 | NV |
| ODWS | NA | OG | OG | OG | AO | MAC | MAC | AO | NA | NA | NA | NA | AO | NA | AO | AO | IMAC | NA | AO | NA |
| RUC | NV | 6.5 to 8.5 | 355 | 261 | 127 | 2.58 | 0.25 | 261 | NV | NV | NV | NV | 101 | NV | 1.83 | 0.31 | 1.26 | NV | 30.2 | NV |
| Nov-12 | 556 | 7.94 | 315 | 297 | 7.28 | <0.05 | <0.05 | 9.96 | <0.10 | 13.3 | 84.0 | 21.3 | 26.2 | 1.21 | 3.96 | 0.25 | 0.040 | 1.72 | 19.8 | 2.2 |
| Apr-13 | 614 | 8.08 | 272 | 332 | 7.43 | <0.10 | <0.10 | 49.8 | <0.20 | 5.4 | 92.3 | 24.6 | 14.8 | 0.91 | 2.74 | 0.26 | <0.01 | 0.75 | 23.4 | 2.24 |
| Oct-15 | 700 | 7.97 | 362 | 295 | 6.83 | 0.18 | <0.10 | 16.5 | <0.20 | 2.35 | 84.6 | 20.3 | 43.4 | 1.53 | 18.7 | 1.02 | | 0.50 | 22.4 | 1.59 |
| Nov-16 | 700 | 7.96 | 340 | 283 | 4.97 | <0.25 | <0.25 | 43.5 | <0.50 | 1.85 | 81.8 | 19.1 | 40.0 | 0.94 | 0.19 | 0.27 | | 0.54 | 26.7 | 2.08 |
| Sep-17 | 700 | 7.81 | 315 | 305 | 5.64 | <0.05 | <0.05 | 45.2 | <0.10 | 1.64 | 86.2 | 21.7 | 19.1 | 0.89 | 0.18 | 0.25 | | 0.50 | 34.3 | 1.56 |
| Nov-18 | 592 | 7.74 | 272 | 310 | 5.84 | <0.10 | <0.05 | 49.5 | <0.10 | < 0.05 | 86.6 | 22.7 | 8.62 | 0.87 | 0.20 | 0.28 | 0.057 | 0.30 | 34.1 | 1.42 |
| Oct-19 | 598 | 7.49 | 294 | 344 | 5.07 | <0.05 | <0.05 | 54.9 | <0.10 | 3.71 | 94.7 | 26.2 | 8.25 | 0.92 | 0.19 | 0.28 | 0.082 | 0.36 | 33.9 | 1.48 |
| Oct-20 | 570 | 7.82 | 294 | 295 | 6.58 | 0.05 | <0.05 | 32.3 | <0.10 | 1.82 | 81.0 | 22.4 | 12.8 | 1.06 | 0.29 | 0.30 | 0.089 | 0.29 | 33.4 | 1.46 |
| Oct-21 | 590 | 7.43 | 276 | 298 | 5.30 | <0.05 | <0.05 | 35.1 | <0.10 | 1.17 | 84.9 | 21.0 | 6.84 | 0.86 | 0.19 | 0.25 | 0.057 | 0.16 | 109 | 1.57 |
| Sep-22 | 542 | 7.69 | 273 | 271 | 5.49 | <0.05 | <0.05 | 19.5 | <0.10 | 1.64 | 74.1 | 20.9 | 10.7 | 1.00 | 0.22 | 0.24 | 0.065 | 0.18 | 34.8 | 2.42 |
| Nov-23 | 506 | 7.26 | 310 | 244 | 4.72 | < 0.05 | < 0.05 | 10.6 | <0.10 | 0.70 | 66.8 | 18.7 | 8.74 | 0.71 | 0.24 | 0.26 | 0.064 | 0.20 | 25.8 | 3.39 |
| Nov-24 | 598 | 7.29 | 324 | 280 | 4.68 | <0.05 | <0.05 | 35.5 | <0.10 | 1.10 | 74.9 | 22.5 | 3.85 | 0.53 | 0.27 | 0.26 | 0.041 | 0.24 | 35.9 | 1.60 |
| | | | | | | | | | | | | | | | | | | | | |
| Average | 606 | 7.71 | 304 | 296 | 5.82 | 0.043 | <0.10 | 33.5 | <0.10 | 2.89 | 82.7 | 21.8 | 16.9 | 0.95 | 2.28 | 0.33 | 0.056 | 0.48 | 36.1 | 1.92 |
| Std. Dev. | 64.0 | 0.28 | 29.1 | 26.4 | 0.98 | 0.045 | NA | 15.92 | NA | 3.57 | 7.8 | 2.13 | 13.0 | 0.25 | 5.32 | 0.22 | 0.025 | 0.43 | 23.6 | 0.58 |

Monitoring Well OW-10D (Deeper Sand Unit)

| Parameter | Conductivity | рН | Alkalinity | Hardness | Chloride | Nitrate | Nitrite | Sulphate | Phosphate | Phosphorus | Calcium | Magnesium | Sodium | Potassium | Iron | Manganese | Boron | Ammonia | DOC | TKN |
|-----------|--------------|------------|------------|-----------|----------|---------|---------|----------|-----------|------------|---------|-----------|--------|-----------|--------|-----------|-------|---------|------|-------|
| UNITS | uS/cm | Unitless | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L |
| odws | NV | 6.5 to 8.5 | 30 to 500 | 80 to 100 | 250 | 10 | 1.0 | 500 | NV | NV | NV | NV | 200 | NV | 0.3 | 0.05 | 5 | NV | 5.0 | NV |
| ODWS | NA | OG | OG | OG | AO | MAC | MAC | AO | NA | NA | NA | NA | AO | NA | AO | AO | IMAC | NA | AO | NA |
| RUC | NV | 6.5 to 8.5 | 355 | 261 | 127 | 2.58 | 0.25 | 261 | NV | NV | NV | NV | 101 | NV | 1.83 | 0.31 | 1.26 | NV | 30.2 | NV |
| Nov-12 | 448 | 8.19 | 261 | 276 | 3.02 | <0.05 | <0.05 | 12.5 | <0.10 | 1.2 | 71.2 | 23.9 | 2.07 | 0.65 | 0.38 | 0.029 | 0.01 | <0.05 | 2.5 | 0.18 |
| Apr-13 | 520 | 8.19 | 268 | 276 | 3.17 | <0.05 | <0.05 | 11.6 | <0.10 | < 0.05 | 69.3 | 25.0 | 1.63 | 0.71 | 0.38 | 0.027 | 0.03 | <0.05 | 2.5 | 0.16 |
| Oct-15 | 517 | 8.06 | 270 | 275 | 4.94 | <0.10 | <0.10 | 15.2 | <0.20 | 0.09 | 70.6 | 24.0 | 1.47 | 0.70 | 1.29 | 0.076 | | 0.02 | 2.0 | <0.10 |
| Nov-16 | 520 | 8.00 | 267 | 274 | 4.62 | <0.05 | < 0.05 | 14.0 | <0.10 | 0.05 | 71.6 | 23.2 | 1.46 | 0.72 | 0.026 | 0.030 | | 0.05 | 2.2 | <0.10 |
| Sep-17 | 579 | 8.09 | 285 | 275 | 4.47 | <0.05 | <0.05 | 13.4 | <0.10 | 0.07 | 69.3 | 24.7 | 1.56 | 0.70 | <0.01 | 0.035 | | 0.18 | 4.8 | 0.34 |
| Nov-18 | 539 | 7.90 | 284 | 287 | 4.74 | <0.05 | <0.05 | 13.6 | <0.10 | < 0.05 | 74.5 | 24.6 | 1.69 | 0.82 | 0.015 | 0.037 | 0.015 | 0.20 | 5.3 | 0.24 |
| Oct-19 | 505 | 7.80 | 276 | 286 | 4.24 | <0.05 | < 0.05 | 15.0 | <0.10 | 80.0 | 72.5 | 25.6 | 1.54 | 0.76 | <0.010 | 0.049 | 0.030 | 0.13 | 2.9 | 0.23 |
| Oct-20 | 516 | 8.03 | 286 | 285 | 4.36 | <0.05 | < 0.05 | 14.3 | <0.10 | 0.13 | 71.1 | 26.1 | 1.60 | 0.68 | <0.010 | 0.038 | 0.019 | 0.09 | 3.3 | 0.24 |
| Oct-21 | 520 | 7.80 | 269 | 265 | 3.29 | <0.05 | <0.05 | 8.86 | <0.10 | 0.05 | 68.4 | 22.9 | 1.56 | 0.60 | 0.22 | 0.061 | 0.020 | 0.24 | 35.7 | 0.70 |
| Sep-22 | 538 | 8.07 | 278 | 294 | 4.41 | <0.05 | <0.05 | 14.6 | <0.10 | 0.36 | 77.9 | 24.1 | 1.47 | 0.43 | 0.017 | 0.049 | 0.011 | 0.19 | 33.4 | 0.49 |
| Nov-23 | 552 | 7.78 | 323 | 297 | 3.97 | <0.05 | <0.05 | 13.1 | <0.10 | 0.11 | 76.5 | 25.8 | 1.69 | 0.63 | <0.010 | 0.038 | 0.017 | 0.06 | 1.7 | <0.10 |
| Nov-24 | 534 | 7.77 | 339 | 253 | 2.58 | <0.05 | <0.05 | 6.45 | <0.10 | 0.70 | 65.9 | 21.4 | 1.72 | < 0.50 | <0.020 | 0.062 | 0.022 | 0.28 | 9.2 | 0.54 |
| | | | | | | | | | | | | | | | | | | | | |
| Average | 524 | 7.97 | 284 | 279 | 3.98 | <0.1 | <0.1 | 12.7 | <0.10 | 0.24 | 71.6 | 24.3 | 1.62 | 0.67 | 0.33 | 0.044 | 0.019 | 0.12 | 8.8 | 0.27 |
| Std. Dev. | 31 | 0.16 | 23.6 | 12.2 | 0.77 | NA | NA | 2.6 | NA | 0.36 | 3.4 | 1.34 | 0.17 | 0.10 | 0.45 | 0.015 | 0.007 | 0.09 | 12.2 | 0.21 |

Monitoring Well OW-11 (Shallow Sand Unit)

| Parameter | Conductivity | рН | Alkalinity | Hardness | Chloride | Nitrate | Nitrite | Sulphate | Phosphate | Phosphorus | Calcium | Magnesium | Sodium | Potassium | Iron | Manganese | Boron | Ammonia | DOC | TKN |
|-----------|--------------|------------|------------|-----------|----------|---------|---------|----------|-----------|------------|---------|-----------|--------|-----------|------|-----------|-------|---------|-------|------|
| UNITS | uS/cm | Unitless | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L |
| ODWS | NV | 6.5 to 8.5 | 30 to 500 | 80 to 100 | 250 | 10 | 1.0 | 500 | NV | NV | NV | NV | 200 | NV | 0.3 | 0.05 | 5 | NV | 5.0 | NV |
| ODWS | NA | OG | OG | OG | AO | MAC | MAC | AO | NA | NA | NA | NA | AO | NA | AO | AO | IMAC | NA | AO | NA |
| RUC | NV | 6.5 to 8.5 | 355 | 261 | 127 | 2.58 | 0.25 | 261 | NV | NV | NV | NV | 101 | NV | 1.83 | 0.31 | 1.26 | NV | 30.2 | NV |
| Sep-17 | 674 | 7.78 | 335 | 307 | 4.81 | <0.05 | <0.05 | 17.6 | NM | 0.13 | 86.3 | 22.3 | 7.67 | 0.33 | 1.49 | 0.238 | 0.019 | 0.33 | 39.7 | 4.08 |
| Nov-18 | 590 | 7.26 | 319 | 327 | 6.01 | <0.05 | <0.05 | 35.2 | <0.10 | < 0.05 | 93.3 | 22.9 | 5.97 | 0.48 | 0.38 | 0.219 | 0.014 | 0.22 | 40.4 | 1.57 |
| Oct-19 | 547 | 7.72 | 290 | 315 | 4.91 | < 0.05 | < 0.05 | 25.7 | <0.10 | 0.71 | 89.3 | 22.3 | 4.67 | 0.47 | 0.56 | 0.238 | 0.021 | 0.26 | 34.9 | 1.17 |
| Oct-20 | 572 | 7.87 | 301 | 322 | 6.38 | 0.06 | <0.05 | 29.6 | <0.10 | 0.30 | 91.0 | 22.9 | 3.40 | 0.54 | 0.83 | 0.273 | 0.028 | 0.26 | 36.0 | 1.49 |
| Oct-21 | 588 | 7.64 | 296 | 309 | 4.99 | <0.05 | <0.05 | 21.2 | <0.10 | 0.61 | 87.3 | 22.2 | 3.49 | < 0.50 | 0.65 | 0.214 | 0.010 | 0.15 | 83.2 | 1.85 |
| Sep-22 | 583 | 7.88 | 297 | 332 | 4.40 | < 0.05 | < 0.05 | 17.4 | <0.10 | 0.37 | 95.0 | 22.9 | 2.83 | <0.05 | 1.03 | 0.259 | 0.015 | 0.18 | 35.3 | 2.30 |
| Nov-23 | 633 | 7.17 | 408 | 330 | 5.29 | < 0.05 | < 0.05 | 3.15 | <0.10 | 0.80 | 91.7 | 24.5 | 2.71 | <0.50 | 0.91 | 0.255 | 0.020 | 0.13 | 34.1 | 4.43 |
| Nov-24 | 609 | 7.52 | 373 | 291 | 2.90 | <0.05 | <0.05 | 0.31 | <0.10 | 0.12 | 82.7 | 20.4 | 2.75 | <1.00 | 0.94 | 0.263 | 0.021 | 0.12 | 38.6 | 1.20 |
| | | | | | | | | | | | | | | | | | | | | |
| Average | 600 | 7.61 | 327 | 317 | 4.96 | <0.05 | <0.05 | 18.8 | <0.10 | 0.383 | 89.6 | 22.6 | 4.19 | 0.46 | 0.85 | 0.245 | 0.019 | 0.21 | 42.8 | 2.26 |
| Std. Dev. | 39.2 | 0.27 | 42.6 | 13.9 | 1.06 | NA | NA | 12.1 | NA | 0.293 | 4.02 | 1.14 | 1.80 | 0.09 | 0.34 | 0.02 | 0.005 | 0.07 | 16.50 | 1.29 |

Monitoring Well OW-12S (Shallow Sand Unit)

| Parameter | Conductivity | pН | Alkalinity | Hardness | Chloride | Nitrate | Nitrite | Sulphate | Phosphate | Phosphorus | Calcium | Magnesium | Sodium | Potassium | Iron | Manganese | Boron | Ammonia | DOC | TKN |
|-----------|--------------|------------|------------|-----------|----------|---------|---------|----------|-----------|------------|---------|-----------|--------|-----------|--------|-----------|---------|---------|-------|-------|
| UNITS | uS/cm | Unitless | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L |
| ODWS | NV | 6.5 to 8.5 | 30 to 500 | 80 to 100 | 250 | 10 | 1.0 | 500 | NV | NV | NV | NV | 200 | NV | 0.3 | 0.05 | 5 | NV | 5.0 | NV |
| ODWS | NA | OG | OG | OG | AO | MAC | MAC | AO | NA | NA | NA | NA | AO | NA | AO | AO | IMAC | NA | AO | NA |
| RUC | NV | 6.5 to 8.5 | 355 | 261 | 127 | 2.58 | 0.25 | 261 | NV | NV | NV | NV | 101 | NV | 1.83 | 0.31 | 1.26 | NV | 30.2 | NV |
| Sep-17 | 405 | 8.05 | 202 | 180 | 1.08 | <0.05 | <0.05 | 6.86 | NM | 6.5 | 47.3 | 15.0 | 0.65 | 0.42 | <0.010 | 0.018 | <0.010 | 0.07 | 2.0 | 0.23 |
| Nov-18 | 369 | 7.85 | 198 | 192 | 1.28 | < 0.05 | <0.05 | 6.88 | <0.10 | < 0.05 | 50.3 | 16.2 | 1.22 | 0.57 | <0.010 | 0.006 | < 0.010 | <0.02 | 3.0 | <0.10 |
| Oct-19 | 333 | 7.76 | 193 | 191 | 1.02 | <0.05 | <0.05 | 4.34 | <0.10 | 1.67 | 49.7 | 16.2 | 0.91 | 0.61 | <0.010 | 0.013 | 0.016 | <0.02 | 3.6 | <0.10 |
| Oct-20 | 360 | 8.06 | 207 | 198 | 2.42 | 0.10 | <0.05 | 4.77 | <0.10 | 0.38 | 50.9 | 17.3 | 0.92 | 0.33 | <0.010 | 0.003 | 0.033 | <0.02 | 3.0 | <0.10 |
| Oct-21 | 364 | 7.86 | 196 | 191 | 0.78 | <0.05 | < 0.05 | 4.21 | <0.10 | 0.94 | 49.1 | 16.5 | 0.67 | < 0.50 | 0.015 | 0.006 | <0.010 | <0.02 | 51.1 | <0.10 |
| Sep-22 | 365 | 8.08 | 191 | 194 | 0.99 | <0.05 | <0.05 | 3.77 | <0.10 | 0.27 | 50.4 | 16.5 | 0.78 | < 0.05 | 0.027 | 0.007 | <0.010 | <0.02 | 1.7 | 0.15 |
| Nov-23 | 369 | 7.58 | 238 | 209 | 7.12 | <0.05 | <0.05 | 4.91 | <0.10 | 0.42 | 55.4 | 17.2 | 1.03 | < 0.50 | <0.010 | 0.010 | <0.010 | <0.02 | 1.4 | 0.41 |
| Nov-24 | 341 | 7.88 | 234 | 166 | 0.74 | <0.05 | <0.05 | 4.18 | <0.10 | 0.54 | 42.6 | 14.5 | 0.72 | <0.50 | <0.020 | 0.003 | <0.010 | <0.02 | 1.9 | <0.10 |
| | | | | | | | | | | | | | | | | | | | | |
| Average | 363 | 7.89 | 207 | 190 | 1.93 | <0.05 | <0.05 | 4.99 | <0.10 | 1.34 | 49.5 | 16.2 | 0.86 | 0.48 | <0.01 | 0.008 | 0.010 | 0.018 | 8.46 | 0.13 |
| Std Dev | 21.5 | 0.17 | 18.4 | 12.7 | 2.16 | NA | NA | 1 21 | l NA | 2.14 | 3 60 | 0.98 | 0.20 | 0.13 | NA | 0.005 | 0.010 | 0.021 | 17.24 | 0.13 |

Monitoring Well OW-12D (Deeper Sand Unit)

| Parameter | Conductivity | Hq | Alkalinity | Hardness | Chloride | Nitrate | Nitrite | Sulphate | Phosphate | Phosphorus | Calcium | Magnesium | Sodium | Potassium | Iron | Manganese | Boron | Ammonia | DOC | TKN |
|-----------|--------------|------------|------------|-----------|----------|---------|---------|----------|-----------|------------|---------|-----------|--------|-----------|---------|-----------|-------|---------|-------|------|
| UNITS | uS/cm | Unitless | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L |
| ODWS | NV | 6.5 to 8.5 | 30 to 500 | 80 to 100 | 250 | 10 | 1.0 | 500 | NV | NV | NV | NV | 200 | NV | 0.3 | 0.05 | 5 | NV | 5.0 | NV |
| ODWS | NA | OG | OG | OG | AO | MAC | MAC | AO | NA | NA | NA | NA | AO | NA | AO | AO | IMAC | NA | AO | NA |
| RUC | NV | 6.5 to 8.5 | 355 | 261 | 127 | 2.58 | 0.25 | 261 | NV | NV | NV | NV | 101 | NV | 1.83 | 0.31 | 1.26 | NV | 30.2 | NV |
| Sep-17 | 453 | 8.08 | 228 | 196 | 1.79 | <0.05 | <0.05 | 1.36 | NM | < 0.05 | 53.8 | 15.0 | 2.39 | 2.06 | 0.16 | 0.113 | 0.025 | 0.21 | 14.7 | 0.95 |
| Nov-18 | 388 | 7.92 | 212 | 203 | 2.16 | 0.10 | <0.05 | 1.98 | <0.10 | < 0.05 | 58.7 | 13.8 | 2.82 | 1.95 | < 0.010 | 0.174 | 0.021 | 0.06 | 19.6 | 0.81 |
| Oct-19 | 340 | 7.89 | 196 | 197 | 1.71 | <0.05 | < 0.05 | 0.31 | <0.10 | 0.13 | 56.6 | 13.5 | 2.38 | 1.04 | 1.15 | 0.302 | 0.027 | 0.23 | 18.9 | 0.55 |
| Oct-20 | 353 | 8.00 | 211 | 190 | 3.08 | 0.08 | < 0.05 | 0.48 | <0.10 | 3.17 | 54.4 | 13.2 | 2.33 | 1.18 | 0.070 | 0.141 | 0.040 | 0.12 | 18.0 | 0.72 |
| Oct-21 | 362 | 7.81 | 196 | 171 | 1.62 | 0.10 | < 0.05 | 1.70 | <0.10 | 0.03 | 48.8 | 12.0 | 1.83 | 1.43 | 0.031 | 0.077 | 0.023 | <0.02 | 230 | 0.85 |
| Sep-22 | 371 | 8.10 | 197 | 190 | 1.95 | 0.05 | 0.05 | 0.92 | <0.10 | 2.41 | 55.5 | 12.6 | 2.81 | 0.65 | 0.060 | 0.089 | 0.021 | 0.06 | 17.6 | 1.26 |
| Nov-23 | 338 | 7.44 | 234 | 191 | 1.93 | 0.18 | < 0.05 | 1.09 | <0.10 | 0.84 | 54.5 | 13.4 | 2.22 | 1.45 | 0.018 | 0.051 | 0.028 | 0.08 | 7.2 | 2.01 |
| Nov-24 | 350 | 7.72 | 360 | 171 | 1.57 | 0.24 | < 0.05 | 0.78 | <0.10 | 3.11 | 48.6 | 12.1 | 1.81 | 0.71 | 0.033 | 0.038 | 0.020 | 0.06 | 18.2 | 1.14 |
| | | | | | | | | | | | | | | | | | | | | |
| Average | 369 | 7.87 | 229 | 189 | 1.98 | 0.10 | <0.05 | 1.08 | <0.10 | 1.218 | 53.9 | 13.2 | 2.32 | 1.31 | 0.19 | 0.123 | 0.026 | 0.12 | 43.0 | 1.04 |
| Std. Dev. | 37.6 | 0.22 | 54.8 | 11.7 | 0.49 | 0.08 | NA | 0.58 | NA | 1.434 | 3.54 | 0.98 | 0.38 | 0.52 | 0.39 | 0.085 | 0.007 | 0.07 | 75.65 | 0.45 |

Monitoring Well OW-13 (Shallow Sand Unit)

| Parameter | Conductivity | pH | Alkalinity | Hardness | Chloride | Nitrate | Nitrite | Sulphate | Phosphate | Phosphorus | Calcium | Magnesium | Sodium | Potassium | Iron | Manganese | Boron | Ammonia | DOC | TKN |
|-----------|--------------|------------|------------|-----------|----------|---------|---------|----------|-----------|------------|---------|-----------|--------|-----------|--------|-----------|--------|---------|------|------|
| UNITS | uS/cm | Unitless | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L | mg/L |
| ODWS | NV | 6.5 to 8.5 | 30 to 500 | 80 to 100 | 250 | 10 | 1.0 | 500 | NV | NV | NV | NV | 200 | NV | 0.3 | 0.05 | 5 | NV | 5.0 | NV |
| ODWS | NA | OG | OG | OG | AO | MAC | MAC | AO | NA | NA | NA | NA | AO | NA | AO | AO | IMAC | NA | AO | NA |
| RUC | NV | 6.5 to 8.5 | 355 | 261 | 127 | 2.58 | 0.25 | 261 | NV | NV | NV | NV | 101 | NV | 1.83 | 0.31 | 1.26 | NV | 30.2 | NV |
| Sep-17 | 471 | 8.07 | 237 | 205 | 1.16 | 0.25 | < 0.05 | 3.23 | NM | 2.62 | 62.9 | 11.7 | 0.82 | 0.28 | <0.010 | 0.003 | <0.010 | 0.11 | 1.2 | 0.34 |
| Oct-21 | 404 | 7.98 | 217 | 202 | 0.66 | 0.12 | <0.05 | 1.68 | <0.10 | 1.18 | 61.5 | 11.8 | 0.74 | < 0.50 | <0.010 | 0.002 | <0.010 | <0.02 | 45.6 | 0.12 |
| | | | | | | | | | | | | | | | | | | | | |
| Average | 438 | 8.03 | 227 | 204 | 0.91 | 0.19 | <0.05 | 2.46 | <0.10 | 1.90 | 62.2 | 11.8 | 0.78 | 0.27 | <0.010 | 0.003 | <0.010 | 0.06 | 23.4 | 0.23 |
| Std. Dev. | 47.4 | 0.06 | 14.1 | 2.28 | 0.35 | 0.09 | NA | 1.10 | NA | 1.02 | 0.99 | 0.07 | 0.06 | 0.02 | NA | 0.001 | NA | 0.07 | 31.4 | 0.16 |

Notes:

- 1. ODWS = Ontario Drinking Water Standards (June 2003, Revised June 2006); RUC = Reasonable Use Criteria (RUC shown in BOLD > ODWS).
- 2. NA = Not Applicable: NM = Not Monitored: NV = No value specified
- 3. Results presented in mg/L (milligrams per litre) unless otherwise specified. µS/cm = microsiemens per centimeter.
- 4. Samples analyzed by AGAT Laboratories Limited.
- 5. * indicates outlier interpreted as sample or lab error.
- 6. Data prior to 2006 obtained from Annual Monitoring Report (2005), Henderson, Paddon and Associates, Ltd.
- 7. Values reported as less than detection limits used as ½ detection limit for calculation of averages and plotting.
- 8. Values in bold represent results greater than the Reasonable Use Criteria.
- 9. Shaded values represent results greater than the ODWS.
- 10. Results reported appear to have been erroneously identified. Based on the analytical data, the results for OW4 and OW6 are assumed to be the reverse of that reported on the COC.

| | | | | Well ID | OV | N-2 | | | | | | | OW-3 | | | | | | |
|-------------------------------------|-------|-----|------|---------|--------|--------|--------|--------|--------|--------|--------|--------|--------|--------|--------|--------|--------|--------|--------|
| Parameter | Units | OD | WS | RUC | Nov-23 | Nov-24 | Jun-05 | Apr-08 | Oct-08 | Apr-09 | Apr-10 | Apr-11 | Nov-11 | Apr-12 | Nov-12 | Apr-13 | Nov-13 | Oct-14 | Apr-15 |
| Dichlorodifluoromethane | μg/L | NV | NA | NV | NM | NM | NM | NM | NM | NM | NM | NM | NM | <0.20 | NM | NM | NM | NM | <0.40 |
| Chloromethane | μg/L | NV | NA | NV | NM | NM | NM | NM | NM | <0.80 | NM | NM | NM | <0.40 | NM | NM | NM | NM | NM |
| Vinyl Chloride | μg/L | 2 | MAC | 0.5 | <0.17 | NM | NM | NM | NM | < 0.34 | NM | NM | МИ | <0.17 | NM | NM | NM | NM | <0.34 |
| Bromomethane | μg/L | NV | NA | NV | NM | NM | NM | NM | NM | <0.40 | NM | NM | МИ | <0.20 | NM | NM | NM | NM | <0.40 |
| Chloroethane | μg/L | NV | NA | NV | NM | NM | NM | NM | NM | < 0.40 | NM | NM | NM | <0.20 | NM | NM | NM | NM | NM |
| Trichlorofluoromethane | μg/L | NV | NA | NV | NM | NM | NM | NM | NM | <0.80 | NM | NM | NM | <0.40 | NM | NM | NM | NM | <0.80 |
| Acetone | μg/L | NV | NA | NV | NM | NM | NM | NM | NM | <2.0 | NM | NM | МИ | <1.0 | NM | NM | NM | NM | <2.0 |
| 1,1 Dichloroethylene | μg/L | 14 | MAC | 3.5 | NM | NM | NM | NM | NM | < 0.60 | NM | NM | NM | < 0.30 | NM | NM | NM | NM | < 0.60 |
| Methylene Chloride | μg/L | 50 | MAC | 12.5 | < 0.30 | NM | NM | NM | NM | <0.60 | NM | NM | NM | < 0.30 | NM | NM | NM | NM | <0.60 |
| trans- 1,2-dichloroethylene | μg/L | NV | NA | NV | NM | NM | NM | NM | NM | <0.40 | NM | NM | NM | <0.20 | NM | NM | NM | NM | <0.40 |
| Methyl tert-butyl ether | μg/L | NV | NA | NV | NM | NM | NM | NM | NM | <0.40 | NM | NM | NM | <0.20 | NM | NM | NM | NM | <0.40 |
| 1,1-Dichloroethane | μg/L | NV | NA | NV | NM | NM | NM | NM | NM | <0.60 | NM | NM | NM | < 0.30 | NM | NM | NM | NM | <0.60 |
| Methyl Ethyl Ketone | μg/L | NV | NA | NV | NM | NM | NM | NM | NM | <2.0 | NM | NM | NM | <1.0 | NM | NM | NM | NM | <2.0 |
| cis- 1,2-Dichloroethylene | μg/L | NV | NA | NV | NM | NM | NM | NM | NM | <0.40 | NM | NM | NM | <0.20 | NM | NM | NM | NM | <0.40 |
| Chloroform ⁽⁵⁾ | μg/L | 100 | MAC | 25 | NM | NM | NM | NM | NM | <0.40 | NM | NM | NM | <0.20 | NM | NM | NM | NM | <0.40 |
| 1,2 - Dichloroethane | μg/L | 5 | IMAC | 1.25 | NM | NM | NM | NM | NM | <0.40 | NM | NM | NM | <0.20 | NM | NM | NM | NM | <0.40 |
| 1,1,1-Trichloroethane | μg/L | NV | NA | NV | NM | NM | NM | NM | NM | <0.60 | NM | NM | NM | < 0.30 | NM | NM | NM | NM | <0.60 |
| Carbon Tetrachloride | μg/L | 5 | MAC | 1.25 | NM | NM | NM | NM | NM | < 0.40 | NM | NM | NM | <0.20 | NM | NM | NM | NM | <0.40 |
| Benzene | μg/L | 5 | MAC | 1.25 | <0.20 | <0.20 | <0.1 | <0.04 | <0.2 | <0.40 | <0.2 | <0.40 | <0.20 | <0.20 | <0.20 | <0.20 | <0.80 | <0.40 | <0.40 |
| 1,2-Dichloropropane | μg/L | NV | NA | NV | NM | NM | NM | NM | NM | <0.40 | NM | NM | NM | <0.20 | NM | NM | NM | NM | <0.40 |
| Trichloroethylene | μg/L | 5 | MAC | 1.25 | NM | NM | NM | NM | NM | < 0.40 | NM | NM | NM | <0.20 | NM | NM | NM | NM | <0.40 |
| Bromodichloromethane ⁽⁵⁾ | μg/L | 100 | MAC | 25 | NM | NM | NM | NM | NM | <0.40 | NM | NM | NM | <0.20 | NM | NM | NM | NM | <0.40 |
| cis-1,3-Dichloropropene | μg/L | NV | NA | NV | NM | NM | NM | NM | NM | <0.40 | NM | NM | NM | <0.20 | NM | NM | NM | NM | <0.40 |
| Methyl Isobutyl Ketone | μg/L | NV | NA | NV | NM | NM | NM | NM | NM | <2.0 | NM | NM | NM | <1.0 | NM | NM | NM | NM | <2.0 |
| trans-1,3-Dichloropropene | μg/L | NV | NA | NV | NM | NM | NM | NM | NM | < 0.60 | NM | NM | NM | < 0.30 | NM | NM | NM | NM | <0.60 |
| 1,1,2-Trichloroethane | μg/L | NV | NA | NV | NM | NM | NM | NM | NM | <0.40 | NM | NM | NM | <0.20 | NM | NM | NM | NM | <0.40 |
| Toluene | μg/L | 24 | AO | 12 | <0.20 | <0.20 | 0.9 | <0.04 | <0.2 | <0.40 | <0.2 | <0.40 | <0.20 | <0.20 | <0.20 | <0.20 | <0.80 | < 0.40 | <0.40 |
| 2-Hexanone | μg/L | NV | NA | NV | NM | NM | NM | NM | NM | <0.60 | NM | NM | NM | < 0.30 | NM | NM | NM | NM | NM |
| Dibromochloromethane | μg/L | NV | NA | NV | NM | NM | NM | NM | NM | <0.20 | NM | NM | NM | <0.10 | NM | NM | NM | NM | <0.20 |
| Ethylene Dibromide | μg/L | NV | NA | NV | NM | NM | NM | NM | NM | <0.40 | NM | NM | NM | <0.10 | NM | NM | NM | NM | <0.20 |
| Tetrachloroethylene | μg/L | 30 | MAC | 7.5 | NM | NM | NM | NM | NM | <0.40 | NM | NM | NM | <0.20 | NM | NM | NM | NM | <0.40 |
| 1,1,1,2-Tetrachloroethane | μg/L | NV | NA | NV | NM | NM | NM | NM | NM | <0.20 | NM | NM | NM | <0.10 | NM | NM | NM | NM | <0.20 |
| Chlorobenzene | μg/L | NV | NA | NV | NM | NM | NM | NM | NM | <0.20 | NM | NM | NM | <0.10 | NM | NM | NM | NM | <0.20 |
| Ethylbenzene | μg/L | 2.4 | AO | 1.2 | NM | <0.10 | <0.1 | <0.05 | <0.1 | <0.20 | <0.1 | <0.20 | <0.10 | <0.10 | <0.10 | <0.10 | <0.40 | <0.20 | <0.20 |
| m & p-Xylene | μg/L | NV | NA | NV | NM | <0.20 | NM | NM | NM | <0.40 | NM | NM | NM | <0.20 | NM | NM | NM | NM | <0.40 |
| Bromoform | μg/L | NV | NA | NV | NM | NM | NM | NM | NM | <0.20 | NM | NM | NM | <0.10 | NM | NM | NM | NM | <0.20 |
| Styrene | μg/L | NV | NA | NV | NM | NM | NM | NM | NM | <0.20 | NM | NM | NM | <0.10 | NM | NM | NM | NM | <0.20 |
| 1,1,2,2-Tetrachloroethane | μg/L | NV | NA | NV | NM | NM | NM | NM | NM | <0.20 | NM | NM | NM | <0.10 | NM | NM | NM | NM | <0.20 |
| o-Xylene | μg/L | NV | NA | NV | NM | <0.10 | NM | NM | NM | <0.20 | NM | NM | NM | <0.10 | NM | NM | NM | NM | <0.20 |
| 1,3-Dichlorobenzene | μg/L | NV | NA | NV | NM | NM | NM | NM | NM | <0.20 | NM | NM | NM | <0.10 | NM | NM | NM | NM | <0.20 |
| 1,4-Dichlorobenzene | μg/L | 5 | MAC | 1.25 | <0.10 | NM | NM | NM | NM | <0.20 | NM | NM | NM | <0.10 | NM | NM | NM | NM | <0.20 |
| 1,2-Dichlorobenzene | μg/L | 200 | MAC | 50 | NM | NM | NM | NM | NM | <0.20 | NM | NM | NM | <0.10 | NM | NM | NM | NM | <0.20 |
| 1,2,4-Trichlorobenzene | μg/L | NV | NA | NV | NM | NM | NM | NM | NM | <0.60 | NM | NM | NM | <0.30 | NM | NM | NM | NM | NM |
| 1,3-Dichloropropene (Cis + Trans) | μg/L | NV | NA | NV | NM | NM | NM | NM | NM | <0.60 | NM | NM | NM | <0.30 | NM | NM | NM | NM | NM |
| Xylene Mixture (Total) | µa/L | 300 | AO | 150 | NM | <0.20 | 0.1 | < 0.04 | <0.2 | < 0.40 | <0.2 | < 0.40 | <0.20 | <0.20 | <0.20 | <0.20 | <0.80 | < 0.40 | <0.40 |

- Notes:

 1. ODWS = Ontario Drinking Water Standards (June 2006); AO= Aesthetic Objective and [I]MAC = [Interim] Maximum Acceptable Concentration.

 2. μg/L = micrograms per litre: NA = Not Applicable: NM = Not Monitored: NV = No value specified

 3. Data prior to 2006 obtained from Annual Monitoring Report (2005), Henderson, Paddon and Associates, Ltd.

 4. The ODWS is for trihalomethanes (THMs) based on a four quarter moving annual average of test results. The four most commonly detected THMs in drinking water are chloroform, bromodichloromethane, chlorodibromomethane and bromoform.
- 5. RUC = Reasonable Use Criteria (background concentration for VOCs assumed to be zero)
- 6. Shaded values outline detected parameters, values shown in **bold** indicate an exceedence of the RUC.

| | | | | Well ID | | | | OV | V-8 | | | 1 |
|-------------------------------------|-------|-----|------|---------|--------|--------|--------|--------|--------|--------|--------|--------|
| Parameter | Units | OD | ws | RUC | Oct-15 | Nov-16 | Sep-17 | Nov-18 | Oct-19 | Oct-20 | Nov-23 | Nov-24 |
| Dichlorodifluoromethane | μg/L | NV | NA | NV | <0.8 | <0.20 | NM | NM | <0.80 | <0.80 | NM | NM |
| Chloromethane | μg/L | NV | NA | NV | NM | <0.40 | NM | NM | <1.60 | NM | NM | NM |
| Vinyl Chloride | μg/L | 2 | MAC | 0.5 | <0.68 | 0.2 | NM | NM | <0.68 | <0.50 | <0.68 | NM |
| Bromomethane | µg/L | NV | NA | NV | <0.8 | <0.20 | NM | NM | <0.80 | <0.80 | NM | NM |
| Chloroethane | μg/L | NV | NA | NV | NM | 2.0 | NM | NM | <0.80 | NM | NM | NM |
| Trichlorofluoromethane | μg/L | NV | NA | NV | <1.6 | < 0.40 | NM | NM | <1.60 | <1.60 | NM | NM |
| Acetone | μg/L | NV | NA | NV | <4.0 | <1.0 | NM | NM | <4.0 | <4.0 | NM | NM |
| 1,1 Dichloroethylene | μg/L | 14 | MAC | 3.5 | <1.2 | < 0.30 | NM | NM | <1.20 | <0.50 | NM | NM |
| Methylene Chloride | μg/L | 50 | MAC | 12.5 | <1.2 | < 0.30 | NM | <1.2 | <1.20 | <1.20 | <1.2 | NM |
| trans- 1,2-dichloroethylene | μg/L | NV | NA | NV | <0.8 | 0.4 | NM | NM | <0.80 | <0.80 | NM | NM |
| Methyl tert-butyl ether | μg/L | NV | NA | NV | <0.8 | <0.20 | NM | NM | <0.80 | <0.80 | NM | NM |
| 1,1-Dichloroethane | µg/L | NV | NA | NV | <1.2 | < 0.30 | NM | NM | <1.20 | <0.50 | NM | NM |
| Methyl Ethyl Ketone | µg/L | NV | NA | NV | <4.0 | <1.0 | NM | NM | <4.0 | <4.0 | NM | NM |
| cis- 1,2-Dichloroethylene | μg/L | NV | NA | NV | <0.8 | <0.20 | NM | NM | <0.80 | <0.80 | NM | NM |
| Chloroform ⁽⁵⁾ | µg/L | 100 | MAC | 25 | <0.8 | <0.20 | NM | NM | <0.80 | <0.80 | NM | NM |
| 1,2 - Dichloroethane | μg/L | 5 | IMAC | 1.25 | <0.8 | 0.32 | NM | NM | <0.80 | <0.50 | NM | NM |
| 1,1,1-Trichloroethane | μg/L | NV | NA | NV | <1.2 | < 0.30 | NM | NM | <1.20 | <0.50 | NM | NM |
| Carbon Tetrachloride | µg/L | 5 | MAC | 1.25 | <0.8 | <0.20 | NM | NM | <0.80 | <0.20 | NM | NM |
| Benzene | µg/L | 5 | MAC | 1.25 | 2.5 | 2.4 | 2.0 | 2.2 | 1.6 | <0.50 | 2.24 | 1.83 |
| 1,2-Dichloropropane | µg/L | NV | NA | NV | <0.8 | <0.20 | NM | NM | <0.80 | <0.50 | NM | NM |
| Trichloroethylene | μg/L | 5 | MAC | 1.25 | <0.8 | <0.20 | NM | NM | <0.80 | <0.50 | NM | NM |
| Bromodichloromethane ⁽⁵⁾ | µg/L | 100 | MAC | 25 | <0.8 | <0.20 | NM | NM | <0.80 | <0.80 | NM | NM |
| cis-1,3-Dichloropropene | µg/L | NV | NA | NV | <0.8 | <0.20 | NM | NM | <0.80 | <0.80 | NM | NM |
| Methyl Isobutyl Ketone | μg/L | NV | NA | NV | <4.0 | <1.0 | NM | NM | <4.0 | <4.0 | NM | NM |
| trans-1,3-Dichloropropene | µg/L | NV | NA | NV | <1.2 | < 0.30 | NM | NM | <1.20 | <1.20 | NM | NM |
| 1,1,2-Trichloroethane | μg/L | NV | NA | NV | <0.8 | <0.20 | NM | NM | <0.80 | <0.50 | NM | NM |
| Toluene | μg/L | 24 | AO | 12 | <0.8 | <0.20 | <0.80 | <0.80 | <0.80 | <0.80 | <0.80 | <0.20 |
| 2-Hexanone | μg/L | NV | NA | NV | NM | <1.0 | NM | NM | <4.0 | NM | NM | NM |
| Dibromochloromethane | μg/L | NV | NA | NV | <0.40 | <0.10 | NM | NM | <0.40 | <0.40 | NM | NM |
| Ethylene Dibromide | μg/L | NV | NA | NV | <0.4 | <0.10 | NM | NM | <0.40 | <0.20 | NM | NM |
| Tetrachloroethylene | µg/L | 30 | MAC | 7.5 | <0.8 | <0.20 | NM | NM | <0.80 | <0.50 | NM | NM |
| 1,1,1,2-Tetrachloroethane | µg/L | NV | NA | NV | <0.4 | <0.10 | NM | NM | <0.40 | <0.40 | NM | NM |
| Chlorobenzene | µg/L | NV | NA | NV | <0.4 | <0.10 | NM | NM | <0.40 | < 0.40 | NM | NM |
| Ethylbenzene | μg/L | 2.4 | AO | 1.2 | <0.4 | 0.1 | <0.40 | <0.40 | <0.40 | <0.40 | NM | <0.10 |
| m & p-Xylene | μg/L | NV | NA | NV | <0.8 | <0.20 | NM | NM | <0.80 | <0.80 | NM | <0.20 |
| Bromoform | μg/L | NV | NA | NV | <0.4 | <0.10 | NM | NM | <0.40 | <0.40 | NM | NM |
| Styrene | μg/L | NV | NA | NV | <0.4 | <0.10 | NM | NM | <0.40 | <0.40 | NM | NM |
| 1,1,2,2-Tetrachloroethane | µg/L | NV | NA | NV | <0.4 | <0.10 | NM | NM | <0.40 | <0.40 | NM | NM |
| o-Xylene | µg/L | NV | NA | NV | <0.4 | <0.10 | NM | NM | <0.40 | <0.40 | NM | <0.10 |
| 1,3-Dichlorobenzene | µg/L | NV | NA | NV | <0.4 | <0.10 | NM | NM | <0.40 | <0.40 | NM | NM |
| 1,4-Dichlorobenzene | µg/L | 5 | MAC | 1.25 | <0.4 | <0.10 | NM | <0.40 | <0.40 | <0.40 | <0.40 | NM |
| 1,2-Dichlorobenzene | µg/L | 200 | MAC | 50 | <0.4 | <0.10 | NM | NM | <0.40 | <0.40 | NM | NM |
| 1,2,4-Trichlorobenzene | µg/L | NV | NA | NV | NM | < 0.30 | NM | NM | <1.20 | NM | NM | NM |
| 1,3-Dichloropropene (Cis + Trans) | μg/L | NV | NA | NV | <1.2 | < 0.30 | NM | NM | <1.20 | NM | NM | NM |
| Xylene Mixture (Total) | µg/L | 300 | AO | 150 | <0.8 | <0.20 | <0.80 | <0.80 | <0.80 | <0.80 | NM | <0.20 |

GROUNDWATER QUALITY DATA COMPREHENSIVE LIST

| | | | | | | | | | LI | EACHAT | TE CHA | RACTE | RIZATIO | N | | | | | | BACK | GROUNI | GW QU | ALITY |
|--------------------------|-------|-------|---------|---------|---------|---------|---------|---------|---------|---------|---------|-----------|---------|---------|---------|---------|---------|---------|------------|---------|---------|---------|---------|
| | | | Well ID | OW-2 | OW-2 | OW-2 | OW-2 | OW-2 | OW-2 | OW-2 | OW-2 | OW-8 | OW-8 | OW-8 | OW-8 | OW-8 | OW-8 | OW-8 | OW-8 | OW-11 | OW-12S | OW-12D | OW-13 |
| Parameter | Units | OD | WS | Oct-15 | Nov-16 | Sep-17 | Nov-18 | Oct-19 | Oct-20 | Nov-23 | Nov-24 | Oct-15 | Nov-16 | Sep-17 | Nov-18 | Oct-19 | Oct-20 | Nov-23 | Nov-24 | Sep-17 | Sep-17 | Sep-17 | Sep-17 |
| OTHER INORGANICS | | | | | | | | | | | | | | | | | | | | | | | |
| Biological Oxygen Demand | mg/L | NV | NA | | <5 | | <5 | жинн | <5 | <6 | | | 13 | | 10 | | 11 | 5 | y==== | | | | |
| Total Suspended Solids | mg/L | NV | NA | | 638 | | 2430 | | 513 | | | | 1530 | | 4340 | | 916 | | | | | | |
| Total Dissolved Solids | mg/L | 500 | AO | | 1900 | 2430 | 2450 | 2400 | 2710 | 1940 | 1640 | | 1640 | 1390 | 1220 | 888 | 1120 | 1090 | 1100 | 380 | 180 | 258 | 224 |
| Chemical Oxygen Demand | mg/L | NV | NA | | 22 | 47 | 23 | 9.9 | 18 | 58 | 46 | | 135 | 170 | 108 | 28.5 | 101 | 152 | 98 | 95 | 8 | 17 | <5 |
| Phenols | mg/L | NV | NA | | <0.001 | <0.001 | <0.001 | 2000 | 0.062 | 0.013 | | (40)-(40) | 0.002 | 0.002 | 0.008 | | 0.036 | 0.016 | - | <0.001 | <0.001 | <0.001 | <0.001 |
| METALS | | | | | | | | | | | | | | | | | | | | | | | |
| Aluminum | mg/L | 0.1 | OG | 0.033 | | | | 2002 | | | | 0.068 | | | | | | | - Carriera | | | **** | |
| Antimony | mg/L | 0.006 | IMAC | <0.003 | | | | | | | | < 0.003 | | | ; | | | | | | | | |
| Arsenic | mg/L | 0.025 | IMAC | <0.003 | <0.003 | < 0.003 | <0.003 | <0.003 | <0.001 | <0.001 | <0.001 | 0.007 | 0.007 | 0.006 | 0.009 | < 0.003 | 0.002 | 0.011 | 0.001 | < 0.003 | < 0.003 | 0.01 | < 0.003 |
| Barium | mg/L | 1.0 | MAC | 0.086 | 0.07 | 0.091 | 0.067 | 0.072 | 0.073 | 0.055 | 0.041 | 0.376 | 0.250 | 0.292 | 0.193 | 0.081 | 0.114 | 0.133 | 0.086 | 0.015 | 0.006 | 0.047 | 0.007 |
| Beryllium | mg/L | NV | NA | <0.001 | | | **** | анин) | | | | < 0.001 | | | | | | | | | | | |
| Bismuth | mg/L | NV | NA | <0.002 | | | | | | | | < 0.002 | 1 | | | | | | | | | | |
| Boron | mg/L | 5 | IMAC | 1.98 | 1.11 | 1.73 | 1.44 | 1.55 | 1.59 | 1.54 | 1.62 | 2.06 | 1.57 | 1.65 | 1.30 | 0.78 | 1.19 | 1.34 | 0.93 | 0.019 | <0.010 | 0.025 | <0.010 |
| Cadmium | mg/L | 0.005 | MAC | <0.001 | <0.001 | <0.002 | <0.002 | <0.002 | <0.0001 | <0.0001 | <0.0001 | <0.001 | <0.001 | <0.002 | <0.002 | < 0.002 | <0.0001 | <0.0001 | <0.0001 | <0.002 | <0.002 | < 0.002 | <0.002 |
| Chromium | mg/L | 0.05 | MAC | <0.003 | <0.003 | 0.011 | <0.003 | <0.003 | < 0.002 | <0.002 | <0.002 | 0.007 | 0.006 | 0.011 | 0.006 | < 0.003 | 0.003 | 0.004 | 0.003 | 0.003 | <0.003 | < 0.003 | <0.003 |
| Cobalt | mg/L | NV | NA | <0.001 | | | | | | | | 0.004 | | | | | | | | | | | |
| Copper | mg/L | NV | NA | <0.002 | <0.003 | <0.003 | <0.003 | <0.003 | 0.003 | <0.001 | 0.001 | 0.008 | <0.003 | <0.003 | <0.003 | < 0.003 | 0.006 | <0.001 | <0.001 | <0.003 | <0.003 | <0.003 | <0.003 |
| Iron | mg/L | 0.3 | AO | 3.87 | 3.02 | 4.13 | <0.010 | 3.55 | 0.034 | 5.23 | 0.033 | 24.9 | 23.4 | 12.9 | 25.6 | 1.45 | 0.065 | 40.7 | 0.08 | 1.49 | <0.010 | 0.16 | <0.010 |
| Lead | mg/L | 0.01 | MAC | <0.002 | <0.002 | <0.002 | <0.001 | <0.001 | <0.0005 | <0.0005 | <0.0005 | < 0.002 | <0.002 | <0.002 | <0.001 | <0.001 | <0.0005 | <0.0005 | <0.0005 | <0.002 | <0.002 | <0.002 | <0.002 |
| Lithium | mg/L | NV | NA | <0.010 | | - | | 222 | | | | <0.010 | | | | | | | | | | | |
| Manganese | mg/L | 0.05 | AO | 1.49 | 1.59 | 1.5 | 1.38 | 1.68 | 1.51 | 1.17 | 0.956 | 0.616 | 0.568 | 0.49 | 0.805 | 0.541 | 0.598 | 1.16 | 0.889 | 0.238 | 0.018 | 0.113 | 0.003 |
| Molybdenum | mg/L | NV | NA | 0.002 | | | | | | | | <0.001 | | | | 10000 | | | : | | | | |
| Mercury | mg/L | 0.001 | MAC | | <0.0001 | <0.0001 | <0.0001 | <0.0001 | <0.0001 | <0.0001 | <0.0001 | | <0.0001 | <0.0001 | <0.0001 | <0.0001 | <0.0001 | <0.0001 | <0.0001 | <0.0001 | <0.0001 | <0.0001 | <0.0001 |
| Nickel | mg/L | NV | NA | <0.003 | | | | | | | | 0.005 | | | | | | | | | | | |
| Selenium | mg/L | 0.01 | MAC | <0.004 | | | | | | | | <0.004 | | | | | | | | | | | |
| Silicon | mg/L | NV | NA | 4.23 | | 1 | | | | | | 7.93 | 1 | | | | | | | | | (| |
| Silver | mg/L | NV | NA | <0.002 | | | **** | 5,000 | | | | < 0.002 | | | | : mm== | | | 3,000 | | | | |
| Strontium | mg/L | NV | NA | 0.784 | | | | | | | | 0.899 | | | | | | 2000 | | | | | |
| Thallium | mg/L | NV | NA | <0.0003 | | | | | | | | <0.0003 | | | | | | | | | | | |
| Tin | mg/L | NV | NA | <0.002 | | | | | | | | < 0.002 | | | | | | | | | | | |
| Titanium | mg/L | NV | NA | 0.02 | 12222 | | | | | | | 0.003 | 10000 | | | 70000 | | | 10000 | | | 2000 | |
| Uranium | mg/L | NV | NA | 0.003 | | | | | | | | <0.002 | | | | | | | | | | | |
| Vanadium | mg/L | NV | NA | <0.002 | | | | | | | | 0.002 | | | | | | | | | | | |
| Zinc | mg/L | 5 | AO | 0.011 | 0.007 | <0.005 | 0.005 | 0.006 | <0.005 | <0.005 | <0.005 | 0.006 | 0.006 | <0.005 | <0.005 | <0.005 | <0.005 | <0.005 | <0.005 | <0.005 | <0.005 | <0.005 | <0.005 |
| Zirconium | mg/L | NV | NA | <0.004 | | | | mmm | | | | <0.004 | | | | | | | | | | | |

- Notes:


 1. ODWS = Ontario Drinking Water Standards (June 2003, Revised June 2006); AO= Aesthetic Objective and [I]MAC = [Interim] Maximum Acceptable Concentration.


 2. NA = Not Applicable: NM = Not Monitored: NV = No value specified


 3. Samples analyzed by AGAT Laboratories Limited.


 4. mg/L = milligrams per litre


 5. Shaded values exceed the ODWS



































MONITORING WELL OW-11




MONITORING WELL OW-12S



MONITORING WELL OW-12D



MONITORING WELL OW-13



Environmental Compliance Approval No. A272301 Eastnor Landfill Site: Annual Monitoring Report (2024) Municipality of Northern Bruce Peninsula, Ontario May 20, 2025

Appendix G Laboratory Certificates of Analyses



CLIENT NAME: GM BLUEPLAN

1260 Second Avenue East, Unit 1 OWEN SOUND, ON N4K2J3

(519) 376-1805

ATTENTION TO: Jessica Weller

PROJECT: M1553

AGAT WORK ORDER: 24T144883

WATER ANALYSIS REVIEWED BY: Yris Verastegui, Inorganic Team Lead

DATE REPORTED: May 13, 2024

PAGES (INCLUDING COVER): 7 VERSION*: 1

Should you require any information regarding this analysis please contact your client services representative at (905) 712-5100

| *Notes | |
|--------|--|
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |

Disclaimer:

- All work conducted herein has been done using accepted standard protocols, and generally accepted practices and methods. AGAT test methods may
 incorporate modifications from the specified reference methods to improve performance.
- All samples will be disposed of within 30 days after receipt unless a Long Term Storage Agreement is signed and returned. Some specialty analysis may
 be exempt, please contact your Client Project Manager for details.
- AGAT's liability in connection with any delay, performance or non-performance of these services is only to the Client and does not extend to any other
 third party. Unless expressly agreed otherwise in writing, AGAT's liability is limited to the actual cost of the specific analysis or analyses included in the
 services.
- . This Certificate shall not be reproduced except in full, without the written approval of the laboratory.
- The test results reported herewith relate only to the samples as received by the laboratory.
- Application of guidelines is provided "as is" without warranty of any kind, either expressed or implied, including, but not limited to, warranties of
 merchantability, fitness for a particular purpose, or non-infringement. AGAT assumes no responsibility for any errors or omissions in the guidelines
 contained in this document.
- All reportable information as specified by ISO/IEC 17025:2017 is available from AGAT Laboratories upon request.
- For environmental samples in the Province of Quebec: The analysis is performed on and results apply to samples as received. A temperature above 6°C upon receipt, as indicated in the Sample Reception Notification (SRN), could indicate the integrity of the samples has been compromised if the delay between sampling and submission to the laboratory could not be minimized.

AGAT Laboratories (V1)

Page 1 of 7

Member of: Association of Professional Engineers and Geoscientists of Alberta (APEGA)

Western Enviro-Agricultural Laboratory Association (WEALA) Environmental Services Association of Alberta (ESAA)



CLIENT NAME: GM BLUEPLAN

SAMPLING SITE:Eastnor

Certificate of Analysis

AGAT WORK ORDER: 24T144883

PROJECT: M1553

ATTENTION TO: Jessica Weller

SAMPLED BY:

5835 COOPERS AVENUE MISSISSAUGA, ONTARIO CANADA L4Z 1Y2 TEL (905)712-5100 FAX (905)712-5122 http://www.agatlabs.com

GM BLUEPLAN - Eastnor Groundwater Package

| DATE RECEIVED: 2024-05-01 | | | | | | | | | DATE REPORTE | D: 2024-05-13 | 3: |
|----------------------------------|-----------|-----|--|--|-------|--|--|-------|---|---------------|--|
| Parameter | § Unit | | RIPTION: LE TYPE: AMPLED: RDL | OW-4 Water 2024-04-30 5830742 | RDL | OW-5 Water 2024-04-30 5830748 | OW-6 Water 2024-04-30 5830749 | RDL | OW-7S Water 2024-04-30 5830750 | RDL | OW-8 Water 2024-04-30 5830751 |
| Electrical Conductivity | µS/cm | 6/3 | 2 | 434 | 2 | 952 | 882 | 2 | 3050 | 2 | 2450 |
| pH | pH Units | | NA | 7.88 | NA | 7.50 | 7.67 | NA NA | 6.98 | NA | 7.06 |
| Alkalinity (as CaCO3) | mg/L | | 5 | 257 | 5 | 485 | 416 | 5 | 1200 | 5 | 937 |
| Chloride | mg/L | | 0.10 | 1.44 | 0.12 | 14.2 | 20.1 | 0.49 | 128 | 0.49 | 115 |
| Nitrate as N | mg/L | | 0.10 | < 0.05 | 0.12 | <0.05 | <0.05 | 0.49 | <0.14 | 0.49 | <0.14 |
| Nitrite as N | mg/L | | 0.05 | <0.05 | 0.05 | <0.05 | <0.05 | 0.14 | <0.14 | 0.14 | <0.14 |
| Sulphate | mg/L | | 0.10 | 11.6 | 0.10 | 74.8 | 34.6 | 0.11 | 2.92 | 0.38 | 55.8 |
| Ortho Phosphate as P | mg/L | | 0.10 | <0.10 | 0.10 | <0.10 | <0.10 | 0.26 | <0.26 | 0.26 | <0.26 |
| Hardness (as CaCO3) (Calculated) | mg/L | | 0.10 | 255 | 0.5 | 520 | 419 | 0.5 | 794 | 0.5 | 679 |
| Ammonia as N | mg/L | | 0.02 | 0.05 | 0.02 | 0.40 | 0.13 | 0.16 | 63.5 | 0.16 | 30.6 |
| Total Kjeldahl Nitrogen | mg/L | | 0.10 | 0.12 | 0.10 | 1.06 | 3.55 | 0.36 | 66.0 | 0.14 | 35.6 |
| Dissolved Organic Carbon | mg/L | | 0.5 | 10.7 | 0.5 | 12.1 | 18.0 | 0.5 | 56.9 | 0.5 | 29.8 |
| Total Phosphorus | mg/L | | 0.02 | 0.03 | 0.02 | 1.11 | 2.49 | 0.02 | 0.67 | 0.02 | 0.28 |
| Dissolved Calcium | mg/L | | 0.05 | 66.3 | 0.05 | 137 | 113 | 0.05 | 235 | 0.05 | 198 |
| Dissolved Magnesium | mg/L | | 0.05 | 21.8 | 0.05 | 43.1 | 33.2 | 0.05 | 50.2 | 0.05 | 44.8 |
| Dissolved Potassium | mg/L | | 0.50 | 1.26 | 0.50 | 6.96 | 4.53 | 0.50 | 62.3 | 0.50 | 44.0 |
| Dissolved Sodium | mg/L | | 0.05 | 3.10 | 0.25 | 8.75 | 13.1 | 0.5 | 120 | 0.5 | 103 |
| Dissolved Boron | mg/L | | 0.010 | 0.040 | 0.010 | 0.484 | 0.111 | 0.010 | 1.94 | 0.010 | 1.27 |
| Dissolved Iron | mg/L | | 0.020 | 0.118 | 0.020 | <0.020 | <0.020 | 0.020 | 0.153 | 0.020 | 0.082 |
| Dissolved Manganese | mg/L | | 0.002 | 0.031 | 0.002 | 0.771 | 0.630 | 0.002 | 1.55 | 0.002 | 0.812 |
| Lab Filtration DOC | 3 | | | 1 | | 1 | 1 | | 1 | | 1 |
| Lab Filtration Metals | | | | 1 | | 1 | 1 | | 1 | | 1 |
| Lad Filtration Metals | | | | 1 | | 1 | 1 | | 1 | | |

Comments: RDL - Reported Detection Limit; G / S - Guideline / Standard

5830742-5830751 Metals analysis completed on a filtered sample.

DOC analysis completed on a filtered sample.

Dilution required, RDL has been increased accordingly.

Analysis performed at AGAT Toronto (unless marked by *)

Certified By:

Iris Verastegui



Quality Assurance

CLIENT NAME: GM BLUEPLAN

PROJECT: M1553

AGAT WORK ORDER: 24T144883 ATTENTION TO: Jessica Weller

SAMPLING SITE:Eastnor SAMPLED BY:

| OAMI LING SITE. Lastrici | | | | | | | <i>77</i> (1011 | LLD D | 78.083 | | | | | |
|---|-----------------|--------|----------|------|-----------------|--------------------|-----------------|----------------|----------|----------------------|-------|--------------|-------|----------------|
| Water Analysis | | | | | | | | | | | | | | |
| RPT Date: May 13, 2024 | | | UPLICATI | E | | REFERENCE MATERIAL | | | METHOD | BLANK | SPIKE | MATRIX SPIKE | | |
| PARAMETER | Batch Sample | Dup #1 | Dup #2 | RPD | Method Blank | Measured Value | | ptable nits | Recovery | Acceptable Limits | | Recovery | 1.1. | ptable nits |
| | | | | | | Value | Lower | Upper | | Lower | Upper | - | Lower | Upper |
| GM BLUEPLAN - Eastnor Groundwater Package | | | | | | | | | | | | | | |
| Electrical Conductivity | 5832463 | 931 | 941 | 1.1% | < 2 | 96% | 90% | 110% | | | | | | |
| pH | 5832463 | 8.04 | 8.11 | 0.9% | NA | 100% | 90% | 110% | | | | | | |
| Alkalinity (as CaCO3) | 5832463 | 422 | 428 | 1.4% | < 5 | 106% | 80% | 120% | | | | | | |
| Chloride | 5830353 | 27.6 | 27.8 | 0.7% | < 0.10 | 94% | 70% | 130% | 100% | 80% | 120% | 103% | 70% | 130% |
| Nitrate as N | 5830353 | 0.72 | 0.72 | 0.0% | < 0.05 | 92% | 70% | 130% | 94% | 80% | 120% | 95% | 70% | 130% |
| Nitrite as N | 5830353 | <0.05 | <0.05 | NA | < 0.05 | 94% | 70% | 130% | 96% | 80% | 120% | 96% | 70% | 130% |
| Sulphate | 5830353 | 41.3 | 41.4 | 0.2% | < 0.10 | 92% | 70% | 130% | 95% | 80% | 120% | 97% | 70% | 130% |
| Ortho Phosphate as P | 5830353 | <0.10 | <0.10 | NA | < 0.10 | 96% | 70% | 130% | 105% | 80% | 120% | 101% | 70% | 130% |
| Ammonia as N | 5832460 | 0.03 | 0.03 | NA | < 0.02 | 105% | 70% | 130% | 103% | 80% | 120% | 93% | 70% | 130% |
| Total Kjeldahl Nitrogen | 5836990 | 9.31 | 9.45 | 1.5% | < 0.10 | 102% | 70% | 130% | 88% | 80% | 120% | NA | 70% | 130% |
| Dissolved Organic Carbon | 5836165 | 0.9 | 0.8 | NA | < 0.5 | 96% | 90% | 110% | 104% | 90% | 110% | 101% | 80% | 120% |
| Total Phosphorus | 5832532 | 0.19 | 0.19 | 0.0% | < 0.02 | 104% | 70% | 130% | 97% | 80% | 120% | 83% | 70% | 130% |
| Dissolved Calcium | 5830017 | 129 | 128 | 0.8% | < 0.05 | 102% | 70% | 130% | 105% | 80% | 120% | 104% | 70% | 130% |
| Dissolved Magnesium | 5830017 | 9.99 | 9.83 | 1.6% | < 0.05 | 104% | 70% | 130% | 111% | 80% | 120% | 113% | 70% | 130% |
| Dissolved Potassium | 5830017 | 2.56 | 2.56 | 0.0% | < 0.50 | 102% | 70% | 130% | 105% | 80% | 120% | 107% | 70% | 130% |
| Dissolved Sodium | 5830742 5830742 | 3.10 | 3.06 | 1.3% | < 0.05 | 100% | 70% | 130% | 100% | 80% | 120% | 95% | 70% | 130% |
| Dissolved Boron | 5830017 | 0.059 | 0.057 | 3.4% | < 0.010 | 98% | 70% | 130% | 122% | 80% | 120% | 126% | 70% | 130% |
| Dissolved Iron | 5830017 | <0.020 | <0.020 | NA | < 0.010 | 103% | 70% | 130% | 106% | 80% | 120% | 105% | 70% | 130% |
| Dissolved Manganese | 5830017 | 0.004 | 0.003 | NA | < 0.002 | 101% | 70% | 130% | 107% | 80% | 120% | 107% | 70% | 130% |

Comments: NA signifies Not Applicable.

Duplicate NA: results are under 5X the RDL and will not be calculated.

Matrix spike NA: Spike level < native concentration. Matrix spike acceptance limits do not apply and are not calculated.

QA Qualifier for metals – Dissolved Boron: For a multi-element scan for lab control standards and matrix spikes, up to 10% of analytes may exceed the quoted limits by up to 10% absolute and it is considered acceptable.

Certified By:

Iris Verástegui



QC Exceedance

CLIENT NAME: GM BLUEPLAN

PROJECT: M1553

AGAT WORK ORDER: 24T144883

ATTENTION TO: Jessica Weller

| RPT Date: May 13, 2024 | | REFERENC | E MATERIAL | METHOD | BLANK S | PIKE | MAT | RIX SPIKE |
|------------------------|-----------|----------|----------------------|----------|----------------------|------|----------|----------------------|
| PARAMETER | Sample Id | Measured | Acceptable Limits | Recovery | Acceptable Limits | | Recovery | Acceptable Limits |
| | | Value | Lower Upper | | Lower | | | Lower Upper |

GM BLUEPLAN - Eastnor Groundwater Package

Dissolved Boron 98% 70% 130% 122% 80% 120% 126% 70% 130%

Comments: NA signifies Not Applicable.

Duplicate NA: results are under 5X the RDL and will not be calculated.

Matrix spike NA: Spike level < native concentration. Matrix spike acceptance limits do not apply and are not calculated.

QA Qualifier for metals – Dissolved Boron: For a multi-element scan for lab control standards and matrix spikes, up to 10% of analytes may exceed the quoted limits by up to 10% absolute and it is considered acceptable.

Method Summary

CLIENT NAME: GM BLUEPLAN

PROJECT: M1553

AGAT WORK ORDER: 24T144883

ATTENTION TO: Jessica Weller

SAMPLING SITE:Eastnor SAMPLED BY:

| SAMPLING SITE: Eastnor | | SAMPLED BY: | | | | | | | | | |
|----------------------------------|--------------|--|--------------------------|--|--|--|--|--|--|--|--|
| PARAMETER | AGAT S.O.P | LITERATURE REFERENCE | ANALYTICAL TECHNIQUE | | | | | | | | |
| Water Analysis | | - | | | | | | | | | |
| Electrical Conductivity | INOR-93-6000 | modified from SM 2510 B | PC TITRATE | | | | | | | | |
| pH | INOR-93-6000 | modified from SM 4500-H+ B | PC TITRATE | | | | | | | | |
| Alkalinity (as CaCO3) | INOR-93-6000 | Modified from SM 2320 B | PC TITRATE | | | | | | | | |
| Chloride | INOR-93-6004 | modified from SM 4110 B | ION CHROMATOGRAPH | | | | | | | | |
| Nitrate as N | INOR-93-6004 | modified from SM 4110 B | ION CHROMATOGRAPH | | | | | | | | |
| Nitrite as N | INOR-93-6004 | modified from SM 4110 B | ION CHROMATOGRAPH | | | | | | | | |
| Sulphate | INOR-93-6004 | modified from SM 4110 B | ION CHROMATOGRAPH | | | | | | | | |
| Ortho Phosphate as P | INOR-93-6004 | modified from SM 4110 B | ION CHROMATOGRAPH | | | | | | | | |
| Hardness (as CaCO3) (Calculated) | MET-93-6105 | modified from EPA SW-846 6010C & 200.7 & SM 2340 B | CALCULATION | | | | | | | | |
| Ammonia as N | INOR-93-6059 | modified from SM 4500-NH3 H | LACHAT FIA | | | | | | | | |
| Total Kjeldahl Nitrogen | INOR-93-6048 | modified from EPA 351.2 and SM 4500-NORG D | LACHAT FIA | | | | | | | | |
| Dissolved Organic Carbon | INOR-93-6049 | modified from SM 5310 B | SHIMADZU CARBON ANALYZER | | | | | | | | |
| Total Phosphorus | INOR-93-6057 | modified from LACHAT 10-115-01-3A | LACHAT FIA | | | | | | | | |
| Dissolved Calcium | MET-93-6103 | modified from EPA 200.8 and EPA 3005A | ICP/MS | | | | | | | | |
| Dissolved Magnesium | MET-93-6103 | modified from EPA 200.8, 3005A, 3010A & 6020B | ICP/MS | | | | | | | | |
| Dissolved Potassium | MET-93-6103 | modified from EPA 200.8 and EPA 3005A | ICP/MS | | | | | | | | |
| Dissolved Sodium | MET-93-6105 | modified from EPA 6010D | ICP/OES | | | | | | | | |
| Dissolved Boron | MET-93-6103 | modified from EPA 200.8 and EPA 3005A | ICP-MS | | | | | | | | |
| Dissolved Iron | MET-93-6103 | modified from EPA 200.8 and EPA 3005A | ICP-MS | | | | | | | | |
| Dissolved Manganese | MET-93-6103 | modified from EPA 200.8 and EPA 3005A | ICP-MS | | | | | | | | |
| Lab Filtration DOC | SR-78-9001 | | FILTRATION | | | | | | | | |
| Lab Filtration Metals | SR-78-9001 | | FILTRATION | | | | | | | | |



CLIENT NAME: GEI CONSULTANTS

1260 Second Avenue East, Unit 1 OWEN SOUND, ON N4K2J3

(519) 376-1805

ATTENTION TO: Jessica Weller

PROJECT: M1553 - Eastnor

AGAT WORK ORDER: 24T220810

TRACE ORGANICS REVIEWED BY: Neli Popnikolova, Senior Chemist WATER ANALYSIS REVIEWED BY: Yris Verastegui, Inorganic Team Lead

DATE REPORTED: Nov 25, 2024

PAGES (INCLUDING COVER): 14 VERSION*: 1

Should you require any information regarding this analysis please contact your client services representative at (905) 712-5100

| <u>Notes</u> | |
|--------------|--|
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |

Disclaimer

- All work conducted herein has been done using accepted standard protocols, and generally accepted practices and methods. AGAT test methods may
 incorporate modifications from the specified reference methods to improve performance.
- All samples will be disposed of within 30 days after receipt unless a Long Term Storage Agreement is signed and returned. Some specialty analysis may
 be exempt, please contact your Client Project Manager for details.
- AGAT's liability in connection with any delay, performance or non-performance of these services is only to the Client and does not extend to any other
 third party. Unless expressly agreed otherwise in writing, AGAT's liability is limited to the actual cost of the specific analysis or analyses included in the
 services.
- This Certificate shall not be reproduced except in full, without the written approval of the laboratory.
- The test results reported herewith relate only to the samples as received by the laboratory.
- Application of guidelines is provided "as is" without warranty of any kind, either expressed or implied, including, but not limited to, warranties of
 merchantability, fitness for a particular purpose, or non-infringement. AGAT assumes no responsibility for any errors or omissions in the guidelines
 contained in this document.
- All reportable information is available on request from AGAT Laboratories, in accordance with ISO/IEC 17025:2017, ISO/IEC 17025:2005 (Quebec), DR-12-PALA and/or NELAP Standards.
- This document is signed by an authorized signatory who meets the requirements of the MELCCFP, CALA, CCN and NELAP.
- For environmental samples in the Province of Quebec: The analysis is performed on and results apply to samples as received. A temperature above 6°C upon receipt, as indicated in the Sample Reception Notification (SRN), could indicate the integrity of the samples has been compromised if the delay between sampling and submission to the laboratory could not be minimized.

AGAT Laboratories (V1)

Page 1 of 14

Member of: Association of Professional Engineers and Geoscientists of Alberta (APEGA)

Western Enviro-Agricultural Laboratory Association (WEALA) Environmental Services Association of Alberta (ESAA) AGAT Laboratories is accredited to ISO/IEC 17025 by the Canadian Association for Laboratory Accreditation Inc. (CALA) and/or Standards Council of Canada (SCC) for specific tests listed on the scope of accreditation. AGAT Laboratories (Mississauga) is also accredited by the Canadian Association for Laboratory Accreditation Inc. (CALA) for specific drinking water tests. Accreditations are location and parameter specific. A complete listing of parameters for each location is available from www.cala.ca and/or www.scc.ca. The tests in this report may not necessarily be included in the scope of accreditation. Measurement Uncertainty is not taken into consideration when stating conformity with a specified requirement.



Certificate of Analysis

AGAT WORK ORDER: 24T220810

PROJECT: M1553 - Eastnor

ATTENTION TO: Jessica Weller

SAMPLED BY:

5835 COOPERS AVENUE MISSISSAUGA, ONTARIO CANADA L4Z 1Y2 TEL (905)712-5100 FAX (905)712-5122 http://www.agatlabs.com

O. Reg. 153(511) - BTEX (Water)

| DATE REPORTED: 2024-11-25 |
|---------------------------|
| DATE REPORTED: 2024-11-25 |
| |

| | SA | AMPLE DESCRIPTION: | OW-2 | OW-8 |
|----------------------|------------|--------------------|------------|------------|
| | | SAMPLE TYPE: | Water | Water |
| | | DATE SAMPLED: | 2024-11-12 | 2024-11-12 |
| Parameter | Unit | G/S RDL | 6323194 | 6323203 |
| Benzene | μg/L | 0.20 | <0.20 | 1.83 |
| Toluene | μg/L | 0.20 | <0.20 | <0.20 |
| Ethylbenzene | μg/L | 0.10 | <0.10 | <0.10 |
| m & p-Xylene | μg/L | 0.20 | <0.20 | <0.20 |
| o-Xylene | μg/L | 0.10 | <0.10 | <0.10 |
| Xylenes (Total) | μg/L | 0.20 | <0.20 | <0.20 |
| Surrogate | Unit | Acceptable Limits | | |
| Toluene-d8 | % Recovery | 50-140 | 93 | 93 |
| 4-Bromofluorobenzene | % Recovery | 50-140 | 118 | 124 |
| | | | | |

Comments: RDL - Reported Detection Limit; G / S - Guideline / Standard

6323194-6323203 Results relate only to the items tested.

Xylenes total is a calculated parameter. The calculated value is the sum of m&p-Xylene + o-Xylene. The calculated parameter is non-accredited. The parameters that are components of the calculation are

accredited.

CLIENT NAME: GEI CONSULTANTS

SAMPLING SITE: EASTNOR

Analysis performed at AGAT Toronto (unless marked by *)

Certified By:





SAMPLING SITE: EASTNOR

Certificate of Analysis

AGAT WORK ORDER: 24T220810

PROJECT: M1553 - Eastnor

ATTENTION TO: Jessica Weller

SAMPLED BY:

5835 COOPERS AVENUE MISSISSAUGA, ONTARIO CANADA L4Z 1Y2 TEL (905)712-5100 FAX (905)712-5122 http://www.agatlabs.com

Eastnor Comprehensive Groundwater Package

| | | Lus | anor compi | CHCHSIVE | Orounawater | 1 dokage |
|---------------------------|----------|--------------------|------------|----------|-------------|---------------------------|
| DATE RECEIVED: 2024-11-14 | | | | | | DATE REPORTED: 2024-11-25 |
| | S | AMPLE DESCRIPTION: | OW-2 | | OW-8 | |
| | | SAMPLE TYPE: | Water | | Water | |
| | | DATE SAMPLED: | 2024-11-12 | | 2024-11-12 | |
| Parameter | Unit | G/S RDL | 6323194 | RDL | 6323203 | |
| Electrical Conductivity | uS/cm | 2 | 2830 | 2 | 2370 | |
| pH | pH Units | NA | 7.48 | NA | 7.09 | |
| Total Dissolved Solids | mg/L | 10 | 1640 | 10 | 1100 | |
| Alkalinity (as CaCO3) | mg/L | 5 | 822 | 5 | 961 | |
| Chloride | mg/L | 0.49 | 56.5 | 0.49 | 118 | |
| Nitrate as N | mg/L | 0.14 | <0.14 | 0.14 | <0.14 | |
| Nitrite as N | mg/L | 0.11 | <0.11 | 0.11 | <0.11 | |
| Sulphate | mg/L | 0.38 | 583 | 0.38 | 51.1 | |
| Chemical Oxygen Demand | mg/L | 5 | 46 | 5 | 98 | |
| Ammonia as N | mg/L | 0.02 | 0.03 | 0.06 | 30.4 | |
| Total Kjeldahl Nitrogen | mg/L | 0.10 | 0.60 | 0.14 | 31.1 | |
| Dissolved Organic Carbon | mg/L | 0.5 | 23.0 | 0.5 | 43.3 | |
| Total Phosphorus | mg/L | 0.02 | 0.50 | 0.02 | 1.15 | |
| Dissolved Calcium | mg/L | 0.05 | 193 | 0.05 | 179 | |
| Dissolved Magnesium | mg/L | 0.05 | 138 | 0.05 | 36.4 | |
| Dissolved Potassium | mg/L | 0.50 | 105 | 0.50 | 34.1 | |
| Dissolved Sodium | mg/L | 0.05 | 43.6 | 0.05 | 109 | |
| Dissolved Arsenic | mg/L | 0.001 | < 0.001 | 0.001 | 0.001 | |
| Dissolved Barium | mg/L | 0.002 | 0.041 | 0.002 | 0.086 | |
| Dissolved Boron | mg/L | 0.010 | 1.62 | 0.010 | 0.925 | |
| Dissolved Cadmium | mg/L | 0.0001 | <0.0001 | 0.0001 | < 0.0001 | |
| Dissolved Chromium | mg/L | 0.002 | <0.002 | 0.002 | 0.003 | |
| Dissolved Copper | mg/L | 0.001 | 0.001 | 0.001 | < 0.001 | |
| Dissolved Iron | mg/L | 0.020 | 0.033 | 0.020 | 0.080 | |
| Dissolved Lead | mg/L | 0.0005 | <0.0005 | 0.0005 | < 0.0005 | |
| Dissolved Manganese | mg/L | 0.002 | 0.956 | 0.002 | 0.889 | |
| Dissolved Mercury | mg/L | 0.0001 | <0.0001 | 0.0001 | < 0.0001 | |
| Dissolved Zinc | mg/L | 0.005 | <0.005 | 0.005 | < 0.005 | |
| Lab Filtration DOC | | | 1 | | 1 | |
| Lab Filtration Metals | | | 1 | | | |

Certified By:

Iris Verastegui



Certificate of Analysis

AGAT WORK ORDER: 24T220810

PROJECT: M1553 - Eastnor

ATTENTION TO: Jessica Weller

SAMPLED BY:

5835 COOPERS AVENUE MISSISSAUGA, ONTARIO CANADA L4Z 1Y2 TEL (905)712-5100 FAX (905)712-5122 http://www.agatlabs.com

Eastnor Comprehensive Groundwater Package

DATE RECEIVED: 2024-11-14 **DATE REPORTED: 2024-11-25**

> OW-2 SAMPLE DESCRIPTION: 8-WO SAMPLE TYPE: Water Water DATE SAMPLED: 2024-11-12 2024-11-12 G/S RDL 6323194 RDL 6323203

Unit Lab Filtration mercury

Comments: RDL - Reported Detection Limit; G / S - Guideline / Standard

6323194-6323203 Metals analysis completed on a filtered sample. Dilution required, RDL has been increased accordingly.

Analysis performed at AGAT Toronto (unless marked by *)

CLIENT NAME: GEI CONSULTANTS

SAMPLING SITE: EASTNOR

Parameter

Certified By:

Yris Verástegui



SAMPLING SITE: EASTNOR

Certificate of Analysis

AGAT WORK ORDER: 24T220810

PROJECT: M1553 - Eastnor

ATTENTION TO: Jessica Weller

SAMPLED BY:

5835 COOPERS AVENUE MISSISSAUGA, ONTARIO CANADA L4Z 1Y2 TEL (905)712-5100 FAX (905)712-5122 http://www.agatlabs.com

Eastnor Groundwater Package

| DATE RECEIVED: 2024-11-14 | | | | | | | D | ATE REPORT | ED: 2024-11-25 | |
|----------------------------------|----------|--|--|-------|--|-------|--|------------|--|--|
| Parameter | S | SAMPLE DESCRIPTION: SAMPLE TYPE: DATE SAMPLED: G/S RDL | OW-1 Water 2024-11-12 6323085 | RDL | OW-3 Water 2024-11-12 6323181 | RDL | OW-4 Water 2024-11-12 6323182 | RDL | OW-5 Water 2024-11-12 6323183 | OW-6 Water 2024-11-12 6323184 |
| Electrical Conductivity | uS/cm | 2 | 525 | 2 | 2590 | 2 | 441 | 2 | 1030 | 836 |
| pH | pH Units | NA | 7.70 | NA | 7.47 | NA | 7.83 | NA | 7.53 | 7.77 |
| Alkalinity (as CaCO3) | mg/L | 5 | 295 | 5 | 831 | 5 | 266 | 5 | 553 | 512 |
| Chloride | mg/L | 0.10 | 3.69 | 0.49 | 64.3 | 0.10 | 1.48 | 0.12 | 12.7 | 23.1 |
| Nitrate as N | mg/L | 0.05 | 0.05 | 0.14 | <0.14 | 0.05 | <0.05 | 0.05 | < 0.05 | < 0.05 |
| Nitrite as N | mg/L | 0.05 | <0.05 | 0.11 | <0.11 | 0.05 | <0.05 | 0.05 | < 0.05 | < 0.05 |
| Sulphate | mg/L | 0.10 | 35.2 | 0.38 | 496 | 0.10 | 10.5 | 0.10 | 89.7 | 25.6 |
| Ortho Phosphate as P | mg/L | 0.10 | <0.10 | 0.26 | <0.26 | 0.10 | <0.10 | 0.10 | <0.10 | <0.10 |
| Hardness (as CaCO3) (Calculated) | mg/L | 0.5 | 278 | 0.5 | 1150 | 0.5 | 216 | 0.5 | 507 | 353 |
| Ammonia as N | mg/L | 0.02 | 0.29 | 0.02 | 0.17 | 0.02 | <0.02 | 0.02 | <0.02 | < 0.02 |
| Total Kjeldahl Nitrogen | mg/L | 0.10 | 0.90 | 0.10 | 0.77 | 0.10 | 0.26 | 0.10 | 0.50 | 1.88 |
| Dissolved Organic Carbon | mg/L | 0.5 | 13.0 | 0.5 | 22.4 | 0.5 | 10.6 | 0.5 | 11.7 | 20.8 |
| Total Phosphorus | mg/L | 0.02 | 0.14 | 0.02 | 0.15 | 0.02 | 0.11 | 0.02 | 0.56 | 2.32 |
| Dissolved Calcium | mg/L | 0.05 | 73.6 | 0.05 | 209 | 0.05 | 57.4 | 0.05 | 137 | 97.0 |
| Dissolved Magnesium | mg/L | 0.05 | 22.8 | 0.05 | 153 | 0.05 | 17.7 | 0.05 | 40.1 | 26.9 |
| Dissolved Potassium | mg/L | 0.50 | <0.50 | 0.50 | 62.6 | 0.50 | 0.88 | 0.50 | 6.34 | 4.95 |
| Dissolved Sodium | mg/L | 0.05 | 2.22 | 0.05 | 40.9 | 0.05 | 2.92 | 0.05 | 9.12 | 14.1 |
| Dissolved Boron | mg/L | 0.010 | 0.018 | 0.010 | 1.19 | 0.010 | 0.038 | 0.010 | 0.553 | 0.158 |
| Dissolved Iron | mg/L | 0.020 | 0.341 | 0.020 | <0.020 | 0.020 | <0.020 | 0.020 | 0.025 | < 0.020 |
| Dissolved Manganese | mg/L | 0.002 | 0.233 | 0.002 | 0.775 | 0.002 | 0.025 | 0.002 | 0.595 | 0.041 |
| Lab Filtration DOC | | | 1 | | 1 | | 1 | | 1 | 1 |
| Lab Filtration Metals | | | 1 | | 1 | | 1 | | 1 | 1 |

Certified By:

Tris Verastegui



SAMPLING SITE: EASTNOR

Certificate of Analysis

AGAT WORK ORDER: 24T220810

PROJECT: M1553 - Eastnor

ATTENTION TO: Jessica Weller

SAMPLED BY:

5835 COOPERS AVENUE MISSISSAUGA, ONTARIO CANADA L4Z 1Y2 TEL (905)712-5100 FAX (905)712-5122 http://www.agatlabs.com

Eastnor Groundwater Package

| | | | | | | 1 T | | | | |
|----------------------------------|----------|--|------------------------------|-------|------------------------------|-------|-------------------------------|-------------------------------|--------------|------------------------------|
| DATE RECEIVED: 2024-11-14 | | | | | | | ĺ | DATE REPORTE | D: 2024-11-2 | 5 |
| | | SAMPLE DESCRIPTION: SAMPLE TYPE: DATE SAMPLED: | OW-7S Water 2024-11-12 | | OW-7D Water 2024-11-12 | | OW-10S Water 2024-11-12 | OW-10D Water 2024-11-12 | | OW-11 Water 2024-11-12 |
| Parameter | Unit | G/S RDL | 6323185 | RDL | 6323186 | RDL | 6323187 | 6323188 | RDL | 6323189 |
| Electrical Conductivity | uS/cm | 2 | 2900 | 2 | 924 | 2 | 598 | 534 | 2 | 609 |
| рН | pH Units | NA | 7.03 | NA | 7.63 | NA | 7.29 | 7.77 | NA | 7.52 |
| Alkalinity (as CaCO3) | mg/L | 5 | 1220 | 5 | 496 | 5 | 324 | 339 | 5 | 373 |
| Chloride | mg/L | 0.49 | 126 | 0.12 | 18.2 | 0.10 | 4.68 | 2.58 | 0.10 | 2.90 |
| Nitrate as N | mg/L | 0.14 | <0.14 | 0.05 | < 0.05 | 0.05 | < 0.05 | < 0.05 | 0.05 | < 0.05 |
| Nitrite as N | mg/L | 0.11 | <0.11 | 0.05 | <0.05 | 0.05 | <0.05 | <0.05 | 0.05 | < 0.05 |
| Sulphate | mg/L | 0.38 | 3.08 | 0.10 | 78.9 | 0.10 | 35.5 | 6.45 | 0.10 | 0.31 |
| Ortho Phosphate as P | mg/L | 0.26 | <0.26 | 0.10 | <0.10 | 0.10 | <0.10 | <0.10 | 0.10 | <0.10 |
| Hardness (as CaCO3) (Calculated) | mg/L | 0.5 | 597 | 0.5 | 250 | 0.5 | 280 | 253 | 0.5 | 291 |
| Ammonia as N | mg/L | 0.16 | 90.5 | 0.02 | 0.10 | 0.02 | 0.24 | 0.28 | 0.02 | 0.12 |
| Total Kjeldahl Nitrogen | mg/L | 0.72 | 344 | 0.10 | 0.79 | 0.10 | 1.60 | 0.54 | 0.10 | 1.20 |
| Dissolved Organic Carbon | mg/L | 0.5 | 51.8 | 0.5 | 17.4 | 0.5 | 35.9 | 9.2 | 0.5 | 38.6 |
| Total Phosphorus | mg/L | 0.02 | 1.03 | 0.02 | 2.87 | 0.02 | 1.10 | 0.70 | 0.02 | 0.12 |
| Dissolved Calcium | mg/L | 0.05 | 182 | 0.05 | 65.3 | 0.05 | 74.9 | 65.9 | 0.10 | 82.7 |
| Dissolved Magnesium | mg/L | 0.05 | 34.7 | 0.05 | 21.0 | 0.05 | 22.5 | 21.4 | 0.10 | 20.4 |
| Dissolved Potassium | mg/L | 0.50 | 53.3 | 0.50 | <0.50 | 0.50 | 0.53 | <0.50 | 1.00 | <1.00 |
| Dissolved Sodium | mg/L | 0.05 | 114 | 0.05 | 1.65 | 0.05 | 3.85 | 1.72 | 0.10 | 2.75 |
| Dissolved Boron | mg/L | 0.010 | 1.63 | 0.010 | 0.023 | 0.010 | 0.041 | 0.022 | 0.010 | 0.021 |
| Dissolved Iron | mg/L | 0.020 | 0.106 | 0.020 | 0.022 | 0.020 | 0.273 | <0.020 | 0.040 | 0.937 |
| Dissolved Manganese | mg/L | 0.002 | 1.13 | 0.002 | 0.059 | 0.002 | 0.259 | 0.062 | 0.004 | 0.263 |
| Lab Filtration DOC | | | 1 | | 1 | | 1 | 1 | | 1 |
| Lab Filtration Metals | | | 1 | | 1 | | 1 | 1 | | 1 |

Certified By:

Yris Verastegui



SAMPLING SITE: EASTNOR

Certificate of Analysis

AGAT WORK ORDER: 24T220810

PROJECT: M1553 - Eastnor

ATTENTION TO: Jessica Weller

SAMPLED BY:

5835 COOPERS AVENUE MISSISSAUGA, ONTARIO CANADA L4Z 1Y2 TEL (905)712-5100 FAX (905)712-5122 http://www.agatlabs.com

Eastnor Groundwater Package

| | | | Luctii | or organiame | ioi i donago |
|----------------------------------|----------|---|---------|-------------------------------|---------------------------|
| DATE RECEIVED: 2024-11-14 | | | | | DATE REPORTED: 2024-11-25 |
| | S. | AMPLE DESCRIPTION: SAMPLE TYPE: DATE SAMPLED: | Water | OW-12D Water 2024-11-12 | |
| Parameter | Unit | G/S RDL | 6323190 | 6323191 | |
| Electrical Conductivity | uS/cm | 2 | 341 | 350 | |
| рН | pH Units | NA | 7.88 | 7.72 | |
| Alkalinity (as CaCO3) | mg/L | 5 | 234 | 360 | |
| Chloride | mg/L | 0.10 | 0.74 | 1.57 | |
| Nitrate as N | mg/L | 0.05 | < 0.05 | 0.24 | |
| Nitrite as N | mg/L | 0.05 | < 0.05 | <0.05 | |
| Sulphate | mg/L | 0.10 | 4.18 | 0.78 | |
| Ortho Phosphate as P | mg/L | 0.10 | <0.10 | <0.10 | |
| Hardness (as CaCO3) (Calculated) | mg/L | 0.5 | 166 | 171 | |
| Ammonia as N | mg/L | 0.02 | < 0.02 | 0.06 | |
| Total Kjeldahl Nitrogen | mg/L | 0.10 | <0.10 | 1.14 | |
| Dissolved Organic Carbon | mg/L | 0.5 | 1.9 | 18.2 | |
| Total Phosphorus | mg/L | 0.02 | 0.54 | 3.11 | |
| Dissolved Calcium | mg/L | 0.05 | 42.6 | 48.6 | |
| Dissolved Magnesium | mg/L | 0.05 | 14.5 | 12.1 | |
| Dissolved Potassium | mg/L | 0.50 | < 0.50 | 0.71 | |
| Dissolved Sodium | mg/L | 0.05 | 0.72 | 1.81 | |
| Dissolved Boron | mg/L | 0.010 | <0.010 | 0.020 | |
| Dissolved Iron | mg/L | 0.020 | < 0.020 | 0.033 | |
| Dissolved Manganese | mg/L | 0.002 | 0.003 | 0.038 | |
| Lab Filtration DOC | | | 1 | 1 | |
| Lab Filtration Metals | | | 1 | 1 | |

Comments: RDL - Reported Detection Limit; G / S - Guideline / Standard

6323085-6323191 Metals analysis completed on a filtered sample.

Dilution required, RDL has been increased accordingly.

Analysis performed at AGAT Toronto (unless marked by *)

Certified By:

Yris Verastegui



Quality Assurance

CLIENT NAME: GEI CONSULTANTS

PROJECT: M1553 - Eastnor SAMPLING SITE:EASTNOR

AGAT WORK ORDER: 24T220810
ATTENTION TO: Jessica Weller

SAMPLED BY:

| CAMILLING CITE. LACTION | | | | | | | | | | | | | | | | | | | |
|---------------------------------|---------|-----------|--------|--------|--------------------|-----------------|----------------|--------------------|----------|----------------------|--------------|----------|------|-------|---------------------|--|----------|----------------------|--|
| Trace Organics Analysis | | | | | | | | | | | | | | | | | | | |
| RPT Date: Nov 25, 2024 | | DUPLICATE | | | REFERENCE MATERIAL | | TERIAL | METHOD BLANK SPIKE | | | MATRIX SPIKE | | KE | | | | | | |
| PARAMETER | Batch | Sample | Dup #1 | Dup #2 | RPD | Method Blank | Blank Measured | | Measured | Acceptable Limits | | Recovery | Limi | | Acceptabl Limits | | Recovery | Acceptable Limits | |
| | | ld | | | | | Value | Lower | Upper | | Lower | Upper | | Lower | Upper | | | | |
| O. Reg. 153(511) - BTEX (Water) | | | | | | | | | | | | | | | | | | | |
| Benzene | 6323433 | | <0.20 | < 0.20 | NA | < 0.20 | 112% | 50% | 140% | 114% | 60% | 130% | 87% | 50% | 140% | | | | |
| Toluene | 6323433 | | <0.20 | < 0.20 | NA | < 0.20 | 119% | 50% | 140% | 115% | 60% | 130% | 105% | 50% | 140% | | | | |
| Ethylbenzene | 6323433 | | <0.10 | < 0.10 | NA | < 0.10 | 112% | 50% | 140% | 111% | 60% | 130% | 95% | 50% | 140% | | | | |
| m & p-Xylene | 6323433 | | <0.20 | < 0.20 | NA | < 0.20 | 120% | 50% | 140% | 118% | 60% | 130% | 105% | 50% | 140% | | | | |
| o-Xylene | 6323433 | | <0.10 | < 0.10 | NA | < 0.10 | 97% | 50% | 140% | 117% | 60% | 130% | 105% | 50% | 140% | | | | |

Comments: When the average of the sample and duplicate results is less than 5x the RDL, the Relative Percent Difference (RPD) will be indicated as Not Applicable (NA).

Certified By:

NPoprikolof

Quality Assurance

CLIENT NAME: GEI CONSULTANTS

PROJECT: M1553 - Eastnor SAMPLING SITE:EASTNOR

AGAT WORK ORDER: 24T220810
ATTENTION TO: Jessica Weller
SAMPLED BY:

| SAMIFEING SITE.EASTNON | SAMPLING SITE: EASTNOR SAMPLED BT. | | | | | | | | | | | | | |
|-----------------------------|------------------------------------|-----------|-----------|-------|-----------------|--------------------|-----|--------------------|----------|----------------------|-------|----------|-------|-----------------|
| | | | Wat | er Ar | nalys | is | | | | | | | | |
| RPT Date: Nov 25, 2024 | | | DUPLICATE | | | REFERENCE MATERIAL | | METHOD BLANK SPIKE | | | MAT | RIX SP | IKE | |
| DADAMETED | Batal San | iple D #4 | D #0 | DDD | Method Blank | Measured | | ptable nits | D | Acceptable Limits | | D | | eptable mits |
| PARAMETER | Batch Gall | Dup #1 | Dup #2 | RPD | | Value | | Upper | Recovery | - | Upper | Recovery | Lower | Upper |
| Eastnor Groundwater Package | 0 | | | | | | | | | | | l. | | |
| Electrical Conductivity | 6323184 63231 | 84 836 | 834 | 0.2% | < 2 | 104% | 80% | 120% | | | | | | |
| рН | 6322928 | 7.67 | 7.80 | 1.7% | NA | 100% | 90% | 110% | | | | | | |
| Alkalinity (as CaCO3) | 6322928 | 412 | 412 | 0.0% | < 5 | 106% | 80% | 120% | | | | | | |
| Chloride | 6323184 63231 | 84 23.1 | 22.9 | 0.6% | < 0.10 | 91% | 70% | 130% | 97% | 80% | 120% | 98% | 70% | 130% |
| Nitrate as N | 6323184 63231 | 84 <0.05 | <0.05 | NA | < 0.05 | 91% | 70% | 130% | 93% | 80% | 120% | 93% | 70% | 130% |
| Nitrite as N | 6323184 63231 | 84 <0.05 | <0.05 | NA | < 0.05 | 91% | 70% | 130% | 88% | 80% | 120% | 96% | 70% | 130% |
| Sulphate | 6323184 63231 | 84 25.6 | 25.5 | 0.5% | < 0.10 | 91% | 70% | 130% | 94% | 80% | 120% | 92% | 70% | 130% |
| Ortho Phosphate as P | 6323184 63231 | 84 <0.10 | < 0.10 | NA | < 0.10 | 93% | 70% | 130% | 101% | 80% | 120% | 98% | 70% | 130% |
| Ammonia as N | 6328086 | < 0.02 | < 0.02 | NA | < 0.02 | 97% | 70% | 130% | 112% | 80% | 120% | 72% | 70% | 130% |
| Total Kjeldahl Nitrogen | 6323085 63230 | 85 0.90 | 0.90 | 0.2% | < 0.10 | 101% | 70% | 130% | 94% | 80% | 120% | 84% | 70% | 130% |
| Dissolved Organic Carbon | 6323085 63230 | 85 13.0 | 13.9 | 6.3% | < 0.5 | 101% | 90% | 110% | 94% | 90% | 110% | NA | 80% | 120% |
| Total Phosphorus | 6323194 63231 | 94 0.50 | 0.53 | 5.8% | < 0.02 | 100% | 70% | 130% | 101% | 80% | 120% | 96% | 70% | 130% |
| Dissolved Calcium | 6330877 | 337 | 314 | 7.3% | < 0.05 | 107% | 70% | 130% | 105% | 80% | 120% | 99% | 70% | 130% |
| Dissolved Magnesium | 6330877 | 122 | 109 | 10.7% | < 0.05 | 107% | 70% | 130% | 106% | 80% | 120% | 96% | 70% | 130% |
| Dissolved Potassium | 6330877 | 8.71 | 8.04 | 8.0% | < 0.50 | 106% | 70% | 130% | 97% | 80% | 120% | 85% | 70% | 130% |
| Dissolved Sodium | 6330877 | 358 | 334 | 7.0% | < 0.05 | 108% | 70% | 130% | 109% | 80% | 120% | 95% | 70% | 130% |
| Dissolved Boron | 6330877 | 0.066 | 0.060 | 8.6% | < 0.010 | 102% | 70% | 130% | 111% | 80% | 120% | 109% | 70% | 130% |
| Dissolved Iron | 6330877 | 0.085 | 0.071 | NA | < 0.010 | 98% | 70% | 130% | 98% | 80% | 120% | 108% | 70% | 130% |
| Dissolved Manganese | 6330877 | 0.554 | 0.489 | 12.5% | < 0.002 | 98% | 70% | 130% | 97% | 80% | 120% | 99% | 70% | 130% |
| Eastnor Comprehensive Grour | ndwater Package | | | | | | | | | | | | | |
| Electrical Conductivity | 6323184 63231 | 84 836 | 734 | 13.0% | < 2 | 104% | 80% | 120% | | | | | | |
| рН | 6323184 63231 | 84 7.77 | 7.81 | 0.5% | NA | 100% | 90% | 110% | | | | | | |
| Total Dissolved Solids | 6322927 | 1220 | 1220 | 0.0% | < 10 | 98% | 80% | 120% | | | | | | |
| Alkalinity (as CaCO3) | 6323184 63231 | 84 512 | 497 | 3.0% | < 5 | 116% | 80% | 120% | | | | | | |
| Chloride | 6323184 63231 | 84 23.1 | 22.9 | 0.9% | < 0.10 | 91% | 70% | 130% | 97% | 80% | 120% | 98% | 70% | 130% |
| Nitrate as N | 6323184 63231 | 84 <0.05 | <0.05 | NA | < 0.05 | 91% | 70% | 130% | 93% | 80% | 120% | 93% | 70% | 130% |
| Nitrite as N | 6323184 63231 | 84 <0.05 | < 0.05 | NA | < 0.05 | 91% | 70% | 130% | 88% | 80% | 120% | 96% | 70% | 130% |
| Sulphate | 6323184 63231 | 84 25.6 | 25.5 | 0.4% | < 0.10 | 91% | 70% | 130% | 94% | 80% | 120% | 92% | 70% | 130% |
| Chemical Oxygen Demand | 6318548 | 55 | 56 | 1.8% | < 5 | 100% | 80% | 120% | 97% | 90% | 110% | NA | 70% | 130% |
| Ammonia as N | 6323190 63231 | 90 <0.02 | <0.02 | NA | < 0.02 | 97% | 70% | 130% | 112% | 80% | 120% | 94% | 70% | 130% |
| Total Kjeldahl Nitrogen | 6323085 63230 | 85 0.90 | 0.90 | 0.0% | < 0.10 | 101% | 70% | 130% | 94% | 80% | 120% | 84% | 70% | 130% |
| Dissolved Organic Carbon | 6323085 63230 | 85 13.0 | 13.9 | 6.7% | < 0.5 | 101% | 90% | 110% | 94% | 90% | 110% | NA | 80% | 120% |
| Total Phosphorus | 6323194 63231 | 94 0.50 | 0.53 | 5.8% | < 0.02 | 96% | 70% | 130% | 98% | 80% | 120% | 96% | 70% | 130% |
| Dissolved Calcium | 6326578 | 34.8 | 35.5 | 2.0% | < 0.05 | 95% | 70% | 130% | 93% | 80% | 120% | 87% | 70% | 130% |
| Dissolved Magnesium | 6326578 | 1.07 | 1.19 | 10.6% | < 0.05 | 94% | 70% | 130% | 95% | 80% | 120% | 88% | 70% | 130% |
| Dissolved Potassium | 6326578 | <0.50 | <0.50 | NA | < 0.50 | 88% | 70% | 130% | 89% | 80% | 120% | 82% | 70% | 130% |
| Dissolved Sodium | 6326578 | 1.17 | 1.20 | 2.5% | < 0.05 | 97% | 70% | 130% | 95% | 80% | 120% | 89% | 70% | 130% |
| Dissolved Arsenic | 6326578 | < 0.001 | <0.001 | NA | < 0.001 | 96% | 70% | 130% | 102% | 80% | 120% | 105% | 70% | 130% |
| Dissolved Barium | 6326578 | 0.004 | 0.004 | NA | < 0.002 | 94% | 70% | 130% | 94% | 80% | 120% | 91% | 70% | 130% |

AGAT QUALITY ASSURANCE REPORT (V1)

Page 9 of 14

AGAT Laboratories is accredited to ISO/IEC 17025 by the Canadian Association for Laboratory Accreditation Inc. (CALA) and/or Standards Council of Canada (SCC) for specific tests listed on the scope of accreditation. AGAT Laboratories (Mississauga) is also accredited by the Canadian Association for Laboratory Accreditation Inc. (CALA) for specific drinking water tests. Accreditations are location and parameter specific. A complete listing of parameters for each location is available from www.cala.ca and/or www.scc.ca. The tests in this report may not necessarily be included in the scope of accreditation. RPDs calculated using raw data. The RPD may not be reflective of duplicate values shown, due to rounding of final results.



Quality Assurance

CLIENT NAME: GEI CONSULTANTS

PROJECT: M1553 - Eastnor SAMPLING SITE:EASTNOR

AGAT WORK ORDER: 24T220810
ATTENTION TO: Jessica Weller

SAMPLED BY:

| | | | | | | | | | | (C) (C) | | | | | | | | | |
|---|---------|--------|---------|----------|-------|-----------------|----------|-------|----------------|----------|----------|----------|----------|----------|----------------------|--|----------|----------------------|--|
| Water Analysis (Continued) | | | | | | | | | | | | | | | | | | | |
| RPT Date: Nov 25, 2024 DUPLICATE REFERENCE MATERIAL METHOD BLANK SPIKE MATRIX SPI | | | | | | | | | | KE | | | | | | | | | |
| PARAMETER | Batch | Sample | Dup #1 | Dup #2 | RPD | Method Blank | Measured | | ptable nits | Recovery | Recovery | Recovery | Recovery | Recovery | Acceptable Limits | | Recovery | Acceptable Limits | |
| | | ld | | | | | Value | Lower | Upper | | Lower | Upper | | Lower | Upper | | | | |
| Dissolved Boron | 6326578 | | <0.010 | <0.010 | NA | < 0.010 | 105% | 70% | 130% | 105% | 80% | 120% | 103% | 70% | 130% | | | | |
| Dissolved Cadmium | 6326578 | | <0.0001 | <0.0001 | NA | < 0.0001 | 100% | 70% | 130% | 99% | 80% | 120% | 99% | 70% | 130% | | | | |
| Dissolved Chromium | 6326578 | | < 0.002 | < 0.002 | NA | < 0.002 | 104% | 70% | 130% | 106% | 80% | 120% | 103% | 70% | 130% | | | | |
| Dissolved Copper | 6326578 | | 0.007 | 0.008 | 13.3% | < 0.001 | 104% | 70% | 130% | 102% | 80% | 120% | 102% | 70% | 130% | | | | |
| Dissolved Iron | 6326578 | | < 0.020 | < 0.020 | NA | < 0.010 | 101% | 70% | 130% | 109% | 80% | 120% | 99% | 70% | 130% | | | | |
| Dissolved Lead | 6326578 | | <0.0005 | <0.0005 | NA | < 0.0005 | 96% | 70% | 130% | 90% | 80% | 120% | 88% | 70% | 130% | | | | |
| Dissolved Manganese | 6326578 | | 0.006 | 0.006 | NA | < 0.002 | 103% | 70% | 130% | 105% | 80% | 120% | 101% | 70% | 130% | | | | |
| Dissolved Mercury | 6324169 | | <0.0001 | < 0.0001 | NA | < 0.0001 | 103% | 70% | 130% | 103% | 80% | 120% | 93% | 70% | 130% | | | | |
| Dissolved Zinc | 6326578 | | < 0.005 | < 0.005 | NA | < 0.005 | 102% | 70% | 130% | 100% | 80% | 120% | 106% | 70% | 130% | | | | |

Comments: NA signifies Not Applicable.

Duplicate NA: results are under 5X the RDL and will not be calculated.

Matrix spike NA: Spike level < native concentration. Matrix spike acceptance limits do not apply and are not calculated.

Certified By:

Iris Verastegui



Method Summary

CLIENT NAME: GEI CONSULTANTS

PROJECT: M1553 - Eastnor

AGAT WORK ORDER: 24T220810 **ATTENTION TO: Jessica Weller**

| SAMPLING SITE:EASTNOR | | SAMPLED BY: | | | | | | |
|-------------------------|--------------|--|----------------------|--|--|--|--|--|
| PARAMETER | AGAT S.O.P | LITERATURE REFERENCE | ANALYTICAL TECHNIQUE | | | | | |
| Trace Organics Analysis | | | | | | | | |
| Benzene | VOL-91-5001 | modified from EPA SW-846 5030C & 8260D | (P&T)GC/MS | | | | | |
| Toluene | VOL-91-5001 | modified from EPA SW-846 5030C & 8260D | (P&T)GC/MS | | | | | |
| Ethylbenzene | VOL-91-5001 | modified from EPA SW-846 5030C & 8260D | (P&T)GC/MS | | | | | |
| m & p-Xylene | VOL-91-5001 | modified from EPA SW-846 5030C & 8260D | (P&T)GC/MS | | | | | |
| o-Xylene | VOL-91-5001 | modified from EPA SW-846 5030C & 8260D | (P&T)GC/MS | | | | | |
| Xylenes (Total) | VOL-91-5001 | modified from EPA SW-846 5030C & 8260D | (P&T)GC/MS | | | | | |
| Toluene-d8 | VOL-91-5001 | modified from EPA 5030B & EPA 8260D | (P&T)GC/MS | | | | | |
| 4-Bromofluorobenzene | VOL-91- 5001 | modified from EPA 5030B & EPA 8260D | (P&T)GC/MS | | | | | |

Method Summary

CLIENT NAME: GEI CONSULTANTS

PROJECT: M1553 - Eastnor SAMPLING SITE:EASTNOR

AGAT WORK ORDER: 24T220810 ATTENTION TO: Jessica Weller

SAMPLED BY:

| PARAMETER | AGAT S.O.P | LITERATURE REFERENCE | ANALYTICAL TECHNIQUE |
|----------------------------------|--------------|---|--------------------------|
| Water Analysis | AOAT 0.0.1 | EITERATORE REI ERENGE | ANALI HOAL TECHNIQUE |
| Electrical Conductivity | INOR-93-6000 | SM 2510 B | PC TITRATE |
| pH | INOR-93-6000 | modified from SM 4500-H+ B | PC TITRATE |
| Total Dissolved Solids | INOR-93-6028 | modified from EPA 1684,ON MOECC E3139,SM 2540B,C,D | BALANCE |
| Alkalinity (as CaCO3) | INOR-93-6000 | Modified from SM 2320 B | PC TITRATE |
| Chloride | INOR-93-6004 | modified from SM 4110 B | ION CHROMATOGRAPH |
| Nitrate as N | INOR-93-6004 | modified from SM 4110 B | ION CHROMATOGRAPH |
| Nitrite as N | INOR-93-6004 | modified from SM 4110 B | ION CHROMATOGRAPH |
| Sulphate | INOR-93-6004 | modified from SM 4110 B | ION CHROMATOGRAPH |
| Chemical Oxygen Demand | INOR-93-6042 | modified from SM 5220 A and SM 5220 D | SPECTROPHOTOMETER |
| Ammonia as N | INOR-93-6059 | modified from SM 4500-NH3 H | LACHAT FIA |
| Total Kjeldahl Nitrogen | INOR-93-6048 | modified from EPA 351.2 and SM 4500-NORG D | LACHAT FIA |
| Dissolved Organic Carbon | INOR-93-6049 | modified from SM 5310 B | SHIMADZU CARBON ANALYZER |
| Total Phosphorus | INOR-93-6057 | modified from LACHAT 10-115-01-3A | LACHAT FIA |
| Dissolved Calcium | MET-93-6103 | modified from EPA 200.8 and EPA 3005A | ICP/MS |
| Dissolved Magnesium | MET-93-6103 | modified from EPA 200.8, 3005A, 3010A & 6020B | ICP/MS |
| Dissolved Potassium | MET-93-6103 | modified from EPA 200.8 and EPA 3005A | ICP/MS |
| Dissolved Sodium | MET-93-6103 | modified from EPA 200.8 and EPA 3005A | ICP/MS |
| Dissolved Arsenic | MET-93-6103 | modified from EPA 200.8 and EPA 3005A | ICP-MS |
| Dissolved Barium | MET-93-6103 | modified from EPA 200.8 and EPA 3005A | ICP-MS |
| Dissolved Boron | MET-93-6103 | modified from EPA 200.8 and EPA 3005A | ICP-MS |
| Dissolved Cadmium | MET-93-6103 | modified from EPA 200.8 and EPA 3005A | ICP-MS |
| Dissolved Chromium | MET-93-6103 | modified from EPA 200.8 and EPA 3005A | ICP-MS |
| Dissolved Copper | MET-93-6103 | modified from EPA 200.8 and EPA 3005A | ICP-MS |
| Dissolved Iron | MET-93-6103 | modified from EPA 200.8 and EPA 3005A | ICP-MS |
| Dissolved Lead | MET-93-6103 | modified from EPA 200.8 and EPA 3005A | ICP-MS |
| Dissolved Manganese | MET-93-6103 | modified from EPA 200.8 and EPA 3005A | ICP-MS |
| Dissolved Mercury | MET-93-6100 | modified from EPA 245.2 and SM 311. | ² CVAAS |
| Dissolved Zinc | MET-93-6103 | modified from EPA 200.8 and EPA 3005A | ICP-MS |
| Lab Filtration DOC | SR-78-9001 | | FILTRATION |
| Lab Filtration Metals | SR-78-9001 | | FILTRATION |
| Lab Filtration mercury | SR-78-9001 | | FILTRATION |
| Ortho Phosphate as P | INOR-93-6004 | modified from SM 4110 B | ION CHROMATOGRAPH |
| Hardness (as CaCO3) (Calculated) | MET-93-6105 | modified from EPA SW-846 6010C & 200.7 & SM 2340 B | CALCULATION |